

APPENDIX XI: RIG SPECIFICATIONS

Rig Inventory for RIG # 30

DRAWWORKS	:	Ideco Hydrair H-725-D double drum with V-80 Parmac hydromatic brake, Martin Decker satellite automatic drilling control. Max. single line pull - 50,000 lbs. Main drum grooved for 1-1/8" drilling line.
SUBSTRUCTURE	:	One piece substructure 14' high x 13'6" wide x 50' long with 12' BOP clearance. Setback area loading: 250,000 lbs Casing area loading: 275,000 lbs
ENGINES	:	Four (4) Caterpillar Model 3412 PCTA diesel engines.
BRAKE	:	V-80 Parmac hydromatic brake,
MAST	:	Dreco Model #: M12713-510 Floor Mounted Cantilever Mast designed in accordance with API Specification 4E Drilling & Well Servicing Structures. Hook load Gross Nominal Capacity - 510,000 lbs with:- 10 lines strung - 365,000 lbs 8 lines strung - 340,000 lbs Clear working height of 127'. Base width of 13'6". Adjustable racking board with capacity for i) 108 stands of 4.½" drill pipe, ii) 10 stands of 6.½" drill collars, iii) 3 stands of 8" drill collars Designed to withstand an API windload of 84 mph with pipe racked and 100 mph with no pipe racked.
CATHEADS	:	One (1) Foster Model 37 make-up spinning cathead mounted on drillers side. One (1) Foster Model 24 break-out cathead mounted off drillers side.
TRAVELLING BLOCK/HOOK	:	One (1) 667 Crosby McKissick 250 ton combination block hook Web Wilson. 250 ton Hydra hook Unit 5 - 36" sheaves.
WINCHES	:	One (1) Ingersol Rand HU-40 with 5/8" wireline. Capacity 2,000 lb. One (1) ANSI B30.7 with 3/8" wire capacity 4000lbs @ 70 fpm
SWIVEL	:	One (1) Oilwell PC-300 ton swivel
RIG LIGHTING	:	Explosive proof fluorescent. As per approved State Specifications.
KELLY DRIVE	:	One (1) 27 HDP Varco kelly drive bushing.
MUD PUMPS	:	Two (2) Gardner Denver mud pumps Model PZH-8 each driven by 750 HP EMD D-79 motors. 8" stroke with liner size 6" through to 5". 6" liner maximum pressure 2387 psi 5.1/2" liner maximum pressure 2841 psi 5" liner maximum pressure 3437 psi 6" liner maximum volume 412 gpm 5.1/2" liner maximum volume 345 gpm 5" liner maximum volume 280 gpm
MIXING PUMP	:	Two (2) Mission Magnum 5" x 6" x 14" centrifugal pump complete with 50 HP, 600 Volt, 60 Hz, 3 phase explosion proof electric motors.

MUD AGITATORS	:	Five (5) Geolograph/Pioneer 40TD - 15" 'Pitbull' mud agitators with 15 HP, 60 Volt, 60 HZ, 3 phase electric motors.
LINEAR MOTION SHALE SHAKERS	:	Two (2) DFE SCR-01 Linear motion shale shakers.
DEGASSER	:	48" Dia Poor Boy Degasser
DESILTER	:	One (1)DFE - Harrisburg style 12 cone desilter 12 x 5" cones. Approximate output of 960 gpm. Driven by Mission Magnum 5" x 6" x 11" centrifugal pump complete with 50 hp 600 volt 60 Hz 3 phase explosion proof motor.
GENERATORS	:	Four (4) Brown Boveri 600 volt, 600 Kw, 750 kva , 3 phase, 60 HZ AC generators. Powered by four (4) Cat 3412 PCTA diesel engines.
BOP's & ACCUMULATOR	:	One (1) Wagner Model 20-160 3 BND 160 gallon accumulator consisting of: Sixteen (16) 11 gallon bladder type bottles One (1) 20 HP electric driven triplex pump 600 volts, 60 HZ, 3 phase motor and controls. One (1) Wagner Model A 60 auxiliary air pump 4.5 gals/minute.
BOP's & ACCUMULATOR (Cont'd)	:	One (1) Wagner Model UM2SCB5S mounted hydraulic control panel with five (5) 1" stainless steel fitted selector valves and two (2) stripping controls and pressure reducing valves. Three (3) 4" hydraulic readout gauges:- one for annular pressure- one for accumulator pressure one for manifold pressure. One (1) Stewart & Stevenson 5 station remote drillers control with air cable umbilical with three pressure gauges, increase and decrease control for annular pressure. One (1) Shaffer 13.5/8" x 3,000 psi spherical annular BOP, One (1) Shaffer 13.5/8" x 5,000 psi LWS studded, double gate autolock B.O.P.
KELLY COCK (UPPER)	:	Two (2) Upper Kelly Cock 7.3/4"OD with 6.5/8" API connections (1 x M&M, 1 x Hydril).
KELLY COCK (LOWER)	:	Three (3) M&M Lower Kelly Cocks 6.½" OD with 4" IF connections
DRILL PIPE SAFETY VALVE	:	One (1) Hydril 6.½" stabbing valve (4" IF). One (1) Gray inside BOP with 4.3/4" OD and 2.1/4" ID with 3.1/2" IF connections c/w releasing tool and thread protectors.
AIR COMPRESSORS AND RECEIVERS	:	Two (2) LeRoi Dresser Model 660A air compressor packages c/w 10 HP motors rated at 600 Volts, 60 HZ, 3 phase. Receivers each 120 gallon capacity and fitted with relief valves.
POWER TONGS	:	One (1) Farr 13.5/8" - 5.½" hydraulic casing tongs c/w hydraulic power pack and hoses and torque gauge assembly. One (1) Foster hydraulic kelly spinner with 6.5/8" LH connection.
TORQUE WRENCH	:	Yutani c/w drive sockets 1 1/8" through to 2 3/8"
SPOOLS	:	One (1) set double studded adaptor flanges to mate 13.5/8" 5,000 psi. API BOP flange to following wellhead flange 13.5/8" x 3,000 series, 11" x 3,000 series, 11" x 5,000 series 7.1/16" x 3,000 series, 7.1/16" x 5,000 series 4 1/16" 5000 x 3 1/16" 5000 3 1/16" 5000 x 2 1/16" 5000

SPOOLS (Cont'd)	:	1 double studded adaptor flange 4 1/16" 5K x 3 1/16" 5K 1 double studded adaptor flange 3 1/16" 5K x 2 1/16" 5K 1 only 14" - BOP mud cross (drilling spool) 13.5/8" 5,000 x 13.5/8" 5,000 BX160. with 2 x 3 1/16" 5K outlets. 1 only BOP spacer spool 13 5/8" 3,000 x 13 5/8" 3,000 1 only BOP spacer .spool 11" 3,000 x 13.5/8" 5,000 .
ROTARY TABLE	:	One (1) Oilwell A 20.1/2" rotary table torque tube driven from drawworks complete with Varco MASTER bushings and Insert Bowls.
MUD TANKS	:	SHAKER Active No 1. 277 BBL Desilter 73 BBL Sand Trap 50 BBL Trip Tank 29 BBL Total <u>429 BBL</u> SUCTION Active No 2 174 BBL Pre-Mix 146 BBL Pill Tank 63 BBL Total <u>383 BBL</u>
TRIP TANK	:	Trip Tank <u>29 BBL</u> One (1) Mission Magnum 2" x 3" centrifugal pump complete with 20 HP, 600 Volts, 60 HZ, 3 phase explosion proof motors
KILL LINE VALVE	:	2 x 3 1/8" Cameron FL 5K gate valves
CHOKE LINE VALVES	:	1 x 4 1/16 Cameron FC 5K hydraulic operated gate valve 1 x 4 1/16 5K manual gate valve
CHOKE MANIFOLD	:	One (1) McEvoy choke and kill manifold 3" 5,000 psi with hydraulic Swaco "super" choke.
DRILL PIPE	:	240 joints (2270 m) - 3.1/2" 13.30lb/ft drill pipe Grade 'G' 105 with 3 1/2" IF conn
PUP JOINTS	:	One (1) - 10'(3.65 m) 3.1/2" OD Grade 'G' with 3.1/2" IF conn
HEVI-WATE DRILL PIPE	:	6 joints of 3.1/2" H.W.D.P. with 3.1/2" IF conn
DRILL COLLARS	:	12 x 6.1/2" OD drill collars (113 m) with 4" IF conn 24 x 4 3/4" O.D. drill collars (227 m) with 3.1/2" IF conn 1 x 4.3/4" OD Pony Drill Collar
KELLIES	:	Two (2) Square Kelly drive 4.1/4" x 40' complete with Scabbard and 55 ft x 3 1/2" kelly hose
FISHING TOOLS	:	One (1) only 8.1/8" Bowen series 150 FS overshot One (1) 5.3/4" SH Bowen 150 Overshot c/w grapples and packoffs to fish contractors downhole equipment. One (1) only Reverse circulating junk basket 4" IF box One (1) only 6.1/2" OD Griffith Fishing Jars One (1) only 4 3/4" O.D. Bowen Type "Z" Fishing Jar One (1) only Bumper Sub 6.1/2" OD 4" IF pin & box. One (1) 5" R.C.J.B. One (1) 5" Junk Sub with 4.3/4" OD x 1.1/2" ID.
WIRELINE SURVEY UNIT	:	Gearmatic hydraulic drive Model 5 c/w .092" line

SUBSTITUTES	:	<p>Two (2) Bit Sub - 7.5/8" reg x 6.5/8" reg double box. Two (2) Bit Subs - 6.5/8" reg double box. Two (2) Bit Sub - 6.5/8" reg box. x 4½" IF box Two (2) Bit Subs - 4½" reg x 4" IF double box. Two (2) 4.3/4" bit subs (36" long) with 3.1/2" IF box x 3.1/2" reg box bored for float. One (1) Float Sub 6.5/8" reg box (FC) x 6.5/8" reg pin Two (2) XO Sub - 4" IF box x 4½" IF pin. Two (2) XO Sub - 4½" IF box x 4." IF pin. One (1) XO Sub - 4½" reg x 4" IF double pin. Two (2) XO Sub - 6.5/8" reg pin x 4" IF box. One (1) Junk Sub - 6.5/8" reg pin x 6.5/8" reg box One (1) Junk Sub - 4½" reg box x 4½" reg pin. One (1) XO Sub - 4½" IF box x 4" IF box. Two (2) Kelly Saver Subs c/w rubber 4" IF pin & box. Two (2) Kelly Saver Subs 4" IF pin & box One (1) Kelly Saver Subs 4½" IF pin & box. Two (2) 4 IF box x 3.1/2" IF pin Saver Subs. One (1) Circulating Subs - 4" IF x 2" 1502 hammer union. One (1) Circulating Subs - 4" IF x 2" 602 hammer union. Eleven (11) Lifting Subs - 18" Taper 4½" pick up neck and 4" IF pin. Eight (8) Lift Subs with 3.1/2" OD D.P. neck and 3.1/2" IF pin connections.</p>
HANDLING TOOLS	:	<p>2 only 4½" BJ 250 ton 18 degree taper D/P elevators. 1 only 3½" BJ 200 ton 18 degree taper D/P elevators. 1 only 3.1/2" BJ type MGG 18° centre latch Elevators. 1 only 4½" Varco SDXL D/P slips. 1 only 4½" Varco SDML D/P slips 2 only 8" - 6½" DCS-R drill collar slips. 1 only 3.1/2" Varco SDML Slips 1 only 4.3/4" Varco DCS-S Drill Collar Slips</p>
CASING RUNNING TOOLS	:	<p>1 only 13.3/8" Webb Wilson 150 ton side door elevator. 1 only 13.3/8" single joint P.U. elevators. 1 only 9.5/8" Webb Wilson 150 ton side door elevators. 1 only 9.5/8 single joint P.U. elevator. 1 only 7" BJ 150 ton side door elevators. 1 only 7" single joint P.U. elevators. 1 only 5½" BJ 200 ton S11 1 only 2.7/8" BJ 100 ton tubing elevator. 1 only 2.3/8" BJ 100 ton tubing elevator. (all P.U. elevators c/w slings & swivel) 1 only 13.3/8" Varco CMS-XL casing slips 1 only 9.5/8" Varco CMS-XL casing slips. 1 only 7" Varco CMS-XL casing slips. 1 only 3.1/2" Varco SDML tubing slips.</p>
CASING / TUBING DRIFTS	:	<p>9 5/8, 7", 5 ½", 3 ½"</p>
THREAD PROTECTORS	:	<p>9 5/8, 7".</p>
KELLY SPINNER	:	<p>One (1) Foster hydraulic kelly spinner with 6.5/8" LH connection.</p>
PIPE SPINNER	:	<p>One (1) International 850H hydraulic pipe spinner</p>
WELDING EQUIPMENT	:	<p>1 - Miller 400 amp welding machine. 1 - oxy acetylene set.</p>
DOGHOUSE	:	<p>1 Doghouse 5m x 2.4m x 2.3m</p>
GENERATOR HOUSE	:	<p>Ross Hill SCR</p>

UTILITY HOUSE	:	1 Utility and Mechanics House
CATWALKS	:	2 catwalks total 18.6m long x 1.6m wide x 1.08m high
PIPE RACKS	:	8 - 9m tumble racks.
DAY FUEL TANK	:	1 only 19,000 ltrs
WATER/FUEL TANK	:	WATER 1 only 320 bbls. 1 only brake cooling tank 80 bbl FUEL 1 only 27,500 litres
OIL STORAGE	:	drums
DRILLING RATE RECORDER	:	1 only 6 pen Pioneer Geograph drill sentry recorder to record: weight (D) penetration (feet) pump pressure (0-6,000 psi) electric rotary torque rotary speed (rpm) pump spm (with selector switch)
DEVIATION RECORDER	:	1 set Totco 'Double Shot' deviation instrument 0□-8□.
INSTRUMENTS & INDICATORS	:	1 only Martin Decker Sealite. 1 only Martin Decker Deadline type. 1 only drillers console including the following equipment. Martin Decker Weight Indicator type'D' Electric rotary torque gauge. MD Totco Mud Watch Instrumentation c/w display and alarms. Rotary rpm gauge
MUD TESTING	:	1 set Baroid mud testing laboratory (standard kit
RATHOLE DRILLER	:	One (1) fabricated rotary table chain driven.
MUD SAVER	:	Okeh unit
CELLAR PUMP	:	Cellar jet from No 1 pump
WATER PUMP	:	Three (3) Mission Magnum 2" x 3" centrifugal pumps c/w 20 HP, 600 Volts, 60 HZ, 3 phase explosion proof motors
FIRE EXTINGUISHERS	:	Dry Chemical Rig 22 Camp 20 CO2 Rig 3 Camp 0 Foam Rig 1 Camp 1
PIPE BINS	:	5 units
CUP TESTER	:	Two (2) Grey Cup Tester c/w test cups for 9.5/8" & 13.3/8".
DRILLING LINE	:	5,000' 1.1/8" - E.I.P.S

TRANSPORT EQUIPMENT AND MOTOR VEHICLES

One (1) International 530 Forklift
One (1) Tray Top Utility
One (1) Crew Bus

CAMP EQUIPMENT

Four (4) x 8-Man Bunkhouses (12 man emergency)
One (1) x Recreation/Canteen unit
One (1) x Ablution/Laundry/Freezer unit
One (1) x Kitchen/Cooler/Diner unit
One (1) x Toolpushers unit
One (1) x Meeting / Smoko unit
One (1) x Combined Water/Fuel Tank unit
Two (2) x CAT 3304PC generator sets each 106 kVa, 86 KW, 50 HZ.

NOTE: At Contractor's discretion any of the foregoing items may be replaced by equipment of equivalent or greater capacity.