**50000** 

WCR

- Santos -

PETROLEUM DIVISION

GORDON 1

Well Completion Report

WCR GORDON-1 WII91

Santos

PEP119, OTWAY BASIN-VICTORIA A.C.N. 007. 650 923.-

WCF.

(iordon)

(WI191)

# TMOC EXPLORATION LTD - BASIN OIL N.L.

## GORDON-1 WELL COMPLETION REPORT

# COMPILED FOR TMOC PTY LTD

Prepared By: J. A. WATT D.HORNER JUNE, 1997

## **GORDON-1**

## TABLE OF CONTENTS

CONTENTS			PAGE
LOCATION MAP			
WELL CARD			
WELL HISTORY	1. 2. 3.	General Data Drilling Data Drilling Summary	1 1 2
GEOLOGY	1. 2. 3. 4. 5.	Pre-Drilling Summary Drilling Rationale Results of Drilling (a) Stratigraphy (b) Stratigraphic Prognosis (c) Hydrocarbon Summary Summary References	5 7 7 14 15 17
APPENDICES	I II III IV V VI VII VIII IX X XI XII	Lithological Descriptions Part a: Cuttings & Part b: Sidewall Cores Oil Show Evaluation Reports Log Evaluation/Analysis Drill Stem Test Data Hydrocarbon Analysis Water Analysis Palynological Analysis Geothermal Gradient Well Location Survey Drilling, Casing, & Abandonment Summary Rig Specifications FMI Interpretation	
ENCLOSURES	I II	1:200m Composite Log 1:500m Mudlog	

**LOCATION MAP** 






FIGURE 1





WELL CARD

			T				
WELL: Gordon-1	WELL CATEGO	ORY: Wildcat (WCNF)	SPUD: 15/04/97, REACHED: 27/0		TD		
	WELL INTENT	: Gas in the McEachern Sandstone	RIG RELEASE		Ohrs CMPLT:		
		RIG: ODE Rig					
<b>LAT</b> : 37 deg 35' 14.5" S		<b>IG</b> : 141 deg 17' 38.4" E	STATUS: Plugg	ed and Suspende	ed well (PSO)		
SEISMIC STATION: C	Offline 36m NW of Cl	DP827 (SP515) line OMN 93-08	REMARKS: Su	spended for poss	sible re-entry.		
			Sidetrack for potential oil in fractured basement.				
ELEVATION GND: 1	24.89m amsl	RT: 129.59m					
BLOCK/LICENCE: P	EP 119, Onshore Otw	vay Basin, Victoria					
<b>TD</b> : 2303m (Logr Ex	xt); 2505m (D	Orlr)					
PBTD	M (Logr)	M (Drlr)	CASING SIZE	SHOE DEPTH	ТҮРЕ		
TYPE STRUCTURE: T			16"	10m	Conductor		
TYPE COMPLETION:	Plugged and Suspen	nded	9.625" (244mm)	653.3m (D)	K55 - 36lb		
ZONE(S): Basement				652m (L)			

AGE	FORMATION OR ZONE TOPS	DEPT	'H (M)	THICKNESS	HIGH (H)	
		LOGGERS	SUBSEA	(m)	LOW (L)	
	Tertiary (undifferentiated)	4.7 sfc	+124.9	35		
	Otway Group					
Early Cretaceous (Aptian-Albian)	Eumeralla Formation	40.0	+89.6	1110	2.6 (H)	
	Crayfish Group					
E. Cret. (Valanginian- Hauterivian)	Laira Formation	1150	-1020.4	367	3.4 (L)	
E. Cret. (Berriasian-Valanginian)	Pretty Hill Formation	1517.0	-1387.4	601	143.6 (H)	
	McEachern Sandstone	Not	Present			
L. JurE.Cret.(Kimmeridgian- Berriasian)	Casterton Formation	2118.0	-1988.4	243	269.6 (H)	
Palaeozoic	Basement	2361.0	-2231.4	130+	89.6 (H)	
	T.D.	2503.0	-2373.4		7.7 (L)	
*(ages from APG Consultants, 1997)						

LOG INTER		ON (Interval Aver			F	PERFORA	TIONS (4 shots/	ft)		
Ø %	SW %	INTERVAL(ft)	Ø %	SW %	FORM	MATION	II	INTERVAL		
					None					
							CORES			
					FORM	NO.	INTERVAL	CUT	REC	
					None					

LOG	SUITE/	INTERVAL	BHT/TIME/REMARKS	LOG	SUITE/	INTERVAL	BHT/TIME/REMARKS
	RUN	(M)	Degrees C		RUN	(M)	Degrees C
SP-AR	1/1	2473-652		DT	1/1	2485-652	
ECGR	1/1	2490-560	97°C/8Hrs 17 Mins	DTL	1/1	"	
HCAL	1/1	2496-652	"	DTLN	1/1	"	
RXO8	1/1	44	"	DTLF	1/1	46	
HRLD	1/1	2499-652	66	A/S	1/1	2485-2100	
HRLS	1/1	<b>66</b>	ч	CST	1/2		99°C/16Hrs 23Mins, Cut 60, Rec 56 (1 lost, 3 empty) 29/04/97
TNPH	1/1	2492-652	"	FMI	1/3	2498-2170.4	96°C/6 Hrs 30Mins, 29/04/97
RHO8	1/1	2496-652	44				

	FORMATION TESTS												
NO.	INTERVAL (m)	FORMATION	FLOW (mins)	SHUT IN (mins)	BOTTOM GAUGE IP/FP (psia)	SIP	MAX SURF PRESS (psia)	FLUID TO SURF (mins)	TC/ BC	REMARKS			
1 CS	2390-2461 (D) 2388-2459 (L)	Basement	15	42	115.1 181 220.1	2054			0.5"/ 0.75"	Packer failed 17 mins into 2 <sup>nd</sup> flow. NFTS. Rec 6bbls oil cut rathole mud. API 38° @ 60° F., Pr Pt 36° C.			
2 CS	2389.5-2461 (D) 2387.5-2459 (L)	Basement	216	154	158.2 474.7	2773			0.5"/ 0.75"	Packers failed after 216 mins. Rec 1bbl oil cut mud + 7bbls muddy water.			

#### **SUMMARY:**

The Gordon-1 well was drilled during the months April and May, 1997, in PEP 119, situated in southwestern Victoria, approximately 25km east of the border of South Australia. The well was proposed as an exploration well for gas, in the Penola Trough, within the Victorian Otway Basin. Gordon-1 lies about 5km west of the town of Casterton, 9.5km SSE of McEachern-1, 30km E of the Katnook gas pipeline and approximately 50km W of the Victorian gas pipeline at Hamilton.

The Gordon structure is a tilted fault block located on the northeastern flank of the Penola Trough. The primary objective was the McEachern Sandstone, a member of the Pretty Hill Formation, within the Crayfish Group, overlying the Casterton Formation. The McEachern Sandstone was not recognized in the well, presumably pinched out, and the well bottomed in metasiltstone basement at 2505mKB. There were shows both in Early Cretaceous and Late Jurassic sediments, as well as in the Palaeozoic basement. Within the Pretty Hill Sandstone, at 1642-44m, and 1771-75m there were trace residual oil shows, and in the basal section of the Casterton Formation at 2345-63m there were gas shows associated with coals. Underlying the Casterton, in light to dark greenish-grey metasiltstones at 2400-60m, trace to fair oil shows, with moderately bright to bright yellowish-white fluorescence, a milky white crush cut, and a thin ring residue were recorded, associated with fractures in the Palaeozoic basement. A Formation Microscanner Imager Log (FMI) was run to elucidate the fracture system, and it indicated a high density of open fractures across the interval containing the oil shows.

Two drill stem tests were conducted to evaluate the fractured interval intersected at the top of the basement. The first, DST #1, was conducted as a conventional straddle test between 2390-2461m. It lost its packer seat 17 minutes into the second flow, but recovered 6 bbls of oil cut rathole mud. The second test, DST #2, was run over the same interval, however, it too had a packer failure after 216 minutes. Recovery was 1 bbl of oil cut water and 15 bbls of muddy water. The flow rate was calculated to be 47 bbls a day, and the API gravity of the oil was analyzed to be 38° at 60° F.

The Gordon-1 well was plugged and suspended for possible re-entry and the ODE Rig 30 was released on May 3<sup>rd</sup>, 1997 at 22h00.

AUTHOR: D. Horner, A. Pietsch

**WELL HISTORY** 

#### 1. **GENERAL DATA**

Well Name:

Gordon-1

Well Classification:

Exploration (WCNF)

Interest Holders:

TMOC Pty Ltd

60.00%

Basin Oil NL

40.00%

Participating

Interests:

TMOC Pty Ltd

60.00%

Basin Oil NL

40.00%

Operator:

**SANTOS** 

Block/Licence:

PEP 119, Onshore Otway Basin, Victoria

Surface Location:

37° 35' 14.5" South

Longitude: 141° 17' 38.4" East

Surveyed Elevation:

Ground Level: 124.89m

Rotary Table: 129.59m

Seismic Survey:

Kanawinka Seismic Survey

Seismic Location:

Offline 36m NW of CDP827 (SP515) line OMN 93-08

Total Depth:

Driller:

2305m

Logger: 2303m

Completion:

Not Completed

PBTD:

Well plugged and suspended.

Status:

Suspended Oil Well.

#### 2. **DRILLING DATA**

Date Drilling Commenced:

2300 hours, 15th April, 1997

Date Drilling Completed:

2130 hours, 27th April, 1997

Date Rig Released:

2200 hours, 3<sup>rd</sup> May, 1997

Contractor:

Oil Drilling and Exploration Pty. Ltd. (ODE)

Rig:

ODE Rig #30

Rig Specifications:

(Refer to Appendix XI)

#### 3. **DRILLING SUMMARY**

#### (a) <u>Drilling Summary</u> (All Depths Driller's KB)

Gordon-1 was spudded at 2300 hours on the 15<sup>th</sup> of April, 1997.

Tables I and II summarize the major drilling operations in this hole. A more comprehensive summary is appended to this report (Appendix X: Drilling, Casing, and Abandonment Summary).

#### TABLE I: CASING, HOLE, AND CEMENT DETAILS

BIT SIZE	DEPTH	CSG SIZE	CSG DEPTH	JNTS	CSG TYPE	CEMENT
12.25" 301mm	656m	9 5/8" 244mm	653.3m	52	36ppf, K55 LTC	437sx Class "G" cmt with 112.4bbl water + 2.5%PHG @ 12.8ppg; plus 127sx "G" cmt with 15bbl water + 1.2% CaCl2 @ 15.8ppg plus 130sx, 27bbls "G" tail, with 2%CaCl; topup with 26sx "G" with 3bbl water + 2% CaCl2 @ 15.8 ppg.

#### TABLE II: SUMMARY OF MUD SYSTEMS

MUD TYPE	INTERVAL (m)
Spud Mud (Gel/Water) KCL/PHPA	Surface - 656 656 - 2505

#### (b) Lost Time

Lost time at Gordon-1 – This section will be forwarded when available, and appear as part of Appendix X: Drilling, Casing and Abandonment Summary.

#### (c) Water Supply

Make up water (Chlorides 800 mg/l, hardness 140 mg/l, pH 7.3, Pf/Mf 0/0.05) was hauled from the mains.

#### (d) Mudlogging

Mudlogging services were provided by Halliburton Australia Pty Ltd. (Unit 27). Samples were collected, washed, and described at 10m intervals from the surface to 9 5/8" casing point, 656m, then at 5m intervals from 9 5/8" casing shoe to 1300m, and then at 3m intervals to total depth at 2505m. All samples were checked for oil shows using ultraviolet fluorescence. Gas levels were monitored from the surface casing shoe to TD using a total gas detector and other parameters monitored included rate of penetration, weight on hook and mud pit levels.

#### (e) Testing

The following table summarizes the two Drill Stem Tests (DSTs):

### TABLE III: SUMMARY OF DRILL STEM TESTS

DST	INTERVAL	TYPE	TESTING CO	RESULTS
1	Basement 2390-2461m (D) 2388-2459m (L)	Conv. Off Bottom Straddle	Halliburton	Packer failed 17mins into 2 <sup>nd</sup> Flow; NFTS; Rec. 6bbls oil cut rathole mud, @ 38° API, Pr. Pt. 36° C.
2	Basement. 2389-2461m (D) 2387.5-2459m (L)	Conv. Off Bottom Straddle	Halliburton	Packers failed after 216mins. Rec. 1bbl oil cut water + 7bbls muddy water.

#### (f) Coring

No cores were cut in the Gordon-1 well.

#### (g) Electric Logging

One suite of electric logs was run in Gordon-1, as detailed below:-

#### TABLE IV: ELECTRIC LOG SUMMARY

TYPE OF LOG	SUITE/RUN	INTERVAL	BHT/TIME
GR (ECGR) CAL (HCAL)	1/1	2490-560m 2496-652m	97° C/ 8.2 hrs
SP (SPAR) Sonic (DTLF, DTLN, DTL, DT)		2473-652m 2485-652m	
Resistivity (RX08, HRLS, HRLD)		2499-652m	
TNPH A/S		2492-652m 2485-2100m	
CST	1/2	2485-1035m	99° C/ 16.2 hrs; Cut 60, Rec. 56
FMI *Note: Wireline log	ging contractor: So	2498-2270.4 CHLUMBERGER	96° C/ 6.3 hrs.
	56		

#### (h) Geothermal Gradient

A static bottom hole temperature of 102°C is calculated. This gives a geothermal gradient of 3.27°C/100m. An ambient temperature of 21 °C was employed. Data used for calculations is as follows:-

97 °C at 2499m after 8.2 hours from Run 1, Suite 1, with the SP, GR, Resisivity, Sonic etc.

99 °C at 2485m after 16.3 hours from Run 2, Suite 1, with the sidewall cores.

96 °C at 2498m after 6.5 hours, from Run 3, with the FMI log, following last wiper trip.

Note: See Appendix VIII for more detail.

#### (i) Hole Deviation

The Gordon-1 well was not deviated at all.

#### j) Velocity Survey

No velocity survey was run in Gordon-1.

#### (k) Completion Summary

Gordon-1 was cased and suspended for possible re-entry and to sidetrack the well in the future.

**GEOLOGY** 

## 1. PRE-DRILLING SUMMARY (after Well Proposal)

Gordon-1 was proposed as a wildcat, exploration well for gas, located on Offline 36m northwest of CDP827 (SP 515), line OMN 93-08, in PEP 119, in the western part of the Otway Basin of Victoria, very close to the border of South Australia. The structure is a tilted, normal fault block closure, dipping gently to the northeast, on the northern terrace of the northwest-southest trending Penola Trough. It was calculated to have a mapped area of 1050 acres, which it was thought may extend to 4400 acres if lowside closure and evidence of a minor AVO was included.

The primary objective of Gordon-1 was clean, loose sandstones of the early Early Cretaceous McEachern Sandstone, of the Pretty Hill Formation, Crayfish Group. A relatively thick section of the sandstone was predicted, with a mean net pay estimated to be 21m. Nearby, in the McEachern-1 well, (drilled in Dec. 1989/Jan. 1990 by GFE), 250m of the sand was encountered, with a net sand of 144m, with average log porosity of 20%. The sandstone is of good reservoir quality, with a low amount of finer-grained interbeds, however, most of the McEachern is dominated by the grain supported quartzarenites.

In the Otway Basin, especially in the western portion lying in South Australia, sandstones occurring in the Pretty Hill Formation have had encouraging hydrocarbon shows, and exhibit excellent reservoir characteristics. Seal is provided by overlying shales in the upper portion of the Pretty Hill and by the Eumeralla Formation which acts as a regional seal. The underlying Late Jurassic to Early Cretaceous Casterton Formation has been analyzed and proved to be an excellent, mature, source rock capable of generating hydrocarbons. The presence of oil at Gordon-1 was not discounted, due to recovery of oil (thought to have been sourced from the Casterton) from Wynn-1 and Sawpit-1 also located on the flank of the Penola Trough. Thus, prior to the drilling of Gordon-1, it was thought that all the necessary ingredients were in place for the presence of hydrocarbons in the structure.

The critical risks were identified as being fault seal for the gas target and oil charge into the reservoir. Reservoir is also considered as a significant risk in the central Penola Trough.

## 2. <u>DRILLING RATIONALE</u> (after Well Proposal)

Gordon-1 is located in the far western corner of PEP 119, which lies at the western boundary of the State of Victoria. The well is approximately 5 km west of the small town of Casterton, 9.5km south southeast of the McEachern well, 30km east of the Katnook gas pipeline in South Australia, and about 50km west of the Victorian gas pipeline at Hamilton, Victoria.

The Gordon structure, a tilted fault block, is situated on the northeastern flank of the Penola Trough, occurring in the western portion of the Otway Basin.

The well was planned to drill and evaluate the McEachern Sandstone, a member of the Early Cretaceous Pretty Hill Formation (Lavin and Muscatello, 1997). This good quality reservoir sandstone was first intersected in the McEachern-1 well, drilled in 1990, to a total depth of 2384mKB. One drill stem test was conducted in the Pretty Hill and produced 41bbls of salty, gassy water and 9bbls of slightly muddy, gassy water. The Pretty Hill Formation contains several sandstone reservoir units, one of which is the McEachern, that in the well completion report was named the "basal Pretty Hill Sandstone". In the original well it consists of a clear, off-white to very light brownish-grey, coarse-grained sandstone, minor lithic fragments, poor to moderate sorting, and very good porosity, and is interbedded with minor claystone. A section of 250m was encountered in the well, with a net sand of 144m exhibiting a porosity of 20-25% immediately above the Casterton Formation. In the Gordon well, the McEachern was expected to have a mean net pay of a 21m thick, mature, well developed, potential reservoir sandstone.

Geophysical mapping, incorporating seismic data of mixed vintage (1993-1996), indicated that Gordon had strong dip reversal to the northeast, against the monoclinal, southwesterly dip, which is pervasive throughout the Penola Trough. Closure to the south is against a major east-west trending fault, with cross fault seal provided by shales in the Pretty Hill Formation (McGee, 1996). Vertical seal was also expected to have been provided by the overlying thick shale sequence of the Laira Formation of the Crayfish Group. It does, however, contain abundant interbedded sandstones and great lateral variation of lithology, thus there may exist a risk of cross fault leakage (Lavin and Muscatello, 1997), at that level.

[It should be noted that the McEachern Sandstone is not recognized formally in the literature or industry as a subdivision of the Pretty Hill Formation. Lovibond *et al.* (1995) proposed the breakdown of the formation into four units, utilizing the same name for members as the enclosing formation, however, as such they do not meet the criteria of the International Stratigraphic Code of Nomenclature. See Morton *et al* (1995), p.59, in the Petroleum Geology of South Australia, Volume 1: Otway Basin, for more information.]

Unfortunately it was discovered during the drilling of the Pretty Hill Formation, that the McEachern Sandstone was not present. The reasons are presumably because of pinchout of the clean, mature sands, resulting in a more fine-grained section being intersected. The objective was predicted to occur at 2278.3m RT or 2149m SS, and to be 109m thick. At this level in the well, silty claystone grading to minor argillaceous siltstone and a trace of siliceous, argillaceous sandstone was intersected.

#### 3. RESULTS OF DRILLING

#### (a) Stratigraphy

The following table lists the formations intersected in Gordon-1, together with subsea elevations and thicknesses. All depths are Logger's Depths.

TABLE VI: STRATIGRAPHY IN THE GORDON-1 WELL

AGE	FORMATIONS (S)	DEPTH (m)	ELEV (m)	THICK (m)
Tertiary	Heytesbury Group	4.7(sfc	+124.9	35
	undifferentiated			
	Otway Group		i	
E. Cret. (Aptian-Albian)	Eumeralla Formation	40.0	+89.6	1110
E. Cret. (Berriasian-Barremian)	Crayfish Group			
E. Cret. (Valanginian-Barr.)	Laira Formation	1150.0	-1020.4	367
E. Cret. (BerrValanginian)	Pretty Hill Formation	1517.0	-1387.4	601
(not present)	McEachern sst	Not	present	in the well
L. Jur. to E. Cret. (Kimm. to	Casterton Formation	2118.0	-1988.4	243
Berr.)				
Palaeozoic	Basement	2361.0	-2231.4	142+
	Total Depth	2503.0	-2373.4	
	_			

Cuttings samples were collected, washed, and described at 10m intervals from the surface to 9 5/8" csg pt. (656m), thereafter at 5m intervals from 656m to 1300m and at 3m intervals from 1300m to the total depth of 2505m.

#### **STRATIGRAPHY**

A brief summary of the formations penetrated in Gordon-1 and their interpreted environments of deposition follows:- (For more detailed lithological descriptions from the wellsite, please refer to **Appendix I, Part a and Part b).** 

**Total depth** for Gordon-1 was reached at 2505m (D) or -2375.4m ss, in the **Palaeozoic** basement. The well intersected 139m of metasiltstones, interpreted as the basement, before declaring total depth. The weathered, white, very light grey to light green metasiltstone was drilled into at 2361m (-2231.4m ss). With depth, it became medium to dark greenish-grey with fine to medium-grained brown to black inclusions with diffuse grain boundaries. It was very siliceous, slightly to moderately calcareous, with very coarsely crystalline vein quartz in places, abundant micromica, a trace of pyrite, and was hard and fissile. From 2411m to 2505m, the colour became more olive grey, had a siliceous to microcrystalline texture, was slightly to moderately calcareous and ankeritic, had minor increasing to common slickensides (with ankeritic lining), and minor increasing to common, coarsely crystalline quartz infilling fractures, both of which increased with depth. In the last 70m there was common disseminated and nodular pyrite.

## OTWAY BASIN STRATIGRAPHIC COLUMN

Sanus

GEO	)L(	OGIC	AL TI	ME SCA .,1989)		FORAMINIFE MICROPLAN	RAL/	SPORE-POLI ZONES		GROUP	FORMATION	DEPOSITIONAL ENVIRONMENT	rectonics	DISCOVERIES and SIGNIFICANT
PERIOD	1	Ma	1	POCH	Ma	1	Ma		Ma	9	Offshore Onshore	FIGALI (OLGIGIEIA)	田田	SHOWS
UA.		-	PLE		0.0 1,6 5.2	N22/23 N21 N18/20	-  -  -	- C. biturcatus			Whalers Bluff Fm		anism	
X X	21		MIOCENE	MIDO	10.4 LE 16.3 Y 23.3	N7 N6 N5	4	T. bellus  Upper  Middle P. tubercutatus	16.3	HEYTESBURY GROUP	Port Campbell Limestone Fm Chapter Mari Mari Mari Chiton Fm Clitton Fm	Manne prograding sequences	Compression, volcanism	LITHOLOGY LEGEND  Conglomerate  Mainly Sandstone  Sst/Sitst/Shale  Mainly Mudstone
L L A	34	-	OLIGOCENE	EARI	35.4	P19/20 P18 P17 P16 P15		Upper N. asperus  Middle  N. Asperus	; ; - - - 38.6	NIRRANDA GROUP	Narrawaturk Demons Bluff Formation  Mepunga Fm/Nelson Fm	Marine prograding sequences	Sedimont starvation	Mainly Volcanogenic  Carbonate Clast/Mari  Palseozoic Basement and Intrusions
	56	-	EOCENE	MIDD	50.0	P10/14		P. asperopolus Upper M. diversus Lower M. diversus		WANGERRIP GROUP	Dinaku Sari	Fluvial and delta destributory channels, prodelta	Post-rift passave margen	
	60	0 -	PALAEOCENE	EARI	60.5	P4 P3 P2 P1	85.0	Lower L. baimel	<b>-</b> 65.0	WAN	Pember Mudstone/ Rivernook Pm  Pebble Point Fm	Inter-distributary bay muds  Transgressive sands and conglomerate  Angular unc	_	💠 Lindon 1
LATE	80	0   1   1   1   1   1   1   1   1   1	SENONIAN	CAMPANIA SANTONIA DINIACIAN JIRONIAN	74.0	M. druggli  I. korojonense  X. australis  N. aceras  I cretaceum  O. porifera  C. striatoconus  P. infusorioides	73.0 78.0 81.5 83.5 85.6 87.0 88.5	T. lilliei	71.0 78.0 83.0 88.5	SHERBROOK GROUP	Curdies Fm Curdies Fm Timboon Sandstone	Paaratte Lower delta plain, lagoonal, shore-face Cardies Timboon: Upper delta plain	hermal subsidence phase	Contractial Break-up 90-110 Ma (Cande & Mutter, 1982) 95± 5 Ma (Veevers, 1986)
	-	00	CEA	IOMANIAN	97.0	D. multispinum	93.0	A. distocarinatus P. pannosus	98.5		Flavmens Fra  Waarre Sandstone	Lower delta plain, marine 5 Fluvial, upper delta plain Meandering fluvial to tacustrine, upper delta plain	~~	→ LaBelia 1, Peden 1A  → North Paaratte 1 95±  → Caroline 1 (CO2)  → Port Campbell 1 100
	11	10		ALBIAN	112.0		4 :	C. paradoxa C. striatus	† 103.0 -† 110.0 -† 113.0	GROUP	Heathfield Sst	★ Volcanogenic  Lacustine, backswamp, meandering fluvial, alluvial plain	Sportfriff	₩indermere 1 ☆ Katnook 2
EARLY	:["	20	7-	APTIAN	124.			C. hughesi	寸 119.0	SUPER	Windermere Sst  Katmook Sst	Fluvial Angular unconton	mity ~	<b>;</b> Кашоок 1
		30	NEOCOMIAN	IRREMIAN HAUTERIVI	- 131 - 135 NN - 140.	3	:	F wonthaggiensis  C. australiensis	<del>-</del>  138.0	OTWAY	Pretty U. Sawpit Shale Hill Sat L. Sawpit Shale Mc Eachern Sat Australienes Shale	Lacustone with minor meandering fluvial strong to the part of the	Syn-rift rift fill megasequence	Katrook 2, 3  Ladbrook Grove 1  Troas 1, Crayfish A1 Lairs 1
LATE L		-	TI	THONIAN	145.	6		R. wathercoensis	<b>⊣145.6</b>		Casterton Beds Caster	"Fluvio-lacustrine with intrusives	<b>.</b>	Sawpii 1

A live oil show was encountered in the fractured basement between 2401-2410m. The fluorescence was associated with the quartz veining, the adjacent host rock and in part with the slickensides. It was a trace to 2% moderately bright to bright patchy yellowish-white fluorescence, with a dull milky white crush cut forming a thin ring residue. In the three intervals below exhibiting oil shows, at 2411-2436m, 2436-2443m and 2457-2460m the fluorescence became a trace, and slightly weaker, though still bright patchy pale yellow, with also a lesser degree of fracturing in the metasiltstones.

Two drill stem tests were conducted over the fractured interval displaying the shows. The first, DST #1, from 2390-2461m, although it had a packer failure, recovered 6bbls of oil cut mud. The second, DST #2, was run over the same section, recovering 1bbl of oil cut water and 7bbls of muddy water, however, it also lost its packer seat.

[In Sawpit-1, good oil shows were recorded within fracture porosity in metasedimentary, phyllitic basement. A drillstem test recovered 1.5bbl of 32°-35° API oil, with the Casterton interpreted to provide the source of the oil. Also at Kalangadoo-1, carbon dioxide rich gas flowed at a rate of 1.5mmcfd, from fractured basement (from Lovibond *et al.*, 1995).]

The Otway Basin is a Late Jurassic to Recent basin on the southern margin of Australia, straddling the states of South Australia and Victoria. It was formed by the rifting and continental break-up of Australia and Antarctica. The Pre-Mesozoic basement rocks consist of Palaeozoic intrusives and metasediments associated with the Lachlan Fold Belt. The basement reflector is a high amplitude, low frequency event showing strong angular unconformity onto an erosional or faulted surface (Cockshell *et al.*, 1994). The Otway Basin was initiated as a series of half grabens (Sprigg, 1986), separated by basement highs. Many of these grabens such as the Penola Trough in which Gordon is situated, are bounded to the south by large, north-dipping faults. Some of the intervening half-grabens have southerly dipping, north bounding faults (Cockshell *et al.*, 1994). The basement topography and geometry of the half grabens has clearly affected, and thus controlled, the distribution and thickness of the overlying sediments of the Casterton Formation and the Crayfish Group.

Overlying basement at Gordon-1 is the Late Jurassic to Early Cretaceous Casterton Formation. The top of the Casterton came in at 2118m, or -1988.4m ss, 269.6m high to prognosis, and is 243m thick. The top 82m to 2200m(L), consists of medium brownish-grey siltstone grading to and in part laminated with off-white to medium brownish-grey and medium grey sandstone, making up the coarsest grained interval of the formation. From 2160m(L) the sediments display several finingup sequences of 3 to 4m in thickness, and at 2190m(L) a small 3m blocky channel sand is present. A 30m thick interval of medium to dark brown to dark grey silty claystone, more characteristic of the type Casterton occurs below, to 2230m(L). From 2230m to 2274m(L) a finer-grained section dominantly consisting of dark brownish-grey to dark grey, moderately carbonaceous silty claystone is present, with the Gamma Ray showing a fairly expressionless, straight line. In lithological descriptions in contrast, is described claystone grading to argillaceous siltstone and trace sandstone (probably cavings). Below, from 2274m to 2351m (L) grain size increases, with more argillaceous siltstone appearing, moderately carbonaceous, with common black carbonaceous flecks and trace black coaly detritus. At 2351m(L), black to very dark grey coal is present, making up 25% of the samples, with the remainder carbonaceous, silty claystone and argillaceous siltstone, with a trace of very fine sandstone. This basal section is approximately 10m thick, lying above basement. Throughout the formation the argillaceous siltstone and minor sandstone contain abundant very fine partially altered feldspar grains and common grey, greyish-green and brown lithics.

No volcanics, basalts or tuff were described in the samples by the wellsite geologist at this location. The Casterton Formation is known to contain volcanics in eastern Victoria especially, including the Casterton well nearby, however, none have been confirmed within the formation in South Australia (Morton *et al.*, 1995).

The contact with the underlying low grade metasedimentary basement is a low angle unconformity. Distribution and thickness of the formation was fault controlled, and was determined by the underlying topography of the basement. On seismic sections it shows a low angle onlap on to the basement highs. The Casterton has been interpreted to have been deposited in a non-marine lacustrine to swampy environment, with fluvial systems present in the adjacent highlands (from Lavin, 1997). It has been suggested that deposition may have preceded rifting, following seismic work carried out by the Geological Survey of Victoria (Morton *et al.*, 1994, *in* Finlayson *et al.*, 1994). It is also thought (Lovibond *et al.*, 1995) that the Casterton represents the earliest synrift fill in the Penola Trough.

The Casterton Formation is considered to be Late Jurassic to Early Cretaceous, belonging to the Retitriletes watherooensis to lower Cicatricosisporites australiensis zones, ie Tithonian to Berrasian in age (Morton et al., 1995). Twelve sidewall core samples were analyzed for biostratigraphic purposes, from 2126m to 2356.25m, encompassing the whole of the Casterton intersected in the well. The ages ranged from Berriasian (Early Cretaceous) at the top to Kimmeridgian (Late Jurassic) at the base. Most of the cores were siltstone of a varying shade of grey to brownish-grey, some with very fine to fine-grained sandstone laminations. environments of deposition switched between fluvial at the top, to lacustrine, back to fluvial, then lacustrine and remained fluvial until the 2337.5m sample, #14, which was lacustrine again. The final sample at 2356.25m, #11, was identified as being from a peat bog (possibly flanking a lacustrine system), as it was a black, subvitreous coal, containing dominant fern spores. It was indicated to have been derived from the Casterton coal palynofacies (APG Consultants, 1997). The varying palaeoenvironments may have been a result of a general transgressive lacustrine system, intercalated with regressions, thus forming river and alluvial systems on the outer fringes. It was suggested by Lavin (1997) that as the topographic low was created by syn-depositional faulting, the lake deepened, and depositional energy levels decreased. As extensional faulting ceased for a time, or slowed, regression would take place, with deltas and fans becoming more prominent.

Analyses were not carried out on the sidewall cores for maturity, total organic carbon (TOC), or kerogen content, spore colour or TAI indices, thus statements cannot be made as to the source potential of the Casterton at Gordon-1. In general, the formation has a fairly good potential, containing rich organic material. The TOC values commonly exceed 1.5%, but values vary considerably. In the McEachern-1 well, the average TOC measured 1.1%. At Casterton-1 nearby, the formation is a locally excellent source, with maximum TOC=45.90%, though the average was 4.9%, and S1+S2=100.86. These intervals, though thin are capable of generating significant quantities of oil where mature. It has been discovered that the richest source intervals occur towards the base of the unit, possibly reflecting high concentrations of terrestrial detritus in localized rift lakes (from Hill, 1997).

An unconformity separates the Casterton Formation and the overlying **Crayfish Group**. At some locations this is an angular contact (Morton *et al.*, 1994, *in* Finlayson *et al.*, 1994), at others it has proved to be difficult to map reliably on seismic and its identification by palynology and on logs is interpretive, and in addition its distribution is poorly understood (Lovibond *et al.*, 1995).

The Crayfish Group has been divided into three formations, the **Pretty Hill Formation**, **Laira Formation** and the **Katnook Sandstone**, by Morton *et al.*, (1994, *in* Finlayson *et al.*, 1994). They stated nevertheless that regional correlation shows the Katnook Sandstone and Laira Formation can be lateral facies variations of each other, but that the top of the Pretty Hill Formation is probably reasonably synchronous. Seismic mapping of these units is therefore quite difficult. The group is best known from the Penola Trough.

The <u>Pretty Hill Formation</u> which overlies the Casterton Formation unconformably, was intersected at Gordon-1 at 1517m (L) or 1387.4m ss, coming in 143.6m high to prognosis. It was 601m thick in this well. The formation has been subdivided in the past by several authors although they have not been recognized formally (Morton *et al.*, 1995). With additional drilling in the western Otway and further geophysical, geochemical and biostratigraphic work, the members could be formally defined in the near future. Lovibond *et al.* (1995) informally subdivided the formation into four members: 'Pretty Hill sandstone', 'Sawpit sandstone', 'Sawpit shale' and 'McEachern sandstone'. The **McEachern sandstone** was expected to occur at this location and was designated the primary objective in the Gordon-1 well, predicted to come in at 2278.3m or -2149m ss, and be 109m thick. It has been determined that the sandstone was not present in the well.

At the wellsite, the Pretty Hill was not designated into members, thus the present author will deal with the formation as a whole. On logs it appears the formation consists to a high degree of sandstone, with a minority of silty claystone (from 5% to 25%, in the lower portion of the Pretty Hill), with siltstone (5%) and claystone (5%) in the following 200m, and in the top 32m, sandstone makes up 60%, claystone 30%, and siltstone 10%.

In the basal 128m, from 1990-2118m, the sandstone is off-white to light grey, dominantly fine-grained, although ranges from very fine to coarse, poorly sorted, with moderate to strong silica and weak calcareous cement. There is common white argillaceous matrix, trace to common pink to red garnet, common grey to green phyllitic and volcanic lithics, increasing with depth, and a trace of black coaly detritus. The sandstone is moderately hard to hard, has a poor to fair visible porosity, and no fluorescence. It is interbedded and laminated with medium brown to medium grey silty claystone, that is in part dark grey and shaly. It contains a trace of very fine off-white partially altered feldspar grains in part, trace to common black carbonaceous flecks and coaly detritus, is moderately hard, very dispersive and subfissile.

The next section, from 1751-1990m, is made up of a majority of off-white to light grey, medium-grained, poorly sorted sandstone. Generally the description for the sandstone in this interval is the same as the underlying one. There is moderate silica, weak to moderate calcareous and a trace of strong brown dolomite cement. It is interbedded and in part laminated with silty claystone as above. The basal 20m is silty claystone, overlain by a thin sandstone lens with a sharp contact,

which fines upwards. This is followed by a 55m thick sandstone with a trace of claystone, which fines up slowly through 10m to a 5m thick silty claystone. The overlying interval, from 1751m-1808m consists of more thickly interbedded sandstone and silty claystone. The sandy sections generally have a blocky character, except between 1783m and 1776m, where a 3m sand, fining upwards, is immediately overlain by another 3m sand, coarsening upwards. The overlying section (1549m-1751m) is composed of 90% sandstone, dominantly off-white with very light grey to light brown and medium-grained, with common white to light brown argillaceous matrix, common pink to red garnets and only a trace of cherty, volcanogenic and phyllitic lithics, and poor to fair visible porosity, which is interbedded and laminated with 5% siltstone and 5% claystone. The topmost section, from 1517m to 1549m, has 30% claystone and 10% siltstone, overlain by a 15m thick, off-white, fine to medium sand with very poor to fair porosity (inferred), comprising 60%. This sand contains moderate silica and calcareous cements, has common to abundant white argillaceous matrix and only a trace of greyish-green and reddish-brown lithics, a trace of garnet and black to dark brown coaly detritus.

The environments of deposition postulated for the Pretty Hill Formation are related to rapid subsidence and thus ensuing high sedimentation rates in a syn-rift basin. The formation is best known from the Penola Trough. The Gordon-1 well is situated on the far eastern edge of the trough, on its flanks, and therefore will not exhibit all the features that are represented in the Katnook wells, for example. In the axial position of the half graben, Morton *et al.* (1995) suggests that parts of the Pretty Hill have characteristics of a high sinuosity fluvial system, and parts, a low sinuosity system. Flood-basin deposits, silty flood plain with crevasse-splay and sheet-flood sandstone interbeds are thought to have formed adjacent to the main channel. In the case of Gordon-1, where there is a predominance of sandstone, with thin interbedded siltstones and shales, it appears that it is located in the vicinity of a braided, fluvial channel system. A westerly palaeocurrent flow has been interpreted from dipmeter data for the Pretty Hill (Morton *et al.*, 1995) probably sourced from erosion of local basement highs.

The age of the Pretty Hill Formation is Early Cretaceous [Berrasian to Valanginian Stages (140-133Ma)], falling into the upper part of the *Cicatricosisporites australiensis*, and lower part of the *Foraminisisporis wonthaggiensis* palynozones (Morgan *et al.*, 1995). The samples all yielded inaperturate and saccate pollen and fern and lycopod spores, though some were sparse and restricted in diversity. Six sidewall core samples were examined for their spore and pollen content in the Pretty Hill Formation. These were #47—1536m, #44—1593.25m, #43—1614m,#40—1761m, #39—1768m and #36—1882m. The first three, dark grey claystone and light to medium greyish-brown siltstone, were identified as being fluvial in origin, then there was a gap in samples represented by a sandy section, then #40 was a siltstone and thought to be paralic coastal plain, the next #39, a claystone, is lacustrine with algal forms notable, and the final one, #36 a siltstone, is paralic lagoonal. (See APG Consultants Biostratigraphic Report). The base of the formation was not examined, being a thick sandy interval.

Overlying the Pretty Hill Formation is the <u>Laira Formation</u>, forming the top of the Crayfish Group at this location. The contact appears to be gradational, and fairly transitional with the underlying 15m thick sand at the top of the Pretty Hill. The top of the Laira was intersected at 1150m, or -1020.4m ss, and is 367m thick. It was predicted to occur at 1017m ss, thus was only 3.4m low to prognosis.

The Laira Formation is composed to a great extent of shale (claystone, in lithological descriptions), with thin interbeds of siltstone making up 20-30% of the samples and sandstone, only 10%. These interbeds measure from 1m to 5m in thickness.

From 1350m to 1517m, the claystone is light to medium brownish-grey to medium grey and olive grey, and in parts very silty. It contains a trace of black carbonaceous flecks and micromica, and common, in part, abundant dark brown to black coaly material. It is firm to moderately hard and subfissile. The claystone grades to a minor argillaceous siltstone of the same colour, in part finely arenaceous with partially altered feldspar grains with similar carbonaceous material. The sandstone lenses are off-white, very fine, subangular, moderately sorted, with moderate to strong silica and calcareous cements, common to abundant white argillaceous matrix, trace greyish-green and reddish-brown lithics and garnet, and trace to common coaly detritus. It is friable to hard, has no, to poor, porosity (inferred), and no fluorescence. The thickest sand, from 1419m to 1426m, has a sharp base and fines upwards.

The overlying interval, between 1150m and 1350m, appears very similar in log character to the one below, perhaps more shaly, though was described as having a greater percentage of siltstone. One sand lens, (2m), at 1288m has a sharp top, and fines downwards, while the others, no more than 1-1.5m are merely gradational interbeds and laminations. All were expressed as having no visible porosity.

The Laira Formation appears to represent a fluvial flood plain environment, at least at the base of the formation, with its dominance of shale, and the sandstone lenses overbank deposits, or perhaps sheet-flood sediments. In the sidewall core sample (#48) at 1510m *Microfasta evansii* is described as being notable. It does not appear again until at 1369m (#52), where it is denoted as isolated, and at 1275m (#53) it is notable. *M. evansii* is an algal acritarch and is taken to indicate a lacustrine environment. Below 1369m, the preservation and organic yield are poor to very poor which may point to a higher energy fluvial setting, whereas the cores above contain fair to fresh palynomorphs, and other aquatic forms (from APG Consultants, 1997—see Biostratigraphic Analysis), and therefore likely to be lacustrine dominated.

The age attributed to the Laira is Early Cretaceous, in the Valanginian to Hauterivian Stages (136-125Ma), belonging to the lower to upper *Foraminisisporis wonthaggiensis* palynozone (Morgan *et al.*, 1995).

In the Gordon-1 well the Katnook Formation is not present. According to Morgan *et al.*, (1995) it has not yet been mapped in Victoria, and there are difficulties in correlating the unit away from the type section in the Katnook field, as it is absent due to erosion or facies change elsewhere within the Penola Trough.

Overlying the Laira Formation, therefore, at the well site, is the **Eumeralla Formation**, considered to be the basal, oldest formation of the **Otway Group**. It rests unconformably upon the Crayfish Group, Laira Formation in this case. The Eumeralla Formation was intersected at 40.0m, or +89.6m ss, and was expected to be at 42.6m, thus only 2.6m high to that predicted. The formation is 1110m thick at Gordon, and about 1500m in the Penola Trough, though is thought to be possibly greater than 4000m in the eastern Otway (Lavin, 1997). On the wireline logs there is no distinct boundary between the shales of the Laira Formation and the Eumeralla above, although the gamma ray appears slightly higher in the Laira.

The Eumeralla lithology is primarily composed of carbonaceous silty claystone with very fine-grained feldspathic sandstone interbeds, measuring from less than a metre to 4m in thickness. (Note: Wireline logs were not run over the top hole, prior to setting casing at 653.3m, and as a result the lithological descriptions cannot be correlated and compared uphole, except for verifying with the mudlog, for ROP and their lithology column).

From a depth of 955m, in sample descriptions, claystone makes up the bulk of the samples, at 50-60%. It varies from a light to medium olive grey to light to medium grey, (and off-white to medium brown between 1027-1092m), very silty in part, contains a trace to, in part, abundant black carbonaceous flecks and detritus, trace micromica and is firm to moderately hard and slightly subfissile to subfissile. Coal is expressed as 10% of the cuttings samples between 1027-1092m and a trace between 955-1027m, where it is black, blocky fracture, earthy to subvitreous lustre, dark brown and very argillacous in part, hard and brittle. On logs, coal/carbonaceous shale is present mainly around 1041-1044m.

A third of the samples is made up of interbedded off-white to light brown to medium grey to medium olive grey siltstone. It is very argillaceous, and in part very finely arenaceous with partially altered feldspar and quartz grains, with a trace to, in part, abundant black carbonaceous flecks and detritus, firm and slightly subfissile.

Sandstone is fairly minor (10%), grading to, and interbedded with siltstone. It is off-white to medium brownish-grey and light brown, very fine to fine-grained, (in the basal 60m appear rare, clear, medium to very coarse quartz grains), angular to subrounded, moderately sorted, strong calcareous cement (in the basal 60m also moderate to strong silica, and trace strong dolomite, cement), abundant white argillaceous matrix in part (abundant medium grey silt matrix between 955-1027m), with common green-grey and trace red lithics, trace coal detritus from 1092-1150m and becomes more common above. It is moderately hard to hard, has no visible porosity or fluorescence.

The gamma ray curve from 790m-955m is fairly expressionless, hovering around 100 units, indicating a sequence dominated by a silty, partly finely arenaceous and carbonaceous claystone, with very thin interbeds of siltstone and fine-grained sandstone. The samples, however, are almost equally divided between claystone, siltstone and sandstone with descriptions very similar to the previous interval below.

The upper section of the Eumeralla in the well has a more varied expression. At the base, from 775m to 790m, two stacked 3-4m thick sands are present. They appear fairly clean, and are described as off-white to medium brownish-grey, very fine, moderately sorted, with some white argillaceous, and grey silty, matrix, common greenish-grey and red lithics, common black carbonaceous matter, moderately hard, and no visible porosity or fluorescence. The upper sand displays two small fining-up cycles, whereas the lower is more blocky. Two 1m thick sands just above, at 764m and 767m contain more argillaceous matrix and have strong calcareous cement.

The remainder of the sequence above, to 656m just below casing point, and that above from 92m to 656m, is quite shaly (60%) with very silty sections, and the siltstone (30%) described as being very argillaceous. Both contain common black carbonaceous detritus and flecks. After setting casing, a 3m thick fine-grained, very calcareous, argillaceous sand, with no visible porosity, was drilled into. Another, merely 1m thick, at 674m, was encountered.

The interval from 40m to 92m, the top of the Eumeralla, consists of a greater percentage of claystone (90%), medium olive-grey to medium greenish-grey, light to medium brownish-grey and in part, dark greenish-grey, slightly to very silty, finely interbedded and laminated with medium grey to medium greenish-grey fine-grained sandstone (10%).

A number of types of depositional environments have been interpreted for the Eumeralla Formation in South Australia and Victoria. They range from high energy fluvial channels and flood basin deposits, with lenticular channel sands, and minor sheet-flood sands with overbank coals and silts, and also lacustrine deposits.

In the Gordon-1 well, the Eumeralla Formation appears to represent more of an overbank and back swamp facies, with very minor sheet-flood sands, due to the low frequency of sandy horizons. Both the Windermere and Heathfield Members appear to be absent. Coals are not common as such, although many samples contain common carbonaceous material. The only mention of coaly horizons are between 1027-1092m, and trace between 955-1027m in cuttings, and on logs at 1041-1044m.

Only the basal section was sampled and analyzed for biostratigraphic purposes, from 1035m to 1118m, that is SWC# 60, 59, 58, and 57. The spores and pollen present indicated a diverse fern association, existing in swampy conditions, with saccate pollens dominating the 1063m and 1105m samples (#59 and #58), thus a definite non-marine environment. At 1063m (#59), Schizosporis reticulatus was notable, an algal acritarch, which points to a minor lacustrine influence.

It appears that this section sampled is from the lower to middle Eumeralla Formation, and the zones identified in the preliminary biostratigraphy report, indicate an oldest age of Aptian, though the basal 32m was not age dated. The upper portion of the formation that was not analyzed and dated is most likely Aptian to Albian in age (125-97 Ma, *ie.* for the whole formation; Morgan *et al.*, 1995).

Overlying the Eumeralla at the well site, is 40m of an orangey-brown medium-grained, with fine to in part very coarse to grit size grains, poorly to moderately sorted sandstone. At the wellsite, this section was designated as \*undifferentiated Heytsbury Group. The sandstone has common light orange to dark brown argillaceous and silt matrix in part, clear and in part orange quartz grains, trace and, in part common, muscovite flakes, trace black to dark brown, fibrous, carbonaceous flakes, unconsolidated to, in part, hard, very good porosity (inferred), and no fluorescence. It has minor interbedded dark brown, very soft claystone. It was intersected from spudding the well to a depth of 40m (+130m to +89.6m ss). The sandstone overlies the Eumeralla unconformably, though on seismic, apparently not with a great angularity (OMN93-08R).

\*Note: In Victoria and South Australia, the Heytsbury typically contains marine sediments including limestone and marl, though assigned slightly different formation and member names, according to varying lithologies in the two states. The present author questions this assignment. In the McEachern-1 well, the top 130m were included in the Heytsbury, however, and the sample descriptions are similar, though the sandstone was very light grey and light brown.

For further details concerning the lithology, cuttings and sidewall core descriptions of the formations encountered in Gordon-1, refer to Appendix I, Part a: Cuttings, and Part b: Sidewall Cores, of this report.

## (b) Stratigraphic Prognosis (after Well Proposal)

The Gordon-1 well is situated within a tilted fault block on the northeastern flank of the Penola Trough. This structure forms a typical type of play found in the Otway Basin, the successes being located in high side, tilted fault and horst blocks. The structure was identified following mapping and interpretation of an approximately 1km x 4km seismic grid, of mixed vintage derived from 1993 to 1996. A total of five seismic events were interpreted, using seismic ties from six offset wells, including Casterton-1 and -2, McEachern-1, Bus Swamp-1, Tullich-1, and Heathfield-1.

All formations were encountered as predicted on prognosis, excepting the primary objective, the McEachern sandstone, at the base of the Pretty Hill Formation, in the Crayfish Group. During and subsequent to the drilling of Gordon-1, it was deduced that the sandstone was absent at this location.

The well was spudded into an orangey-brown sandstone declared to be undifferentiated Heytsbury Group, though this assignment may be questioned. Forty metres below, the Eumeralla Formation, of the Otway Group, was intersected only 2.6m low to prognosis. The Eumeralla consisted dominantly of claystone, with varying percentages of siltstone (5-40%) and minor (5-30%) sandstone, and was 1110m thick. The Laira Formation of the Crayfish Group was found to underlie the Eumeralla, and came in at 1150mRT, merely 3.4m low to that expected. Claystone (60-70%) again predominates the lithology, with siltstone 20-30%, and sandstone (10%). Below was the Pretty Hill Formation, with its top at 1517mRT, 143.6m high to prognosis. Sandstone makes up the bulk of the samples, up to 95%, with siltstone and claystone ranging from 5% to 30%.

The McEachern sandstone, an informal member of the Pretty Hill Formation, the target of the Gordon-1 well, was expected to occur at 2278m, or -2149m ss. It was deemed not to be present. Underlying the Pretty Hill is the Casterton Formation, intersected at 2118m, or -1988m ss, 269.6m high to prognosis. It is 243m thick at Gordon, overlying the Palaeozoic basement, which was drilled into at 2361m (-2373m ss), but was expected at 2450m, thus 89.6m high. The basement, a fractured metasiltsone, was found to contain live oil, throughout an approximate 40m column, from 2401-2443m, plus an additional 3m section from 2457-2460m. These shows precipitated the two drill stem tests, neither of which was entirely successful, due to packer seat failures, though there were recoveries of oil cut rathole mud.

Actual versus the predicted subsea formation tops plus thicknesses for Gordon-1 are tabled below (all depths quoted are Logger's Depths):

TABLE VIII: ACTUAL VERSUS PREDICTED DEPTHS AND THICKNESSES
GORDON-1

FORMATION	PROG SS	ACTUAL SS	DEPTH DIFF	PROG THICK	ACTUAL THICK	THICK DIFF
	DEPTH	DEPTH				
undiff. Tertiary/L. Cret	+125m	+124.9m		38m	35m	-3m
Eumeralla Fm	+87m	+89.6m	2.6mH	1104m	1110m	+6m
Laira Fm.	-1017m	-1020.4m	3.4mL	514m	367m	-147m
Pretty Hill Fm	-1531m	-1387.4m	143.6mH	618m	601m	-17m
McEachern sst	-2149m	No	present	109m	0m	
Casterton Fm	-2258m	-1988.4m	269.6mH	63m	243m	+180m
Basement	-2321m	-2231.4m	89.6mH	45+m	142+m	
Total Depth	-2366m	-2373.4m				

#### (c) Hydrocarbon Summary

Total gas was recorded from the surface to total depth (2505m KB) using an FID total gas detector run by Halliburton Services, Unit No. 27. One unit of gas is equal to 200 ppm methane equivalent. Chromatographic analysis was determined using an FID chromatograph and these values are quoted as percentages (C1 - C4). Ditch cuttings were collected at 10m intervals from the surface to 9 5/8" casing point, at 653.3m, at 5m intervals to 1300m, and then at 3m intervals from there to T.D. at 2505m. All samples were washed, described and checked for fluorescence using ultraviolet light.

#### Surface to top Pretty Hill Formation (spud to 1517m)

No shows were recorded through the top undifferentiated section, Eumeralla Formation or Laira Formation. Throughout these formations no gas was detected, until at 600m, in the Eumeralla, where total gas was 0.1 units, and maximum was 0.2, with C1 at 100%. Levels remained low, increasing to maximum of 75 units, from coal, with C1--98%, C2--2%, C3&4-- trace between 1027-1092m, dropping back to a maximum of 12 units at the base of the Eumeralla. In the underlying Laira Formation, background gas was still low, with a maximum of 6-7 units, until a maximum of 45 units (on the mudlog it was only 20 units), again associated with a coal, between 1350-55m. On the mudlog, however, a few peaks were recorded, ranging from 20-42 units approximately, but C1 remained at 95-97%, with C2 at 3-4%. No hydrocarbon fluorescence in the drill cuttings were recorded within these formations.

#### Pretty Hill Formation (1517 - 2118m)

Background total gas within the Pretty Hill was low, with virtually no peaks (with a range of less than one to a maximum of about 18 units) in the curve. C1 values were between 94-99%, with C2-1-5%. Sandstone at 1641m to 1645m displayed a trace of patchy, moderately bright yellowish-white fluorescence, a moderately bright milky white crush cut and a thin film residue. At the wellsite, it was determined that the oil show was of a residual nature and confined to tighter aggregates only. The sand was off-white to light brown, medium-grained, with moderately strong silica, moderate dolomite and weak calcareous cements, with a poor to fair visible porosity. There was no associated gas peak.

Another thin sandstone, off-white to light grey, with poor to fair visible porosity, at 1771-1775m, also had a trace of patchy moderately bright yellowish-white fluorescence, with a dull to moderately bright milky white crush cut and a trace of residue. This was again thought to be of a residual nature. It had a small associated gas peak of about 10 units.

The primary objective in the Gordon-1 well was the McEachern sandstone member of the Pretty Hill Formation. During the drilling, it was deduced that the member was not present at this location, perhaps due to pinchout or merely lateral facies variation.

#### Casterton Formation (2118 - 2361m)

Total gas within the formation was low prior to 2325m when it rose to a maximum of about 150 units (see Mudlog for more detail). C1 values dropped from 94% to 77%, and C2 increased from 4 to 12%, with the highest C3 of 10%, C4 of 11%, and C5 of 1%. Black to dark brownish-black coal was noted in the cuttings descriptions, from 2345m to 2364m, immediately above basement, with associated gas peaking between 60 to 150 units.

An off-white to light brown, fine-grained sandstone with very poor porosity at 2195-2212m, displayed a trace to 1% moderately bright, patchy, light yellow fluorescence, with a dull pale yellowish-white crush cut and a thin ring residue. The wellsite assessment was that it was a live oil show, and contained only within aggregates where slightly better porosity existed. No significant gas peaks were recorded over the interval.

#### Basement (2361 - T.D. of 2505m KB)

The level of background total gas remained fairly low with a straight trace, with 5 very minor peaks to total depth, within the basement. The C1 readings ranged from 77-86%, C2 from 6-9, C3 from 5-9, C4 from 1-5 and C5 from trace to 2%. Each of the peaks in total gas was associated with an oil show in the cuttings.

From a depth of 2400m there was an almost continuous live oil show within the metasiltstone to a depth of 2443m. The fluorescence was associated with quartz veining, and was also in the adjacent host metasediments. It appeared as a trace, to 2%, moderately bright to bright patchy yellowish-white, and pale yellow fluorescence with dull milky white crush cut and a thin ring residue. The first show was detected at 2401-2410m and was thought to be associated a fracture system at that depth, and was infilled by coarsely crystalline quartz. The second show interval, at 2411m - 2436m appeared to be weaker and tighter than for the one above, with the degree of fracturing of the metasiltstones far lower. The third interval, from 2436m-2443m, was again seen with the vein quartz and juxtaposed host rock, and also to a minor degree with the slickensiding. It too was weaker than the first interval.

There was a final show seen from 2457m to 2460m, that had a trace patchy pale yellow fluorescence, dull milky yellowish-white crush cut and thick ring residue. (Gas values were as follows:- total gas maximum was 21 units, and C = 77/8/9/5/1).

The wireline logs were analyzed over the interval 2300-2400m. No pay was identified in this section, which included the basal 60m approximately of the Casterton Formation, plus 40m into the fractured metasediments forming the basement.

Two drill stem tests were conducted, the first from 2390-2461m, the second a re-run of the first, as a result of packer failure, from 2389.5-2461m, in the basement. From DST #1 there was a recovery of 6bbls of oil cut rathole and annulus mud, and from DST #2 1bbl of oil cut water plus 15bbls of muddy water. The flow rate calculated from recovery charts was 47bbls a day.

The Gordon-1 well had been classed as a wildcat gas exploration well, and following drill stem tests was plugged and suspended for possible re-entry, and sidetrack for potential oil in the fractured basement.

#### 4. **SUMMARY**

Gordon-1 was drilled as a (WCNF) gas exploration well within PEP 119, situated near the western border of Victoria. The well is situated on the northeastern flank of the Penola Trough, within the Otway Basin. Gordon was spudded on April 15<sup>th</sup>, total depth of 2505m RT reached on April 27<sup>th</sup>, and the ODE Rig #30 released on May 3<sup>rd</sup>, 1997.

The well was a technical success, drilled and completed in a matter of 18 days, including wireline logging and two drill stem tests.

The primary target of the Early Cretaceous McEachern sandstone, at the base of the Pretty Hill Formation, was deduced not to have been present in the well. The sandstone was predicted to occur at 2278.3m RT, and to be 109m in thickness. This sand unit was penetrated by the McEachern-1 nearby, 9.5km south southeast of Gordon, but probably has only a limited lateral extent, and there appear to be many facies changes between wells within the Pretty Hill Formation. Correlation from well to well in this part of the Penola Trough, in western Victoria, is difficult and somewhat tenuous due to the low density of wells.

Reservoir is a significant risk in the central part of the Penola Trough. It has been discovered that sand development within the Crayfish Group is to some degree localized and cannot be mapped accurately, either geophysically or geologically over any great distance (McGee, 1996).

All the remaining formations were intersected as on prognosis, though the older units were high to that predicted. The Eumeralla and Laira formations, however, were merely 2.6m high and 3.4m low, respectively. The underlying formations, the Pretty Hill, was 143.6m high, and the Casterton 269.6m high. Basement at Gordon was intersected high, at 2361m RT, but expected lower at 2450m, thus there was an 89.6m difference.

During the drilling of the well, no significant gas shows or peaks were recorded, until within the Pretty Hill Formation, at 1641m and again at 1771m, where thin, 4m, sandstone beds exhibited trace, patchy fluorescence. These were both assessed at the wellsite to be oil shows of a residual nature. In the underlying Casterton Formation, between 2195-2212m, in a 17m thick section of fine-grained sandstone with very low porosity, was a live oil show, with a trace to 1% patchy fluorescence.

Basement, a greenish-grey metasiltstone, was drilled into at 2361m RT. Forty metres below, live oil shows were recorded, associated with fracturing, quartz veining and the adjacent host metasediments, from 2401-2410m. An almost continuous show was documented down to 2443m, then again from 2457-2460m. The first 10m displayed the strongest fluorescence and cut, and below became weaker and more tight, with the degree of fracturing of the host rock far lower. This interval was deemed to be of sufficient interest to be tested. Following wireline logging, including running sidewall cores (2485m-1035m) and Formation Microscanner Image (FMI) over the zone of interest, DST #1 was conducted over the interval 2388-2459m(L). The packer failed after 17 minutes into the second flow, with no flow to surface, but there was a recovery of 6bbls of oil cut mud. A second test, DST #2, was tried over the same section, but once again there was packer seat failure, this time after 216 minutes. Recovery was 1bbl of oil cut mud and 7bbls of muddy water. A sample from the first test was analyzed to be crude oil with an API of 38° API, at 60°F, with a pour point of 36°.

As a result of the oil discovered in the fractured basement, the Gordon-1 well was plugged and suspended. According to future market demand, financial viability and oil pricing, plus additional rigorous reservoir studies, this well could possibly be re-entered and sidetracked for the potential oil.

#### 5. REFERENCES

Akbari, V. 1990 McEachern-1 Well Completion Report, Volume 1. Gas and Fuel Exploration N.L., PEP 119, Otway Basin. May, 1990. Unpublished Report.

APG Consultants, 1997 Biostratigraphic Report for the Gordon-1 well. Unpublished Report.

Cockshell, C.D., Perincek, D., Finlayson, D.M., Pettifer, G.R., and Hill, K.A., 1994 Key horizon mapping and spatial basin evolution. *In* Finlayson, D.M. (compiler), 1994. NGMA/PESA Otway Basin Symposium, Melbourne, 20 April, 1994: extended abstracts. AGSO Record 1994/14. pp. 19-26

Finlayson, D. M. (compiler), 1994 NGMA/PESA Otway Basin Symposium, Melbourne, 20 April 1994: extended abstracts. AGSO, Record 1994/14.

Hill, A. J., 1995 Source Rock Distribution and Mature Modelling, *in* Petroleum Geology of South Australia, Chapter 7, Volume 1: Otway Basin. Mines and Energy, South Australia. Morton, J.G.G., and Drexel, J.F., (eds) pp. 103-125.

Lavin, C., 1997 A Review of the Prospectivity of the Crayfish Group in the Victorian Otway Basin. APPEA JOURNAL 1997, Volume 37, Part 1; pp. 232-244.

Lavin, C., and Muscatello, 1997 Petroleum Prospectivity - The Casterton Petroleum System. VIMP REPORT 41, pp. 24-27

Lovibond, R., Suttill, R.J., Skinner, J.E., and Aburas, A.N., 1995 The Hydrocarbon Potential of the Penola Trough, Otway Basin. APEA JOURNAL 1995, Volume 35, Part 1; pp.358-371.

McGee, A., 1996 Gordon-1 Well Proposal. Exploration and Development - S.A., Otway Team Santos Ltd. (TMOC). Unpublished Report.

Morton, J.G.G., Hill, A.J., Parker, G., and Tabassi, A., 1994 Towards a Unified Stratigraphy for the Otway Basin. Extended Abstracts, NGMA/PESA Otway Basin Symposium, AGSO Record 1994/14 pp. 7-12

Morton, J.G.G., Alexander, E.M., Hill, A.J. and White, M.R., 1995 Lithostratigraphy and Environments of Deposition. *In* Petroleum Geology of South Australia, Volume 1, Otway Basin. (eds.) J.G.G. Morton and Drexel, J. F. pp. 47-94

Pietsch, A.P. and Horner, D., 1997 Gordon-1 Raw Data Report. Santos Ltd. - Cultus Petroleum N.L. July 1997. Unpublished Report.

Richardson, B., 1997 Gordon-1 Drilling and Evaluation Programme. March 1997. TMOC Exploration Ltd.,--Cultus Petroleum N.L. 1997 Unpublished Report.

Sprigg, R.C., 1986 A history of the search for commercial hydrocarbons in the Otway Basin complex. *In* Glenie, R.C. (ed.) 2<sup>nd</sup> South-eastern Australia Oil Exploration Symposium, Melbourne, 1985. Technical papers. PESA pp. 173-200

**APPENDIX I: PART 1: LITHOLOGICAL DESCRIPTIONS** 

Ditch cuttings were collected, washed, described, and checked for fluorescence at 10m intervals from the surface to 9 5/8" casing point at 656m, thereafter at 5m intervals from the casing shoe to 1300m, and then at 3m intervals to total depth at 2505m.

#### **HEYTSBURY GROUP**

#### **Undifferentiated Tertiary**

(35m thick)

Spud-40m

SANDSTONE: (100%) orange brown, very fine to coarse, dominantly medium, occasional very coarse to grit size grains, angular to subangular, poor to moderately sorted, strong orange iron oxide cement in part - decreasing with depth, common light orange to dark brown argillaceous and silt matrix in part, clear to occasionally orange quartz grains, trace to common coarse muscovite flakes, trace black to dark brown fibrous carbonaceous matter, unconsolidated to occasionally hard, very good inferred porosity, no oil fluorescence, With minor interbedded: CLAYSTONE: (trace) dark brown, minor dispersed very fine to medium quartz sand grains, trace to common black fibrous carbonaceous matter, very soft, very dispersive, non fissile.

#### 40-1150m OTWAY GROUP

# Eumeralla Formation (Early Cretaceous - *i.e* Aptian to Albian) (1110m thick)

40-92m

CLAYSTONE: (95%) medium olive grey to medium green grey, light to medium brown grey, occasionally dark green grey, slightly to occasionally very silty, common very fine partially altered feldspar grains in part, trace black carbonaceous detritus, trace micromica, soft, non fissile,

Finely interbedded and laminated in part with:

SANDSTONE: (5%) medium grey to medium green grey, very fine to dominantly fine, angular to subrounded, dominantly subangular, moderately sorted, weak to moderate silica cement, weak calcareous cement in part, abundant medium olive grey argillaceous and silt matrix, abundant altered feldspar grains, common to abundant grey green and red lithics, trace black coaly detritus, trace mica flakes, friable, no visible porosity, no oil fluorescence

92-476m

CLAYSTONE: (90%) medium green grey to medium olive grey, medium brown, very silty in part, common very fine altered feldspar grains where silty, trace black carbonaceous flecks and detritus, trace coarse brown and green mica flakes, trace to common micromica, trace pyrite, firm, non fissile,

In part grading to:

SILTSTONE: light to medium grey, light to medium olive grey, very argillaceous, often very finely arenaceous and grading to silty sandstone, trace to common black carbonaceous detritus and flecks, slightly calcareous in part, trace micromica, soft to firm, non fissile,

Finely interbedded with, laminated with and in part grading to:

SANDSTONE: (10%) medium green grey, very fine to medium, dominantly fine, angular to subangular, moderately sorted, moderate silica and calcareous cements, common green white argillaceous matrix, common to abundant altered feldspar grains, abundant green grey lithics, trace black carbonaceous detritus often with associated pyrite, trace coarse brown and green mica flakes, trace pyrite, moderately hard, no visible porosity, no oil fluorescence.

476-656m (csg pt.)

CLAYSTONE: (60%) medium olive grey to medium grey, occasionally light to medium brown, occasionally medium green grey, very silty in part, trace black carbonaceous flecks and detritus, trace pyrite, trace micromica, firm, slightly subfissile, Grading to:

SILTSTONE: (30%) light to medium grey, light to medium olive grey, often very finely arenaceous with quartz, altered feldspar and grey green and red lithics, trace black carbonaceous detritus, trace micromica, firm, slightly subfissile,

Grading to, laminated and interbedded with:

SANDSTONE: (10%) light brown to light to medium green grey to medium grey, very fine to dominantly fine, rarely medium, angular to subrounded, moderately sorted, strong silica and calcareous cements in part, abundant medium olive grey argillaceous and silt matrix in part, abundant altered feldspar, abundant grey green and red lithics, trace to common black coaly detritus, trace mica flakes, friable to hard, no visible porosity, no oil fluorescence.

656-659m

SANDSTONE: (100%) off white to medium brown grey, very fine - rarely fine, angular to subrounded, moderately sorted, strong calcareous cement, abundant white argillaceous matrix in part, abundant medium grey silt matrix in part, common green grey and red lithics, common black carbonaceous matter, trace micromica, moderately hard, no visible porosity, no oil fluorescence.

659-790m

CLAYSTONE: (60%) medium olive grey to medium grey to medium brown grey, very silty in part, common black carbonaceous detritus, trace micromica, firm, slightly subfissile,

Grading to:

SILTSTONE: (30%) medium grey to medium brown grey, very argillaceous, often very finely arenaceous, common partially altered feldspar grains in part, common black carbonaceous detritus and flecks, firm, slightly subfissile,

Grading in part to and occasionally interbedded with:

SANDSTONE: (100%) off white to medium brown grey, very fine to rarely fine, angular to subrounded, moderately sorted, strong calcareous cement, abundant white argillaceous matrix in part, abundant medium grey silt matrix in part, common green grey and red lithics, common black carbonaceous matter, trace micromica, moderately hard, no visible porosity, no oil fluorescence

790-835m

CLAYSTONE: (30%) medium olive grey, light to medium grey, light to medium brown grey, very silty in part, common black carbonaceous flecks and detritus, trace micromica, firm, slightly subfissile,

Grading to:

SILTSTONE: (40%) medium grey to medium brown grey, very argillaceous, often very finely arenaceous, common partially altered feldspar grains in part, common black carbonaceous detritus and flecks, firm, slightly subfissile,

Grading in part to and interbedded with:

SANDSTONE: (30%) off white to light grey, very fine to fine, in part with abundant coarse to very coarse quartz grains, angular to subrounded, dominantly subangular, poor to moderately sorted, moderate to strong silica and calcareous cements, abundant white argillaceous matrix, occasionally abundant medium grey argillaceous and silt matrix, common grey green lithics, trace red brown lithics, trace black carbonaceous matter, friable to hard, no to very poor inferred porosity, no oil fluorescence.

835-955m

CLAYSTONE: (40%) light green to medium olive grey, light to medium grey, light to medium brown grey, very silty in part, common black carbonaceous flecks and detritus, trace micromica, firm, slightly subfissile,

Grading to:

SILTSTONE: (40%) medium grey to medium brown grey, very argillaceous, often very finely arenaceous with partially altered feldspar and quartz grains, common black carbonaceous detritus and flecks, firm, slightly subfissile,

Grading in part to and interbedded with:

SANDSTONE: (20%) off white to medium brown grey, very fine to rarely fine, angular to subrounded, moderately sorted, strong calcareous cement, abundant white argillaceous matrix in part, abundant medium grey silt matrix in part, common green grey and red lithics, common black carbonaceous matter, trace micromica, moderately hard, no visible porosity, no oil fluorescence

955-1027m

CLAYSTONE: (60%) medium olive grey to medium grey to light to medium brown grey, very silty in part, trace to occasionally abundant black carbonaceous flecks and detritus, trace micromica, firm, slightly subfissile,

Grading to:

SILTSTONE: (30%) medium grey to medium brown grey, very argillaceous, often very finely arenaceous with partially altered feldspar and quartz grains, trace to occasionally abundant black carbonaceous detritus and flecks, firm, slightly subfissile, Grading in part to and interbedded with:

SANDSTONE: (10%) off white to medium brown grey, very fine to fine, angular to subrounded, moderately sorted, strong calcareous cement, abundant white argillaceous matrix in part, abundant medium grey silt matrix in part, common green grey and red lithics, common black carbonaceous matter, trace micromica, moderately hard to hard, no visual porosity, no oil fluorescence,

With minor laminated and thinly interbedded:

COAL: (trace) black, blocky fracture, earthy to subvitreous lustre, dark brown and very argillaceous in part, hard, brittle

1027-1092m

CLAYSTONE: (50%) off white to medium brown, medium olive grey to medium grey, very silty in part, trace to occasionally abundant black carbonaceous flecks and detritus, trace micromica, firm, slightly subfissile,

Grading to:

SILTSTONE: (30%) off white to medium brown to medium grey, very argillaceous, often very finely arenaceous with partially altered feldspar and quartz grains, trace to occasionally abundant black carbonaceous detritus and flecks, firm, slightly subfissile, Grading in part to and interbedded with:

SANDSTONE: (10%) off white to light brown, very fine to fine, angular to subrounded, moderately sorted, strong calcareous cement, abundant white argillaceous matrix in part, common green grey and trace red lithics, common black carbonaceous matter, trace micromica, moderately hard to hard, no visible porosity, no oil fluorescence,

With occasional laminated and thinly interbedded:

COAL: (10%) black, blocky fracture, earthy to subvitreous lustre, dark brown and very argillaceous in part, hard, brittle micromica, moderately hard to hard, no visible porosity, no oil fluorescence,

With occasional laminated and thinly interbedded:

COAL: (10%) black, blocky fracture, earthy to subvitreous lustre, dark brown and very argillaceous in part, hard, brittle.

1092-1150m

CLAYSTONE: (60%) light to medium olive grey, light to medium brown grey, very silty in part, trace black carbonaceous flecks, common black coal detritus in part, trace micromica, firm to moderately hard, subfissile,

Grading to:

SILTSTONE: (30%) off white to light brown to medium grey to medium olive grey, very argillaceous, often very finely arenaceous with partially altered feldspar grains, trace black carbonaceous flecks, trace to common black coal detritus, trace micromica, firm to moderately hard, subfissile,

Grading to, laminated with and finely interbedded with:

SANDSTONE: (10%) off white to light brown, very fine to fine, dominantly very fine, rare clear medium to very coarse quartz grains, angular to subrounded, dominantly subangular, moderately sorted, moderate to strong silica and calcareous cements, trace strong dolomite cement, abundant white argillaceous matrix, common grey green lithics, trace red brown lithics, common to abundant off white partially altered feldspar grains, trace coal detritus, hard, no visible porosity, no oil fluorescence.

### 1150-2118m 1150-1517m

### **CRAYFISH GROUP**

## <u>Laira Formation (E. Cret.—i.e. Valanginian - Hauterivian)</u> (367m thick)

1150-1350m

CLAYSTONE: (60%) medium brown grey to medium olive grey to medium grey, very silty in part, trace black carbonaceous flecks and coal detritus, trace micromica, firm to moderately hard, subfissile,

Grading to:

SILTSTONE: (30%) medium brown grey to medium olive grey to medium grey, very argillaceous, often very finely arenaceous with partially altered feldspar grains, trablack carbonaceous flecks and coal detritus, trace micromica, firm to moderately hard, subfissile,

Grading to, laminated with and finely interbedded with

SANDSTONE: (10%) off white to light brown, very fine to fine, dominantly very fine, rare clear medium to very coarse quartz grains, angular to subrounded, dominantly subangular, moderately sorted, moderate to strong silica and calcareous cements, trace strong dolomite cement, abundant white argillaceous matrix, common grey green lithics, trace red brown lithics, common to abundant off white partially altered feldspar grains, trace coal detritus, hard, no visible porosity, no oil fluorescence.

1350-1517m

CLAYSTONE: (70%) light to medium brown grey to medium grey to medium olive grey, occasionally very silty, trace black carbonaceous flecks, common to occasionally abundant dark brown to black coaly material, trace micromica, firm to moderately hard, subfissile,

Grading to:

SILTSTONE: (20%) medium brown grey to medium grey to medium olive grey, very argillaceous, occasionally very finely arenaceous with partially altered feldspar grains, trace black carbonaceous flecks, common dark brown to black coaly material, trace micromica, firm to moderately hard, subfissile,

Grading in part to, laminated with and finely interbedded with:

SANDSTONE: (10%) off white, very fine to occasionally medium, dominantly very fine, angular to subrounded, dominantly subangular, moderately sorted, moderate to strong silica and calcareous cements, common to abundant white argillaceous matrice grey green and red brown lithics, trace garnet, trace to common coaly detritus, friable to hard, no to poor inferred porosity, no oil fluorescence.

# 1517-2118m <u>Pretty Hill Formation (E. Cret.—i.e. Berriasian to Valanginian)</u> (601m thick)

1517-1549m

CLAYSTONE: (30%) light to medium brown grey to medium grey to medium olive grey, occasionally very silty, trace black carbonaceous flecks, common to occasionally abundant dark brown to black coaly material, trace micromica, firm to moderately hard, subfissile,

Grading to:

SILTSTONE: (10%) medium brown grey to medium grey to medium olive grey, very argillaceous, occasionally very finely arenaceous with partially altered feldspar grains, trace black carbonaceous flecks, common dark brown to black coaly material, trace micromica, firm to moderately hard, subfissile,

Grading in part to, laminated with and finely interbedded with:

SANDSTONE: (60%) off white, very fine to coarse, dominantly fine to medium, angular to subrounded, dominantly subangular, moderately sorted, moderate silica and calcareous cements, common to abundant white argillaceous matrix, trace grey green and red brown lithics, trace garnet, trace black to dark brown coaly detritus, friable to moderately hard, very poor to fair inferred porosity, no oil fluorescence.

1549-1751m

SANDSTONE: (90%) off white to very light grey to light brown, dominantly off white, very fine to coarse, dominantly medium, trace very coarse to grit sized grains in part, angular to subangular, moderate to strong silica cement, weak calcareous cement, occasionally moderate dolomite cement, common white to occasionally light brown argillaceous matrix, clear to opaque quartz grains, common pink to red garnet, trace green grey cherty lithics, trace medium green volcanogenic lithics, trace medium grey phyllitic lithics, trace black coal detritus, moderately hard, poor to dominantly fair visible porosity,

Interbedded and laminated with:

SILTSTONE: (5%) medium grey to medium brown grey, moderately to very argillaceous, common very fine off white partially altered feldspar grains in part, trace black carbonaceous flecks, common micromica, moderately hard, very dispersive, subfissile

Grading in part to

CLAYSTONE: (5%) medium grey to medium brown grey, moderately to very silty, trace black carbonaceous flecks, common micromica, moderately hard, very dispersive, subfissile.

1751-1839m

SANDSTONE: (80%) off white to light grey, very fine to very coarse, dominantly medium, angular to subangular, poorly sorted, moderate silica cement, weak to moderate calcareous cement, trace strong brown dolomite cement, common white argillaceous matrix, common pink to red garnet, trace to common grey to green phyllitic and volcanogenic lithics, trace black coaly detritus, moderately hard, poor to fair visible porosity,

Interbedded and in part laminated with:

SILTY CLAYSTONE: (20%) medium brown grey to medium grey, occasionally dark grey and shaley, trace very fine off white partially altered feldspar grains in part, trace to common black carbonaceous flecks and coaly detritus, common micromica, firm to moderately hard, very dispersive, subfissile.

1839-1990m

SANDSTONE: (75%) off white to light grey, very fine to very coarse, dominantly fine, angular to subangular, very poorly sorted, moderate to strong silica cement, weak calcareous cement, trace strong brown dolomite cement, common to occasionally abundant white argillaceous matrix, trace to common pink to red garnet, common green phyllitic and volcanogenic lithics, trace brown mica flakes, trace black coally detritus, moderately hard to hard, very poor to fair visible porosity,

Interbedded and laminated with:

SILTY CLAYSTONE: (25%) medium brown to medium grey, occasionally dark grey and shaley, occasionally dark brown and very carbonaceous, trace very fine off white partially altered feldspar grains in part, trace to common black carbonaceous flecks and coaly detritus, trace fine brown mica flakes, common micromica, firm to moderately hard, very dispersive, subfissile.

1990-2118m

SANDSTONE: (95%) off white to light grey, very fine to very coarse, dominantly fine, angular to subangular, poorly sorted, moderate to strong silica cement, weak calcareous cement, common white argillaceous matrix, trace to common pink to red garnet, common grey to green phyllitic and volcanogenic lithics in general increasing with depth, trace black coaly detritus, moderately hard to hard, poor to fair visible porosity, no oil fluorescence,

Interbedded and laminated with:

SILTY CLAYSTONE: (5%) medium brown to medium grey, occasionally dark grey and shaley, trace very fine off white partially altered feldspar grains in part, trace to common black carbonaceous flecks and coaly detritus, trace fine brown mica flakes, common micromica, moderately hard, very dispersive, subfissile.

# 2118-2361m <u>Casterton Formation (Late Jurassic to E. Cret.—i.e. Kimmeridgian to Berriasian)</u> (243m thick)

2118-2212m

SILTSTONE: (75%) medium brown grey to dominantly dark grey, slightly to moderately argillaceous, common to abundant off white very fine partially altered feldspar grains in part, common black carbonaceous flecks, trace black coaly laminae, common micromica, moderately hard, subfissile,

Grading to and in part laminated with:

SANDSTONE: (25%) off white to medium brown grey to medium grey, silty to very fine, angular to subangular, moderately sorted, strong silica cement, weak to occasionally moderate calcareous cement, common off white argillaceous matrix, abundant medium grey silty matrix in part, abundant off white very fine partially altered feldspar grains, common fine clear to brown mica flakes, common very fine grey to brown lithics, common very fine black carbonaceous grains and detritus, hard, no to occasionally very poor visible porosity.

2212-2230m

SILTY CLAYSTONE: (100%) medium to dark brown to medium to dark grey, very silty grading in part to siltstone, common very fine partially altered feldspar grains where very silty, common very fine brown and clear mica flakes, moderately carbonaceous, common black carbonaceous flecks and coaly detritus, moderately hard, subfissile.

2230-2343m

SILTY CLAYSTONE: (70%) dark brown grey to dark grey, moderately carbonaceous, common black carbonaceous flecks, trace black coaly detritus, common micromica, moderately hard, subfissile,

Grading to:

ARGILLACEOUS SILTSTONE: (28%) medium to dark brown grey to dark grey, moderately carbonaceous, common black carbonaceous flecks, trace black coaly detritus, abundant off white very fine partially altered feldspar and quartz grains in part, common micromica, moderately hard, subfissile.

Grading to and laminated with:

SANDSTONE: (2%) light to medium brown grey, silty to very fine, angular to subangular, moderately sorted, strong silica cement, common to abundant white to dark brown grey argillaceous and silt matrix, abundant very fine partially altered feldspar grains, common grey green and brown lithics, common very fine to fine brown and clear mica flakes, hard, no visible porosity, no oil fluorescence.

2343-2361m

COAL: (25%) black to very dark grey, very argillaceous and silty in part, subconchoidal to platy fracture, subvitreous lustre where pure, earthy where argillaceous, hard, brittle,

Interbedded and laminated with and grading to:

SILTY CLAYSTONE: (55%) dark brown grey to dark grey to grey black, moderately to very carbonaceous, common black carbonaceous flecks, common micromica, moderately hard, subfissile,

Grading to:

ARGILLACEOUS SILTSTONE: (20%) medium to dark brown grey to grey black, moderately to very carbonaceous, common black carbonaceous flecks, abundant off white very fine partially altered feldspar and quartz grains in part, common micromica, moderately hard, subfissile,

Grading to and in part laminated with:

SANDSTONE: (trace) light to medium brown grey, silty to very fine, angular to subangular, moderately sorted, strong silica cement, common to abundant white to dark brown grey argillaceous and silt matrix, abundant very fine partially altered feldspar grains, common grey green and brown lithics, common very fine to fine brown and clear mica flakes, hard, no visible porosity, no oil fluorescence

### 2361-2505m T.D.

## <u>Metamorphic Basement (Palaeozoic)</u> (144m thick)

2361-2411m

METASILTSTONE: (100%) weathered in part at top to white clay, very light grey to light green, becoming medium to dark green grey with depth, often with fine to medium grained brown to black inclusions with diffuse grain boundaries, very siliceous, slightly to occasionally moderately calcareous, nil to occasionally common very coarsely crystalline vein quartz, trace pyrite, abundant micromica, hard, fissile.

2411-2436m

METASILTSTONE: (100%) light to dark olive grey, dominantly medium olive grey, siliceous, slightly calcareous and ankeritic, trace fine to medium brown mineral regrowth inclusions with diffuse grain boundaries, minor coarsely crystalline vein quartz, common pyrite, common micromica, earthy to often phyllitic sheen, minor slickensides, hard, fissile.

2436-2505m T.D. METASILTSTONE: (100%) medium grey to medium olive grey, siliceous to microcrystalline texture, trace diffuse brown micaceous mineral growths, slightly to moderately calcareous and ankeritic, common slickensides often with ankeritic lining, common coarsely crystalline quartz fracture and vein infilling, common disseminate and nodular pyrite, common micromica, hard, fissile.

Note: See Hydrocarbon Show Summary for fluorescence in metasediments.

**APPENDIX II: SIDEWALL CORE DESCRIPTIONS** 

### SANTOS LIMITED

### SIDEWALL CORE DESCRIPTION

WELL: GORDON-1 DATE: 29<sup>th</sup> April 1997 PAGE: 1 of 3

**GUN NOs.:** 1 & 2 **SHOTS FIRED:** 60 **SHOTS BOUGHT:** 56

**GEOLOGIST:** David Horner

CORE NO.	DEPTH	REC.	PALYN. EVAL. REJECT	LITH.	COLOUR	GRAIN SIZE	HYDR. INDIC. (Y/N)	SUPPLEMENTARY INFORMATION
1	2485.0	-						Empty
2	2465.0	19		Metaslt	Lt-m gy	Slt-vf	n	Lt-m gy,slt-vf xln text,v calc,hd
3	2452.0	-	Eval					Empty
4	2446.75	18	Eval	Metaslt	Lt-m gy	Slt-vf	n	Lt gy-m blu gy,slt-vf xln text,abt mmic,m calc,wh flks,hd
5	2429.25	13	Eval	Metaslt	Lt-m gy	Slt-vf	n	Lt gy-m blu gy,slt-vf xln text,abt mmic,sl calc,wh flks,hd
6	2426.5	-	Eval					Empty
7	2400.0	20	Eval	Metaslt	Lt-m blu gu,lt brn	Slt-vf	n	Lt-m blu gy,lt brn,slt-vf xln text,wk-m calc,com mmic,hd
8	2380.0	22		Metaslt	Lt-m blu gu,lt brn	Slt-vf	n	Lt-m blu gy,lt brn,slt-vf xln text,wk-m calc,com mmic,hd
9	2370.0	27		Metaslt	Lt-m blu gy,lt brn	Slt-vf	n	Lt blu grn,lt-m blu gy,lt brn,slt-vf xln text,non calc,tr mmic,hd
10	2359.0	38	Coal Mark	Carb sltst	Dk brn-brn bk	Slt-cly	n	m-dk brn,frm,v carb,v arg,v slty,com mmic,frm,sbfis
11	2356.25	36	Eval	Carb sltst	Brn bk	Slt-cly	n	Brn bk,v carb & coaly,tr mmic,non calc,tr wh veins,frm,sbfis
12	2350.0	40	Eval	Arg sltst	Dk brn	Slt-cly	n	Dk-v dk brn,mod carb,tr mmic,non calc,frm,sbfis
13	2345.25	26		Arg sltst	M gy-m brn	Slt-cly	n	M gy-m brn,off wh i/p,mod carb,sft- frm,tr mmic,sl sbfis
14	2337.5	22	Eval	Arg sltst	M-dk brn	Slt-cly	n	m-dk brn,v arg,mod carb,tr-v mmic,frm,sbfis
15	2325.0	25		Arg sltst	m brn	Slt-cly	n	m-dk brn,v arg,mod carb,tr-v mmic,frm,sbfis
16	2295.5	21		Sst/ sltst	Wh,m-dk brn	Slt-vf	n	Wh,m-dk brn,slt-vf,a-sa,m srt,wk sil cmt,non calc,frm,no vis por
17	2270.0	22		Arg sltst	Dk brn	Slt-cly	n	Dk brn,v arg grdg to clyst,non calc,com mmic,sft-frm,sl sbfis
18	2235.0	22		Arg sltst	Dk brn	Slt-cly	n	Dk brn,v arg grdg to clyst,non calc,com mmic,sft-frm,sl sbfis
19	2215.0	19		Sltst/ sst	Lt-m brn	Slt-vf	n	Lt-m brn,slt-vf,a-sa,m srt,wk sil cmt,non
20	2205.0	15		Sltst/ sst	Lt-m brn	Slt-vf	n	calc,v arg i/p,sft-frm,com mmic,sl sbfis  Lt-m brn,slt-vf,a-sa,m srt,wk sil cmt,non
21	2196.6	33	Eval	Sst	Off wh-lt gy	Vf-f	n	calc,v arg i/p,sft-frm,com mmic,sl sbfis  Off wh-lt gy,vf-f,w srt,sa-sr,wk calc cmt,mod sil cmt,abt wh arg mtx,fri,v pr
22	2195.25	28	Eval	Sst	Off wh-lt gy	Vf-f	n	vis por  Off wh-lt gy,vf-f,w srt,sa-sr,wk calc cmt,mod sil cmt,abt wh arg mtx,abt med- dk gy arg & slt mtx, tr multicolor liths, tr mmic,fri,v pr vis por
23	2197.75	16	Eval	Sst	Off wh-lt gy	Vf-f	n	Off wh-lt gy,vf-f,w srt,sa-sr,wk calc cmt,mod sil cmt,abt wh arg mtx,abt meddk gy arg & slt mtx, tr multicolor liths, tr mmic,fri,v pr vis por

WELL:

GORDON-1

**DATE:** 

29<sup>th</sup> April 1997

2of 3

**GUN NOs.:** 

1 & 2

SHOTS FIRED:

60

**SHOTS BOUGHT:** 56

PAGE:

6

**GEOLOGIST:** 

David Horner

CORE NO.	DEPTH	REC.	PALYN. EVAL. REJECT	LITH.	COLOUR	GRAIN SIZE	HYDR. INDIC. (Y/N)	SUPPLEMENTARY INFORMATION
24	2187.5	21		Sst	Off wh-lt gy	Vf-f	n	Off wh-lt gy,vf-f,w srt,sa-sr,wk calc cmt,mod sil cmt,abt wh arg mtx,abt meddk gy arg & slt mtx, tr multicolor liths, tr mmic,fri,v pr vis por
25	2160.25	24		Sltst	Lt-m brn gy	Slt-vf	n	Lt-m gy brn,vf aren grdg to vf sst,tr mmic,frm,sbfis
26	2128.5	18		Sltst	Lt-m brn gy	Slt-vf	n	Lt-m gy brn,vf aren grdg to vf sst,tr mmic,frm,sbfis
27	2126.0	24		Sltst	Lt-m brn gy	Slt-cly	n	Lt-m gy brn,v arg grdg to clyst,tr mmic,frm,sbfis
28	2076.5	12		Sst	Off wh	f-m	n	Wh,clr-trnsl qtz,sa-sr,m srt,m sil cmt,tr wh arg mtx,fri,fr vis por
29	2057.5	22		Sst	Off wh-lt gy-lt brn	f-m	n	Wh,clr-trnsl qtz,sa-sr,m srt,m sil cmt,tr- com wh & brn arg mtx,fri,fr vis por
30	2030.75	19		Sst	Off wh	f-m	n	Wh,clr-trnsl qtz,sa-sr,m srt,m sil cmt,wk calc cmt, tr wh arg mtx,fri,fr vis por
31	2008.75	25		Sst	Wh-lt gy	f-c	n	Wh-lt gy,f-c,dom m,m-w srt,a-sa,wk calc cmt,com wh arg mtx,fri,pr vis por
32	1989.5	35		Sst	Wh-lt gy	f-c	n	Wh-lt gy,f-c,dom m,m-w srt,a-sa,wk calc cmt,com wh arg mtx, tr dk gy slt incl, tr liths,pr vis por
33	1920.5	41		Sst	Wh-lt gy	f-c	n	Wh-lt gy,f-c,dom m,m-w srt,a-sa,wk ca cmt,com wh arg mtx, tr dk gy slt incl, tr liths,pr vis por
34	1899.0	25		Sst	Wh-lt gy	vf-c	n	Wh-lt gy,vf-c,dom f-m,sa-r,pr srt,str calc cmt,com wh arg mtx,tr liths,clr qtz grs,fri,pr vis por
35	1895.0	31		Sst	Lt-m gy	Vf-c	n	Lt-m gy,vf-c,dom m,sa-sr,m-w srt,wk ealc cmt,mod sil cmt,abt wh arg mtx,fri,pr vis por
36	1882.0	37		Sltst	m-dk brn	Cly-vf	n	m-dk brn,vf aren i/p,v arg i/p,frm,sl sbfis
37	1871.5	29		Sst	Lt-m gy	Vf-c	n	Lt-m gy,vf-c,dom m,sa-sr,m-w srt,wk calc cmt,mod sil cmt,com wh arg mtx,com m brn gy arg & slt mtx, fri,pr vis por
38	1810.0	26		Sst/Cly	Lt-m gy	Vf-c	n	Lt-m gy,vf-c,dom m,sa-sr,m-w srt,wk calc cmt,mod sil cmt,com wh arg mtx,abt m brn gy arg & slt mtx grdg to clyst, fri,pr vis por
39	1768.0	39		Clyst	Lt-dk gy	Cly-vf	n	Lt-dk gy,vf aren i/p grdg to vf sst,frm- hd,non fis
40	1761.0	38		Sltst/ sst	Lt-m brn gy	Cly-vf	n	Lt-m gy brn, vf aren i/p grdg to vf sst,frm-hd,non fis
41	1749.5	-			1 87			Lost Bullet
42	1680.0	28		Sst	Wh-lt gy	Vf-m	n	Wh-lt gy,vf-m,dom f,sa-sr,pr srt,mod sil cmt,abt wh arg mtx,mod hd,v pr vis por
43	1614.0	36	<del>-</del>	Sltst	Lt-m brn gy	Slt-vf	n	Lt-m gy brn,vf aren grdg to slty sst,com mmic,frm,sl sbfis
44	1593.25	38		Sltst	M brn-m gy	Cly-vf	n	M brn,m gy,wh,v arg i/p,vf aren i/p grd to vf sst,(laminated),frm,non fis
45	1558.0	30	Eval mark	Sst	Wh	m	n	Wh,m,sa-sr,w srt,mod sil cmt,tr wh mtx,clr qtz grs,tr garn,fri-hd,gd vis por
46	1549.0	32		Sltst/ sst	Lt-m gy brn	Cly-vf	n	Lt-m gy brn,v arg,vf aren grdg to sst,frm,sl sbfis
47	1536.0	31		Sltst	m-dk brn, dk gy	Cly-sst	n	m-dk brn,dk gy,v arg,vf aren grdg to sst,sft-frm,sl sbfis

WELL: GORDON-1 DATE: 29<sup>th</sup> April 1997 PAGE: 3of 3

GUN NOs.: 1 & 2 SHOTS FIRED: 60 SHOTS BOUGHT: 56

GEOLOGIST: David Horner

CORE NO.	DEPTH	REC.	PALYN. EVAL. REJECT	LITH.	COLOUR	GRAIN SIZE	HYDR. INDIC. (Y/N)	SUPPLEMENTARY INFORMATION
48	1510.0	32		Sltst	m-dk brn, dk gy	Cly-sst	n	m-dk brn,dk gy,v arg,vf aren grdg to sst,sft-frm,sl sbfis
49	1482.5	40		Sltst	Lt-m gy	Cly-vf	n	Lt-m gy,v arg,vf aren grdg to vf sst,frm,sl sbfis
50	1428.0	46		Sltst	Lt-m brn gy	Cly-vf	n	Lt-m gy,v arg,vf aren grdg to vf sst,frm,sl sbfis
51	1413.5	37		Sltst	Lt-m gy	Cly-vf	n	Lt-m gy,mod arg,vf aren grdg to vf sst,frm,sl sbfis
52	1369.0	33		Sltst	Lt-m gy	Cly-vf	n	Lt-m gy,v arg,vf aren grdg to vf sst,frm,sl sbfis
53	1275.0	33		Sltst	Lt-m brn gy	Cly-vf	n	Lt-m gy brn,v arg,vf aren grdg to slty sst,frm,sl sbfis
54	1211.0	41		Sltst/ clyst	Lt-dk gy,m brn	Cly-slt	n	Lt-dk gy,m brn,v arg grdg to clyst,sl calc,frm,sl sbfis
55	1184.5	32		Clyst	M gy brn	Cly-slt	n	M gy brn,v slty grdg to sltst,com mmic,frm,sl sbfis
56	1149.5	26		Sst	Lt-m gy, med brn	vf	n	Lt-m gy,m brn,a-sr,w srt,wk sil cmt,abt arg & slt mtx grdg to sltst,tr carb flks,fri,v pr vis por
57	1118.0	35		Sltst	Lt-m gy	Cly-vf	n	Lt-m gy,vf aren grdg to vf slty sst,mod arg,abt mmic,frm,sl sbfis
58	1105.0	32		Sltst	Dk brn -occ bk	Cly-vf	n	Dk brn-occ bk,v carb grdg to v slty coal,occ vf sst lam,frm-hd,non fis
59	1063.0	32		Clyst	Lt-m gy	cly	n	Lt-m gy,frm,non fis
60	1035.0	30		Sst/ clyst	Wh-lt gy, med brn	Cly-vf	n	Wh,lt gy,med brn,vf gr,v arg i/p grdg to clyst,fri-frm,non fis,no vis por

### **COMMENTS:**

Of Note: with a second look at these sidewall cores, the description of some were different from the first look, depending on where the flake of sample to look at was taken from, and from which end, even though to look externally at the core there was no difference due to a smeared coating on the outside of the core from the bullet entry. Wonder if this is always the case, and what can be done to avoid incorrect descriptions apart from destroying the sidewall core in the process?

**APPENDIX II: OIL SHOW EVALUATION REPORTS** 



# **OIL SHOW EVALUATION REPORT**

GEOLOGIST	DATE:
	i
Gordon 1	1641m - 1645m
WELL:	INTERVAL

David Horner 21/04/97 ב ה ה Pretty Hill Sst.

FM:

C1 ppm	5k	10k	20k	30k	40k	50k	100k	150k	200k	>250k
C2+ ppm	500	750	. 1k	2k	3k	4k	5k	7.5k	10k	>15k
Porosity Ø	tight			poor		fair		poob		
% with fluorescence	trace	10	20	30	40	50	09	70	80	06<
Fluorescence appearance	trace		spotted			streaked		patchy		solid
Brightness of fluorescence	v. dull		llub		dim		moderate	bright	v. bright	glowing
Type of cut	trace	v. slow crush cut	crush cut	instant crush cut	v. slow streaming cut	stream	moderate streaming	streaming	fast streaming	instant
Residue on spot plate	trace	heavy trace	v. thin ring	thin ring	thick ring	v. thick ring	thin film	thin film	thick film	solid
Show rating	trace		poor		Fair		poob			
Comments:										

MISTLW S:\GEOLOGY\REPORTS\WCR\R-WCR301.DOC Page 22 of 61

# SANTOS LIMITED

# **OIL SHOW EVALUATION REPORT**

INTERVAL 1771m - 1775m Gordon 1

Pretty Hill Sst.

FM:

GEOLOGIST:

David Horner

DATE:

22/04/97

C1 ppm	5k	10k	20k	30k	40k	50k	100k	150k	200k	>250k
C2+ ppm	200	750	<b>1</b> k	2k	3,4	4k	5k	7.5k	10k	>15k
Porosity Ø	tight			poor		fair		poob		
% with fluorescence	trace	10	20	30	40	50	09	02	80	06<
Fluorescence appearance	trace		spotted			streaked		patchy		solid
Brightness of fluorescence	v. dull		llub		dim		moderate bright	bright	v. bright	glowing
Type of cut	trace	v. slow crush cut	crush cut	instant crush cut	v. slow streaming cut	slow	moderate streaming	streaming	fast streaming	instant
Residue on spot plate	trace	heavy trace	v. thin ring	thin ring	thick ring	v. thick ring	thin film	thin film	thick film	solid
Show rating	trace		poor		Fair		poob			
Comments:										



# **OIL SHOW EVALUATION REPORT**

WELL: Gordon 1
INTERVAL 2195m - 2212m

GEOLOGIST: DATE:

David Horner

24/04/97

FM: Casterton Fm.

C1 ppm	Sk	10k	20k	30k	40k	50k	100k	150k	200k	>250k
C2+ ppm	500	750	1k	2k	ж Ж	4 <sub>4</sub>	5k	7.5k	10k	>15k
Porosity Ø	tight			poor		fair		poob		
% with fluorescence	trace	10	20	30	40	50	09	02	80	06<
Fluorescence appearance	trace		spotted			streaked		patchy		solid
Brightness of fluorescence	v. dull		llub		dim		moderate	bright	v. bright	glowing
Type of cut	trace	v. slow crush cut	crush cut	instant crush cut	v. slow streaming cut	slow	moderate streaming	streaming	fast streaming	instant
Residue on spot plate	trace	heavy trace	v. thin ring	thin ring	thick ring	v. thick ring	thin film	thin film	thick film	solid
Show rating	Trace		poor		Fair		poob			
Comments:	Oil only in ag	igregates wł	Oil only in aggregates where there is some visual $arnothing$ .	some visual (	Ğ.					

# SANTOS LIMITED

# **OIL SHOW EVALUATION REPORT**

WELL: Gordon 1

David Horner

GEOLOGIST:

INTERVAL 2401m - 2410m

DATE:

25/04/97

FM: Basement

C1 ppm	SK.	95	20k	30k	40k	50k	100k	150k	200k	>250k
C2+ ppm	200	750	<b>*</b>	2k	3%	4 4	5k	7.5k	10k	>15k
Porosity Ø	fight			poor		fair		poob		
% with fluorescence	trace	10	20	30	40	50	09	70	80	>90
Fluorescence appearance	trace		spotted			streaked		patchy		solid
Brightness of fluorescence	v. dull		llub		dim			bright	v. bright	glowing
Type of cut	trace	v. slow crush	crush cut	instant crush	v. slow streaming	slow	moderate streaming	streaming	fast streaming	instant
Residue on spot plate	trace	heavy	v. thin ring	thin ring	thick ring	v. thick ring	thin film	thin film	thick film	solid
Show rating	trace		poor		Fair		pooß			
Comments:	Associated v	vith fracture	Associated with fractures and quartz veining.	/eining.						



# **OIL SHOW EVALUATION REPORT**

2411m - 2436m Gordon 1 INTERVAL

Basement

GEOLOGIST:

DATE:

David Horner 26/04/97

FM:

C1 ppm	S. S	10k	20k	30k	40k	AOR	100k	4 7507	1000	7050
							Y00-	400	AUUN	7530R
C2+ ppm	200	750	#	2k	쓙	<del>4</del>	5K	7.5k	10k	>15k
Porosity Ø	tight			poor		fair		poob		
% with fluorescence	trace	10	20	30	40	50	09	02	80	06<
Fluorescence appearance	trace		spotted			streaked		patchy		solid
Brightness of fluorescence	v. dull		Ilub		dim			bright	v. bright	glowing
Type of cut	trace	v. slow crush cut	crush cut	instant crush cut	v. slow streaming	slow	moderate streaming	streaming	fast streaming	instant
Residue on spot plate	trace	heavy trace	v. thin ring	thin ring	thick ring	v. thick ring	thin film	thin film	thick film	solid
Show rating	trace		poor		Fair		poob			
Comments:	Weaker show than for 2401 - 2410m.	w than for 24	101 - 2410m.							

# SANTOS LIMITED

# **OIL SHOW EVALUATION REPORT**

Gordon 1 WELL:

GEOLOGIST:

David Horner

INTERVAL 2436m - 2443m

DATE:

27/04/97

Basement FM:

										!
C1 ppm	λΩ	10k	20k	30k	40k	50k	100k	150k	200k	>250k
C2+ ppm	500	750	*	2k	3k	4 <sub>X</sub>	5k	7.5k	10k	>15k
Porosity Ø	tight			poor		fair		poob		
% with fluorescence	trace	10	20	30	40	50	09	70	80	>90
Fluorescence appearance	trace		spotted			streaked		patchy		solid
Brightness of fluorescence	v. dull		qull		dim			bright	v. bright	glowing
Type of cut	trace	v. slow crush cut	crush cut	instant crush cut	v. slow streaming cut	slow	moderate streaming	streaming	fast streaming	instant
Residue on spot plate	trace	heavy	v. thin ring	thin ring	thick ring	v. thick ring	thin film	thin film	thick film	solid
Show rating	trace		poor		Fair		poob			
Comments:	Weaker show than preceding ba	w than prece	ding baseme	nt shows du	sement shows due to less Basement Fractures.	ement Fractı	Jres.			

**APPENDIX III: LOG EVALUATION** 

## GORDON 1-LOG ANALYSIS

Gordon 1 wireline logs were analysed over the interval 2300-2400m. No pay was identified and the well was plugged and suspended with oil shows in fractured basement.

A 12 1/4" surface hole was drilled to 656m and 9 5/8" casing set at 652m. An 8 1/2" production hole was drilled to 2505m without any significant problems. Two DST's over the intervals 2390-2461m and 2389.5-2361m tested the fractured basement and recovered 6 bbls and 1 bbl of oil respectively.

### Logs Acquired

PEX-AS (Res)

2501-652m (GR to surface)

(Nuclear)

2501-652m (High res 2501-2100m)

FMI

2499-2270m

CST

60 shot (56 recovered)

### **Mud Parameters**

Mud Type KCl/PHPA Mud Density 1.107 gm/cc

 Rm
 0.195 ohmm @ 17 °C

 Rmf
 0.148 ohmm @ 20 °C

 Rmc
 0.321 ohmm @ 16 °C

BHT 99 °C

### Log Processing

- Hole conditions were excellent and all logs were of an acceptable quality.
- An invasion corrected Rt curve was derived from the DLL
- DT was estimated from the median of the four sonic transit time curves.
- No other environmental corrections, other than those applied realtime in the field, were considered necessary

### Interpretation Procedures and Parameters

An interpretation was made using a density-neutron derived Vshale. Water saturations were calculated using the Simandoux equation.

• Total porosity was calculated from the LDL density log:

$$PHID = (2.65 - RHOB) / (RHOG - RHOF)$$

where:

RHOB = Bulk density from log

RHOG = 2.65 gm/cc

RHOF = 1.00 gm/cc

• Effective porosity was calculated as follows:

$$PHIE = PHID - (VSH * PHISH)$$

where:

PHISH = 0.1 (apparent shale porosity)

Formation water resistivity was derived from regional salinity data.

Parameters used for the interpretation are detailed in Table 1.

### **Conclusions**

- 1. FMI data identified fractures within basement rock at Gordon 1.
- 2. Gordon 1 recovered oil from basement fractures.
- 3. Gordon 1 was plugged and suspended.
- 4. Quantitative water saturation and porosity values were not calculated due to the fractured nature of the basement.

TABLE 1

## <u>Log Analysis Parameters</u>

PARAMETERS	MACEACHERN	BASEMENT
Rw (ohmm) @ 25°C	0.5	0.5
a	1	1
m	2	2
n	2 .	2
Rt Sh (ohmm)	30	30
Neut Sh (v/v)	0.2	0.2
Rhob Sh (gm/cc)	2.65	2.65
Rhob Coal (ms/ft)	2.35	2.35

### PE604425

This is an enclosure indicator page. The enclosure PE604425 is enclosed within the container PE905781 at this location in this document.

```
The enclosure PE604425 has the following characteristics:
     ITEM_BARCODE = PE604425
CONTAINER_BARCODE = PE905781
            NAME = Well Evaluation Summary for Gordon-1
           BASIN = OTWAY BASIN
           PERMIT = PEP/119
            TYPE = WELL
          SUBTYPE = WELL_LOG
     DESCRIPTION = Well Evaluation Summary (from WCR) for
                    Gordon-1
         REMARKS =
    DATE\_CREATED = 31/08/97
   DATE_RECEIVED =
            W_NO = W1191
        WELL_NAME = GORDON-1
      CONTRACTOR = SANTOS
    CLIENT_OP_CO = SANTOS LTD
```

(Inserted by DNRE - Vic Govt Mines Dept)

APPENDIX IV: DRILL STEM TEST DATA

The Service Company Reports will be forwarded when available

# Santos

A.C.N. 007 550 923

### DRILL STEM TEST REPORT

**WELL:** 

Gordon-1

**DST NO:** 1

DATE:

30<sup>th</sup> April, 1997

**INTERVAL:** 

2390 - 2461m (2.5m fill)

**FORMATION:** 

Basement

TEST TYPE:

On bottom straddle

Separator:

No

Type:

**CUSHION:** 

No

Rmf:

0.20 at 72 F

**GEOLOGIST:** 

**David Horner** 

Rw: Tracer:

### **REMARKS**

ELAPSED TIME (MIN)	REMARKS/ PRESSURES	ELAPSED TIME (MIN)	REMARKS/ PRESSURES	ELAPSED TIME (MIN)	REMARKS/ PRESSURES
0 IF	No blow	57 FF	No blow		
2	No blow	58	No blow		
4	No blow	59	Very weak bubble		
6	No blow	61	Very weak -increasing		
8	Very weak bubble	64	1" in bucket		
9	Weak bubble	67	2" in bucket		
10	5" in bucket	69	3" in bucket		
11	6" in bucket	71	4" in bucket		
12	7" in bucket	74	5" in bucket		
13	10" in bucket	Lost seat	Annulus dropping		
14	11" in bucket		Strong blow to bottom		
15 ISI	12" in bucket	84	Abort test		

### **SURFACE FLOW SUMMARY**

CHOKE SIZE (IN) SEPARATOR	FLUID TO SURFACE (MIN)	FLOWING TIME	MAXIMUM SURFACE PRESSURE	FINAL GAS RATE (MMCFD)	FINAL LIQUIDS RATE	FIELD GAS ANALYSIS	FIELD LIQUIDS ANALYSIS
	<b>-</b>	-	-	-	-	-	-

### FIELD DOWNHOLE PRESSURE DATA


		BOTTOM ELECTONI C	воттом	TOP ELEC	ТОР	TIMES
DEPTH INITIAL HYDROSTATIC 1ST - INITIAL FLOW 1ST - FINAL FLOW 1ST - CLOSED IN 2ND - INITIAL FLOW 2ND - FINAL FLOW 2ND - CLOSED IN FINAL HYDROSTATIC TEMPERATURE	m psig psig psig psig psig psig psig psig	2403.8 3838.5 115.1 181.0 2054.6 220.1 - 3838.4 211.37	2400.5 3050.5 186.3 - 2007.8 279.5 - - 3850.5	2385.4 3826.2 85.8 155.5 2035.2 194.4 - 3827.6 210	2382.6 3833.7 88.5 - 207.2 215.9 - 3833.7	15min 42 min 17 min Lost seat


WELL:	Gordon-1		DST NO:	1 <b>DA</b>	<b>TE:</b> 30/4/97
		RECO	VERY		
REVERSE CIRCUI PULLED	LATED	Y			
RECOVERY: 6 bt	ols oil cut rathole a	nd annulus mud			
		SAMPL	E DATA		
GAS/CONDENSAT	<u>E</u>				
SAMPLE NO	BOMB NO	ТҮРЕ	SOURCE	PRESS/TI	EMP
NIL					
OIL/CONDENSATI	<u> </u>	FILTRATE			
SAMPLE NO	ТҮРЕ	SAMPLE	RMF	TRACER	CL (PPM)
1 3	TIN PHIAL	OIL Mud Filtrate	0.20 at 72F		
WATER					
SAMPLE NO	ТҮРЕ		RW	REMARKS	
2	Make-up water		>10 at 80F		
REMARKS: Packers failed partwa	v into final flow pe	eriod. Lower tor	p packer and both l	bottom packers n	intured

Fluid before packer seat failure Oil Pour Point 23 degrees C.

GORDON #1 DST#1 REC 22199 2390-2460m ABOUE

GORDON = 1 DST = 1 REC 22200 2395-2460M OUTSIDE





GORDON #1 DST #1 REC 10335 2390-2461m
INSIDE

COMPANY	tntos Lin	1/TED	-	;	STATE TATE	- 1 C K / M	_ UAIE_	<u> </u>	4.7 t	
Vell Name God	PDON #1.			,	CB Flv. /2	9.59 m	← Tick	et No	DST	No a
Vell Name <u>Go</u> Vell Location <u>PEP</u>	119. ONSHORE Dru	IN BASIN VE	141°171.	14.5"5 (	BREW 125	1.89 m	<del>_f+</del> Forn	nation E	ASEME	۸ <i>۱۰</i> ۳-
nterval <u>2390</u> -	-2461m	TD	2505	5 m st 1	Net Pay		ft Type	of Test	WUENT	01/4
API Gravity									PASS STRI	
				,						
RECORDER DA	ATA					TIMED	ATA			
/ //ins								to _	0711	1
FRec.#_		=10335	= 522	#22200	= 526	19 Fr	02//	to	07753	'
IRange			5000	6250	5000			to _		
FClock		24	BATTERY	24	BATTERY	<u> </u>		to _		
SDepth_			2385.4	24505	2403.8	F3 11			<del></del>	
5Deptn_	<u> </u>				<del> </del>	TOTAD	T.C.D.	2145 à	9.407	
1-14 11 -4		7833.7	\$876.7 }81	7880.5	PS1 3838.5					
. Init. Hyd		88.5	858	186.3	1			051		
. First Flow	7	000	·	/86.3	115-1			065		
1 Final Flow		20717	155.5	2000	181.0	T. PULL	ED	0820		
. In. Shut-In		2072.2		2007.8	2054-6	T. OUT_		1800		
Init. Flow		215.9	194.4	279.5	220.1					
Final Flow	, ,			ļ		TOOL		_		
Fl. Shut-in			<u> </u>		3-			<u>5.000</u>		
Final Hyd			3827.6	3825-2	3838-4	Wt. Set o	n Packer_	<u>30,0</u>	<u> </u>	
side/Outside _	ABOVE	(/~)	1/2	1007 1	10071	Wt. Pulled	d Loose _	40,00	رحو	
						Initial Str	. Wt	140.0	ಅಲ	
ECOVERY /							Str M/t	150 0	<del>00</del>	
LOUVEILL						Unseated	OIL AAT	<u> </u>	<del></del>	
/ 20 امنیا⊒ امد	66/5 4	4	f+ := D C		t D.D	D . Cl .		3/./		
tal Fluid 0	ft. or	f	_ft. in D.C.	and	_ft. in D.P.	Bot. Chol	(e	3/4		
CAPDIACOIONI)	66/5 ft. of #. of O/c C	20, 1.70	730			Bot. Chol	(e	3/4 1/2		i
<u> </u>	ft. of					Bot. Chol Hole Size D. Col. I.	(e	3/4 1/2 2 13/16		i
<u> </u>	ft. of	, , , , , , , , , , , , , , , , , , ,				Bot. Chold Hole Size D. Col. I.: D. Pipe I.	Ce	3/4 1/2 2 <sup>13</sup> /6 3 - 826		i
<u>CODDIS(SISM)</u>	ft. of	, , , , , , , , , , , , , , , , , , ,				Bot. Chold Hole Size D. Col. I.I. D. Pipe I.	Ce	3/4 1/2 2 13/6 3 - 826 50.09		
<u>CIDDIS(SISM)</u>	ft. of ft. of					Bot. Chold Hole Size D. Col. I.: D. Pipe I. D.C. Leng	Se	3/4 1/2 2 13/16 8 - 826 50.09		
	ft. of					Bot. Chold Hole Size D. Col. I.: D. Pipe I. D.C. Leng D.P. Leng	D	3/4 1/2 2 1 3/16 3 - 8 2 6 50 · 09 1 4 5 - 9 3 · 2 8	<u> </u>	<u></u>
AS RECOVER'	ft. of ft. of  ft. of  Y MEASURED  Orifice P	WITH	H <sub>2</sub> O	R	ate	Bot. Chold Hole Size D. Col. I.: D. Pipe I. D.C. Leng D.P. Leng	D	3/4 1/2 2 1 3/16 3 - 8 2 6 50 · 09 1 4 5 - 9 3 · 2 8	<u> </u>	<u></u>
AS RECOVER'	ft. of ft. of ft. of	WITH		R		Bot. Chold Hole Size D. Col. I.I. D. Pipe I. D.C. Leng ロ.P. Leng イント MUD DA Mud type	SD	3/4 1/5 2 <sup>1</sup> 3/6 3-826 50.09 145-9 3.38	<u> </u>	<u></u>
AS RECOVER'	ft. of  ft. of  Y MEASURED  Orifice Proches	WITH	H <sub>2</sub> O inches	R	ate	Bot. Chold Hole Size D. Col. I.: D. Pipe I. D.C. Leng	SD	3/4 1/5 2 13/6 3 - 826 50 - 09 145 - 9 3 - 38 - PHP/	<u> </u>	<u></u>
AS RECOVERY Time Commiss.	ft. of  ft. of  Y MEASURED  Orifice Proches	WITH ressure	H <sub>2</sub> O inches	R	ate	Bot. Chold Hole Size D. Col. I.I. D. Pipe I. D.C. Leng ロ.P. Leng イント MUD DA Mud type	SD	3/4 1/5 2 13/6 3-826 50-09 145-9 3-38 2 14111	<u> </u>	<u></u>
AS RECOVER' Time C Mins. in	ft. of  ft. of  Y MEASURED  Orifice Proches	WITH ressure	H <sub>2</sub> O inches	R.	ate cf/d	Bot. Chold Hole Size D. Col. I.I. D. Pipe I. D.C. Leng D.P. Leng HWD DA Mud type Weight	D	3/4 1/5 2 13/6 3 - 826 50 - 09 145 - 9 3 - 38 - PHP/	<u> </u>	<u></u>
AS RECOVER' Time C Mins. in	ft. of ft. of ft. of  Y MEASURED  Orifice Proches	WITH ressure	H <sub>2</sub> O inches	R.	ate cf/d	Bot. Chold Hole Size D. Col. I.I. D. Pipe I. D.C. Leng D.P. Leng H→NDP MUD DA Mud type Weight Vis.	SD	3/4 1/5 2 <sup>1</sup> 3/6 3-826 50-09 145-9 3-38 19-3 12 5-5	<u> </u>	<u>m</u> -
AS RECOVERY Time Common in	ft. of ft. of ft. of  Y MEASURED  Orifice Proches	WITH ressure	H <sub>2</sub> O inches	R.	ate cf/d	Bot. Chold Hole Size D. Col. I.I. D. Pipe I. D.C. Leng D.P. Leng HWDP MUD DA Mud type Weight Vis. W.L.	Se	3/4 1/5 2 <sup>1</sup> 3/6 3-826 50-09 145-9 3-38 19-3 12 5-5	<u> </u>	<u>m</u>
AS RECOVERY Time Commiss.	ft. of ft. of ft. of  Y MEASURED  Orifice Proches	WITH ressure	H <sub>2</sub> O inches	R.	ate cf/d	Bot. Chold Hole Size D. Col. I.I. D. Pipe I. D.C. Leng D.P. Leng H. D.P. MUD D.A. Mud type Weight Vis W.L F.C	Se	3/4 1/5 2 <sup>1</sup> 3/6 3-826 50-09 145-9 3-38 19-3 12 5-5	<u> </u>	<u>m</u> -
AS RECOVER' Time Comins. in	ft. of ft. of ft. of  Y MEASURED  Orifice Proches	WITH ressure	H <sub>2</sub> O inches	R. mo	ate cf/d	Bot. Chold Hole Size D. Col. I.I. D. Pipe I. D.C. Leng D.P. Leng HWDP MUDDH Mud type Weight Vis. W.L. F.C.	SD	3/4 1/5 2 13/6 3 - 826 50 09 145 - 9 3 - 38 2 1717,77 9 - 3 42 5 - 5 1	<u> </u>	<u>m</u> -
AS RECOVERY Time Commiss. in	ft. of ft. of  ft. of  Y MEASURED  Orifice Proches	WITH ressure PSI	H <sub>2</sub> O inches	R. mo	ate cf/d	Bot. Chold Hole Size D. Col. I.I. D. Pipe I. D.C. Leng D.P. Leng H. D.P. MUD D. Mud type Weight Vis W.L F.C Mud Drop GENERA	8 8 8 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9	3/4 1/5 2 13/6 3 - 826 50 09 145 - 9 3 - 38 2 1717,77 9 - 3 42 5 - 5 1	77	<u>m</u> -
AS RECOVERY Time C Mins. in	ft. of ft. of ft. of  Y MEASURED  Orifice P  nches	WITH ressure PSI	H <sub>2</sub> O inches	R	ate cf/d	Bot. Chold Hole Size D. Col. I.I. D. Pipe I. D.C. Leng D.P. Leng H. D.P. MUD D. Mud type Weight Vis W.L F.C Mud Drop GENER Amt. of fi	SD	3/4 1/3 2 <sup>1</sup> 3/6 3-826 50.09 145-9 3-38 2-111111111111111111111111111111111111	n n	
AS RECOVER' Time Common in	ft. of ft. of  Y MEASURED  Orifice Proches	WITH ressure PSI	H <sub>2</sub> O inches	R	ate cf/d	Bot. Chold Hole Size D. Col. I.i. D. Pipe I. D.C. Leng D.P. Leng P. D.P. Mud type Weight Vis W.L F.C Mud Drop GENER Amt. of fi Btm. H. T	Ne	3/4 1/5 2 <sup>1</sup> 3/6 3-826 50-09 145-9 3-38 1-17,77 5-5 1 5 A 211-3	n n	
AS RECOVER' Time Common in	ft. of ft. of ft. of  Y MEASURED  Orifice P  nches	WITH ressure PSI	H <sub>2</sub> O inches	R	ate cf/d	Bot. Chold Hole Size D. Col. I.I. D. Pipe I. D.C. Leng D.P. Leng H. D.P. MUD D. Mud type Weight	Ne 8  D. 2  D. 2  NATA CC  AL DAT.  Hemp	3/4 1/5 2 <sup>1</sup> 3/6 3-826 50.09 145-9 3-38 19-3 12 5-5 1 5 A 211-3: FAIR.	n n	m 1
AS RECOVERY Time Common in	ft. of ft. of ft. of  Y MEASURED  Orifice P  nches	WITH ressure PSI	H <sub>2</sub> O inches	R	ate cf/d	Bot. Chold Hole Size D. Col. I.I. D. Pipe I. D.C. Leng D.P. Leng H. D.P. MUD D. Mud type Weight	YE  AL DAT.  Hemp.  1	3/4 1/5 2'3/6 3-826 50-09 45-9 3-38 - PHPP 5-5 1 5 A 2-5 211-3: FAIR.	n n	m 1
AS RECOVERY Time Common in	ft. of ft. of  Y MEASURED  Orifice Proches	WITH ressure PSI	H <sub>2</sub> O inches	R	ate cf/d	Bot. Chold Hole Size D. Col. I.I. D. Pipe I. D.C. Leng D.P. Leng H. D.P. MUD D. Mud type Weight Vis W.L F.C Mud Drop GENER Amt. of fi Btm. H. T Hole Conc. Packer Siz No. of Packer Size D. Col. Mod. of Packer Size No. of Packer Size D. Col. Mod. Mod. Mod. Mod. Mod. Mod. Mod. Mod	Se	3/4 1/5 2'3/6 3-826 50-09 145-9 3-38 1-011,00 5-5 1-5 1-5 A 211-3 741R 430 4	n 1	
AS RECOVERY Time Common in the	ft. of ft. of ft. of  Y MEASURED  Orifice P  nches	WITH ressure PSI	H <sub>2</sub> O inches	R	ate cf/d	Bot. Chold Hole Size D. Col. I.I. D. Pipe I. D.C. Leng D.P. Leng H. D.P. MUD D. Mud type Weight	Se	3/4 1/5 2'3/6 3-826 50-09 145-9 3-38 1-011,00 5-5 1-5 1-5 A 211-3 741R 430 4	n 1	
AS RECOVERY Time Common in	ft. of ft. of ft. of  Y MEASURED  Orifice P  nches	WITH ressure PSI	H <sub>2</sub> O inches	R	ate cf/d	Bot. Chold Hole Size D. Col. I.I. D. Pipe I. D.C. Leng D.P. Leng H. D.P. MUD D. Mud type Weight Vis W.L F.C Mud Drop GENER Amt. of fi Btm. H. T Hole Conc. Packer Siz No. of Packer Size D. Col. Mod. of Packer Size No. of Packer Size D. Col. Mod. Mod. Mod. Mod. Mod. Mod. Mod. Mod	No	3/4 1/5 2'3/6 3-826 50-09 145-9 3-38 1-17 1-17 5-5 1-17 5-5 1-17 5-17 1-17	n 1	
AS RECOVERY Time Commiss. in	ft. of ft. of ft. of  Y MEASURED  Orifice P  nches	WITH ressure PSI	H <sub>2</sub> O inches	R	ate cf/d	Bot. Chold Hole Size D. Col. I.I. D. Col. I.I. D. C. Leng D.P. Leng Haw D.P. MUD D.A. Mud type Weight	No	3/4 1/5 2'3/6 3-826 50-09 145-9 3-38 1-17 1-17 5-5 1-1 5 A 2.5 211.3 FAIR. +30 +	n 1	
AS RECOVERY Time Common in	ft. of ft. of ft. of  Y MEASURED  Orifice P  nches	WITH ressure PSI	H <sub>2</sub> O inches	R	ate cf/d	Bot. Chold Hole Size D. Col. I.I. D. Pipe I. D.C. Leng D.P. Leng H. D.P. MUD D. Mud type Weight	See	3/4 1/5 2'3/6 3-826 50-09 145-9 3-38 1-17 1-17 5-5 1-17 5-5 1-17 5-17 1-17	n 1	
AS RECOVERY Time Commiss. in	ft. of ft. of ft. of  Y MEASURED  Orifice P  nches	WITH ressure PSI	H <sub>2</sub> O inches	R	ate cf/d	Bot. Chold Hole Size D. Col. I.I. D. Pipe I. D.C. Leng D.P. Leng H. D.P. MUD D. Mud type Weight Vis Mud Drop GENER Amt. of fi Btm. H. T. Hole Conc. Packer Siz No. of Packer Siz No.	AL DAT.	3/4 1/5 2'3/6 3-826 50-09 45-9 3:38 - PHPP 9-3 	n 1	
AS RECOVERY Time Common in	ft. of ft. of ft. of  Y MEASURED  Orifice P  nches	WITH ressure PSI	H <sub>2</sub> O inches	R	ate cf/d	Bot. Chold Hole Size D. Col. I.I. D. Col. I.I. D. Pipe I. D.P. Leng Haw Do Mud type Weight Weight Wis. Mud Drop GENER Amt. of fi Btm. H. T. Hole Conc. Packer Siz No. of Packer Siz No. of Packer Siz Tester — Tool Chase Tester — Tool Chase Tester — Tool Chase Tester — Tool Col. I.I. D. Col. I.I. Col.	AL DAT.	3/4 1/5 2-3/6 3-826 50-09 145-9 3-38 1-17 1-17 5-5 1-17 5-5 1-17 5-17 1-17	n 1	
AS RECOVERY Time Commiss. in	ft. of ft. of ft. of  Y MEASURED  Orifice P  nches	WITH ressure PSI	H <sub>2</sub> O inches	R	ate cf/d	Bot. Chold Hole Size D. Col. I.I. D. Col. I.I. D. Pipe I. D. C. Leng D.P. Leng H. D.P. Mud type Weight	ALDAT.	3/4 1/5 2 <sup>1</sup> 3/6 3-826 50.09 45-9 3.38 1947 5-5 1 5 211-3: F41R. 430 4 NO NO NO VESTER 451EY	n 1	

		Reversed Out <i>No</i>	
			<del></del>
		Tester SILVESTER	
		Co. Rep. <u>A. &amp; AD LEY</u>	
		Contractor <u>りかを</u> Rig No <i>3o</i>	
		Rig No	
BLOW DESCRIPTION 1st FLOW: NIL AIR BLOW INCREASING TO WELK AT END OF FLOW	FOR 8 MINS THEN V.V	V.AS	•
BLOW DESCRIPTION 2nd FLOW: NIC AIR BLOW V. W. A. B AND INCREASING.	FOR ZMINS THEN		
REMARKS: MUD STARTED TO DROP VERY SL LITTLE WEIGHT ON TOOL. APPEARED TO SKID APPROX 1/2m TO KEEP2S, OOC ON BOOL. M	THRU FILL. GIASED J UD SALL DROPPED SLO	964	
		<del></del>	
		<del></del>	
	LENGTH		
TOTAL TOOL TO BOTTOM TOP PACKERS		BO SUB	LENGTH
		P.O. SUB	
INTERVAL TOOL	14.77	C.O. SUB	
INTERVAL TOOL	44.06 74.19 _	SHUT-IN TOOL	
DRILL COLLAR ANCHOR IN INTERVAL	,		
DRILL COLLARS ABOVE TOOLS Stands	Total <i>150.09</i>		
DRILL PIPE ABOVE TOOLS Stands	Total2145.9	HMV	
		JARS	
THER ABOVE TOOL	Total		
OTAL DRILL COLLARS DRILL PIPE AND TOOLS .	2509.69		
OTAL DEPTH	2505	SAFETY JOINT	
OTAL DRILL PIPE ABOVE K.B.	4.69		
EMARKS:		PACKER	
		PACKER	
		DEPTH	
		STUBB	
·		ANCHOR	
		х	
		BULLNOSE	
		V т.D	

<


### SANTOS LIMITED


WELL NAME: GORDON #1 DST #1 DATE: 30/04/97

FORMATION: BASEMENT TESTER: J.SILVESTER

TOTAL TOOL TO BOTTOM TOP PACKEF	15.36
TOOL INTERVAL	14.77
BOTTOM PACKER AND ANCHOR	44.06
TOTAL TOOL	74.19
DRILL COLLARS IN INTERVAL	56.13

STICK UP	-4.69	
DRILL PIPE	2145.9	-4.69 75STDS+SGL+PUP
H.W.DRILL PIPE	83.38	2141.21 3 STANDS
DRILL COLLARS	131.42	2224.59 5 STANDS+JARS
PUMP OUT SUB	0.41	2356.01
DRILL COLLARS	9.28	2356.42 1 SGL
DROP BAR SUB	0.3	2365.7
DRILL COLLARS	9.39	2366 1 SGL
CROSS OVER	0.31	2375.39
RECORDER CARRIER	1.52	2375.7
SHUT-IN TOOL	1.71	2377.22
SAMPLER	1.02	2378.93
TRAVEL SUB	0.46	2379.95
HYD TOOL	1.68	2380.41
RECORDER CARRIER	1.52	2382.09
RECORDER CARRIER EMP	1.83	2383.61
HANGER SUB	0.31	2385.44
SAFETY JOINT	0.66	2385.75
PACKER	2.34	2386.41
PACKER	1.29	2388.75
DEPTH	2390.04	2390.04
STICK DOWN	1.05	2390.04
PERF	8.82	2391.09
RECEIVER SUB	0.31	2399.91
RECORDER CARRIER	1.52	2400.22
RECORDER CARRIER EMP	2.05	2401.74
CROSS OVER	0.31	2403.79
DRILL COLLARS	56.13	2404.1 2 STANDS
CROSS OVER	0.31	2460.23
STICK UP	0.4	2460.54
DEPTH	2460.94	2460.94
PACKER	1.94	2460.94
PACKER	2.34	2462.88
CROSS OVER	0.31	2465.22
DRILL PIPE	38.23	2465.53 4 DRILL PIPE
CROSS OVER	0.31	2503.76
PERF	0.31	2504.07
BULLNOSE	0.62	2504.38
TOTAL DEPTH	2505	





## Santos

A.C.N. 007 550 923

### DRILL STEM TEST REPORT

WELL:

Gordon-1

DST NO:

DATE:

1st May, 1997

INTERVAL:

2389.5-2461m

FORMATION:

Basement

TEST TYPE:

CS

Separator:

Yes/No Type:

**CUSHION:** 

52m (0.8bbls)

Rmf:

0.20 at 72F

2

Rw:

>10 at 80 F

**GEOLOGIST:** 

**David Horner** 

Tracer: Nil

### **REMARKS**

ELAPSED TIME (MIN)	REMARKS/ PRESSURES	ELAPSED TIME (MIN)	REMARKS/ PRESSURES	ELAPSED TIME (MIN)	REMARKS/ PRESSURES
0 open tool	No blow	125	4 1/4" in bucket		
11	No blow	140	5" in bucket		
12	2 bubbles	155	5.5" in bucket		
13	Occasional bubbles	170	5 3/4" in bucket		
20	Continuous bubbles	185	6.25" in bucket		
25	Weak at surface	200	6.25" in bucket		
35	1" in bucket	215	6.75" in bucket		
50	1 5/8" in bucket	216	Lost packer seat		
65	1 3/4" in bucket	ISI	Tool closed in		1
80	2 3/4" in bucket	470	Pull tool free		
95	3" in bucket				
110	4" in bucket	<u> </u>			

### SURFACE FLOW SUMMARY

### FIELD DOWNHOLE PRESSURE DATA

		BOTTOM EMP	воттом	TOP EMP	INTERNAL	TIMES
DEPTH INITIAL HYDROSTATIC 1ST - INITIAL FLOW 1ST - FINAL FLOW 1ST - CLOSED IN 2ND - INITIAL FLOW 2ND - FINAL FLOW 2ND - CLOSED IN FINAL HYDROSTATIC TEMPERATURE	m psig psig psig psig psig psig psig psig	2403.8 3813.1 158.2 474.7 2773.0 - - 3809.9 211.37	2400.5 3803.7 186.3 465.8 2743.7 - - 3803.7	2382.9 3794.8 126.1 448.6 2754.1 - - 3793.8 208	2379.8 3880.9 210.4 485.4 2815.0	219min 150min

**WELL:** 

Gordon-1

DST NO:

2

DATE:

1st May, 1997

### **RECOVERY**

REVERSE CIRCULATED

**PULLED** 

**RECOVERY:** Pulled to shoe, then reverse circulated.

Recovered 1 bbl oil cut water, 15 bbls muddy water.

Flow rate calculated from recovery charts at 47 barrels per day.

### **SAMPLE DATA**

### **GAS/CONDENSATE**

SAMPLE NO	BOMB NO	TYPE	SOURCE	PRESS/TEMP
NIL				

### OIL/CONDENSATE

SAMPLE NO	TYPE	SAMPLE	API	PP	POSITION
1 2	1 gal tin 1 gal tin	Oil/water Oil/water	-	23C 23C	Top of recovery Top of recovery

### MAKEUP WATER/ FILTRATE

SAMPLE NO	ТҮРЕ	SAMPLE	RMF	TRACER	CL (PPM)
13	Glass phial	Mud filtrate	0.20 at 72F	-	25,000
14	Plastic bottle	Makeup water	>10 at 70F		Trace

### WATER

SAMPLE NO	TYPE	RW	REMARKS
3 Muddy water 4 Muddy water 5 Muddy water 6 Muddy water 7 Muddy water 8 Watery Mud 9 Watery mud 10 Dirty water 11 Dirty water 12 Dirty water	0 strokes 31 strokes 67 strokes 104 strokes 141 strokes 170 strokes 245 strokes Top of sample chamber Bottom of sample chamber Bottom of sample chamber	0.30 at 70F 0.28 at 70F 0.30 at 70F 0.28 at 70F 0.22 at 70F 0.22 at 70F 0.20 at 70F	Strokes measured from start of fluid recovery which was 49 into a recovery with a Total theoretical recovery Of 284 strokes ie. Total Strokes of fluid recovery Is 235 strokes.

### **REMARKS:**

IF 216 mins before packer seat failure. Tool closed in for 154 mins. Sample chamber closed prior to pulling tool free.

Well Location Pointerval 2389-	ordon #1				TATE 1//	1C70K/19 5ATE 1-5-97
Well Location Pointerval 2389-	101, 2010			······································		1CTORIA DATE 1.5.97 19.59 mat. Ticket No. 055 DST No. 2
Interval 2389-	EP119 DUSH	ORE OT	WALL RAS	Sent Vic.	BEW /	24 89 m 4. Formation DASEMENT
						ft. Type of Test Convention A
•						ity By PASS STRADO
					<b>J</b>	
RECORDER D	ATA				-	TIME DATA
Mins			<del></del>			PF Fr. 1710 to 2049
PFRec.#_			1			IS Fr. 2049 to 2322
SIRange_		1 6	5000	6520	5000	
	24 hrs.	24	BATTERY	24	BATTERY	FS Frtot
FSDepth_	2373.5 sum	2379.8	2382.9	24005	2403-8	263
		PSI	PSI	PSI	PSI	T STARTED 0930 H
A. Init. Hyd	100 3	3880.9	37948	3803.7	3813.1	T. ON BOTM. 1545
B. First Flow _		210.4	126.1	186.3	128.7	T. OPEN
Final Flow _	· · · · · · · · · · · · · · · · · · ·	485.4 2815.0	448.6	465.8	474.7	T. PULLED 2322 r
C. In. Shut-In _		2015.0	2754.1	2743-7	2773.0	T. OUT r
D. Init. Flow _						TOOL DATA
E. Final Flow _ F. Fl. Shut-in						TOOL DATA
f. Fi. Shutin G. Final Hyd		380.9	3793.8	3803.7	2809-9	
nside/Outside	ARONE	( NSIDE	(/NS/DE)	DUTSIDE	(Dursiga	Wt. Pulled Loose
nside/Odiside	710012	ון אפיזכטיו	(1N 3/0/E)	(DOISIDE)	10013196	12/ 2 - 2
COVERY						
	ft. o	f	ft in D.C.	224	f+ := D D	Unseated Str. Wt. III  Bot. Choke 3/4 in  Hole Size 8/2 in
	fin of DIC C			anu	_11. 111 D.F.	Hole Size 8/2
1586/5	frof Mus	D4 W.	ATER	<del></del>		D. Col. I.D. 246
	_ ft. of	•				`
	_ ft. of					D.C. Leng. 121.55 m +
						D.P. Leng. 2/70-92 m #
SAS RECOVER	RY MEASURED	WITH				HWDP 83.38 m
		ressure	H <sub>2</sub> O		ate	MUD DATA  Mud type XCL PHPA
•	inches	PSI	inches		:f/d	
						Weight <u>9.2</u>
						Vis
<del>م</del>						F.C in
6						Widd Drop
						GENERAL DATA
						. 1 /
						Btm. H. Temp. 2/1/37 0F
						Hole Cond. FAIR
						Packer Size $\frac{7/2 \times 30}{}$ in
URFACE CHOKE	SIZE:					No. of Packers 4
				,		Cushing Ame 52
FLOW KAT	E CALCUL	ATED (	+7-66/5	10A4		Cushion Type WATER
				· /		Reversed Out YES.
						Tool Chased YES . AT 2046 HRS
				··		Tester J. SILVESTER . C. M. GUINN
						01 5


FLOW MALE CHLCUCATON THE	7	Reversed Out YES. AT JE46 HRS Tool Chased YES. AT JE46 HRS Tester J. SILVESTER & C. M. GUY Co. Rep. A. SKADLEY/BRICHAM Contractor ON & E Rig No. 30	;~~\ <b>75€</b> ©
BLOW DESCRIPTION 1st FLOW: NIL 14, R BLOW FOR 12min DECASIONAL BURKLES INCREMSING TO WEAK BLOW AT BLOW DESCRIPTION 2nd FLOW:  REMARKS: MUD DROPPED AT 2046, SHUT IN I	AT2049 STURNED THE	-  - <u>-</u> 	'n
THE OPEN POSITION INTO THE CLOSED POSITION TO CLOSE CHAMBER PRIOR TO PULLING PREE AND P.O.OH.	THESAMPLE	<u>. E</u> 	
TOTAL TOOL TO BOTTOM TOP PACKERS	LENGTH 17.29 15.38	BO SUB P.O. SUB	
INTERVAL TOOL	44.06 76. <del>7</del> 3	SHUT-IN TOOL	
DRILL COLLAR ANCHOR IN INTERVAL	56.13 121.55	H	
DRILL PIPE ABOVE TOOLS StandsTotal  DRILL PIPE ABOVE TOOLS StandsTotal	$\frac{\alpha}{1}$	HMV	
H. W. PIPE ABOVE TOOLS StandsTotal		JARS	
OTHER ABOVE TOOL  TOTAL DRILL COLLARS DRILL PIPE AND TOOLS	2508-7		
TOTAL DEPTH	~ > C)	SAFETTSOM	
TOTAL DRILL PIPE ABOVE K.B.		PACKER	
REMARKS:		PACKER DEPTH STUBB ANCHOR	
		BULLNOSE	


ì

FORMATION: BASEMENT	TESTER:	J.SILVESTER
		C.Mc GUINN

TOTAL TOOL TO BOTTOM TOP PACKER	17.29
TOOL INTERVAL	15.38
BOTTOM PACKER AND ANCHOR	44.06
TOTAL TOOL	76.73
DRILL COLLARS IN INTERVAL	56.13

OTION UP	0.74	
STICK UP	3.71	0.74 70.0TD0: 4.00
DRILL PIPE	2170.92	-3.71 76 STDS+ 1 SG 2167.21 3STDS
H.W.DRILL PIPE	83.38	
DRILL COLLARS	102.88	
PUMP OUT SUB	0.41	
DRILL COLLARS	9.28 0.3	2353.88 1 SGL
DROP BAR SUB DRILL COLLARS	9.39	2363.16 2363.46 1SGL
CROSS OVER	9.39 0.31	
RECORDER CARRIER		2373.16
SHUT-IN TOOL	1.52	
	1.71	2376.39
SAMPLER TRAVEL SUB		
HYD TOOL	0.46 1.68	2377.87
RECORDER CARRIER	1.00	2379.55
RECORDER CARRIER RECORDER CARRIER EMP	1.83	
	1.03	2382.9
JARS HANGER SUB		
SAFETY JOINT	0.31 0.66	2385.14
PACKER	2.34	2385.8
PACKER	1.29	2388.14
DEPTH	1.29	2389.43
STICK DOWN	1.05	
PERF	9.43	
RECEIVER SUB RECORDER CARRIER	0.31 1.52	2399.91 2400.22
RECORDER CARRIER EMP	2.05	
CROSS OVER	0.31	
DRILL COLLARS	56.13	
CROSS OVER	0.31	
STICK UP	0.31	2460.54
DEPTH	0.4	<b>2460.94</b>
PACKER	1.94	
PACKER	2.34	
CROSS OVER	0.31	
DRILL PIPE	38.23	2465.53
	36.23 0.31	
CROSS OVER PERF	0.31	
	0.51	2504.07 2504.38
BULLNOSE TOTAL DEBTH	0.62	
TOTAL DEPTH		2505





APPENDIX V: HYDROCARBON ANALYSIS



Amdel Limited A.C.N. 008 127 802

Petroleum Services PO Box 338 Torrensville Plaza SA 5031

Telephone: (08) 8416 5240 Facsimile: (08) 8234 2933

16 June, 1997

Santos Limited GPO Box 2319 ADELAIDE SA 5001

Attention:

A. Pietsch

# REPORT LQ5871 - Part 1

CLIENT REFERENCE:

C18994

WELL NAME/RE:

Gordon-1, DST-1

MATERIAL:

Crude Oil

WORK REQUIRED:

Liquid Composition and Physical Tests

Please direct technical enquiries regarding this work to the signatory below under whose supervision the work was carried out. This report relates specifically to the sample or samples submitted for testing.

Brian L. Watson

Manager

**Petroleum Services** 

Di Wate

Amdel Limited shall not be liable for loss, cost, damages or expenses incurred by the client, or any other person or company, resulting from the use of any information or interpretation given in this report. In no case shall Amdel Limited be liable for consequential damages including, but not limited to, lost profits, damages for failure to meet deadlines and lost production arising from this report. This document shall not be reproduced except in full and relates only to the items tested.





test(s) reported herein have been performed in accordance with its terms of registration. This document shall not be reproduced except in full.

# PHYSICAL PROPERTIES

Client: SANTOS Ltd.

Report:

LQ5871

Sample: GORDON-1

DST-1

DATE: 30/04/97

	Method	Description	Units	GORDON-1
				DST-1
IP2	ASTM D611	Aniline Point	°C	_
IP143	ABTIVE DOTT	Asphaltenes	% wt	_
IP364	ASTM D976	Calculated Cetane Index	/ / / / /	
IP219	ASTM D2500	Cloud Point	°C	
IP17	AB1W1 D2500	Colour by Lovibond Tintometer		
IP274	ASTM D2624	Conductivity of Fuels	pS/m	
IP13	ASTM D189	Conradson C Residue on 10% Dis Residue	% wt	
IP154	ASTM D130	Copper Corrosion	70 111	
IP365	ASTM D4052	Density @ 15°C	g/mL	0.8341
IP21	7 ED 1101 D-1052	Diesel Index	£E	0.0541
IP123	ASTM D86	Distillation	ĺ	_
11 123	ABTM Doo	IBP	°c	
		10% Rec	°C	-
		20% Rec	°C	-
		30% Rec	_	-
		40% Rec	°C	-
		1	°C	-
		50% Rec 60% Rec	°C	-
		70% Rec	!	-
		80% Rec	°C	-
		90% Rec	°C	-
		95% Rec	°C	-
		Decomposition Point	°C	_
		Residue	% vol	
		Loss	% vol	_
		Evaporated @ 75°C, 105°C, 135°C	% vol	-
IP131	ASTM D381	Existent Gum by Evaporation	mg/100mL	_
IP170	121111 2501	Flash Point Abel Closed Cup	°C	_
IP34	ASTM D93	Flash Point Pensky Martens Closed Cup	°C	_
IP156	ASTM D1319	Fluorescent Indicator Absorption Aromatics	% vol	_
IP16		Freezing Point	°C	-
IP71	ASTM D445	Kinematic Viscosity @ 40°C	cSt	9.697
IP71	ASTM D445	Kinematic Viscosity @ 100°C	cSt	-
IP15	ASTM D97	Pour Point	°C	36
		Aluminium	mg/kg	-
	ASTM D5185	Vanadium	mg/kg	-
		Sodium	mg/kg	-
IP365		Specific Gravity @ 60/60°F	95	0.8345
IP3'54		Total Acidity in Aviation Fuel	mgKOH/g	-
IP216		Total Contaminant	mg/L	_
	ASTM D2270	Viscosity Index		-
IP289 ·		Water Reaction Interface Rating		_
		Separation		_
	ASTM D96	Water	% vol	.
	i i	Mud	% vol	99.0
IP160		API Gravity	degrees	38.06
- 100		- = not determined		

- = not determined

Approved Signatory:

Mohammad Massoumi

Date:

06/06/97

Registration No: 2013

This report relates specifically to the sample submitted for testing.





PETROLEUM SERVICES LIQUID ANALYSIS

Method GL-02-01

Client:

SANTOS Ltd

Report #

LQ5871

Sample:

GORDON-1 DST-1 30/04/97

Boiling Point Range (Deg.C)	Component	Weight%	Mol%
-88.6	ETHANE	0.04	0.24
<b>-42.1</b>	PROPANE	0.18	0.77
-11.7	I-BUTANE	0.27	0.89
-0.5	N-BUTANE	0.49	1.62
27.9	I-PENTANE	0.99	2.63
36.1	N-PENTANE	0.69	1.83
36.1-68.9	HEXANE, C-6	2.56	5.68
80.0	BENZENE	0.03	0.07
68.9-98.3	HEPTANE.C-7	3.50	6.70
100.9	METHYLCYCLOHEXANE	1.69	3.29
110.6	TOLUENE	0.07	0.14
98.3-125.6	OCTANE, C-8	4.01	6.72
136.1-144.4	ETHYLBZ+XYLENES	0.66	1.19
125.6-150.6	C-9	3.79	5.66
150.6-173.9	C-10	4.62	6.23
173.9-196.1	C-11	4.23	5.19
196.1-215.0	C-12	3.73	4.19
215.0-235.0	C-13	4.31	4.47
235.0-252.2	C-14	4.16	4.02
252.2-270.6	C-15	5.13	4.63
270.6-287.8	C-16	3.85	3.26
287.8-302.8	C-17	3.36	2.68
302.8-317.2	C-18	4.27	3.21
317.2-330.0	C-19	3.97	2.83
330.0-344.4	C-20	3.01	2.04
344.4-357.2	C-21	3.69	2.38
357.2-369.4	C-22	3.49	2.15
369.4-380.0	C-23	3.52	2.08
380.0-391.1	C-24	3.99	2.26
391.1-401.7	C-25	3.80	2.07
401.7-412.2	C-26	3.37	1.76
412.2-422.2	C-27	3.39	1.71
>422.2	C-28+	11.14	5.41
	Total	100.00	100.00
	( 0.00 = LESS THAN 0.01% )		

The above boiling point ranges refer to the normal paraffin hydrocarbon boiling in that range. Aromatics, branched hydrocarbons, naphthenes and olefins may have higher or lower carbon numbers but are grouped and reported according to their boiling points.

Average molecular weight of C-8 plus fraction (calc) =

220

g/mol


This report relates specifically to the sample submitted for analysis.

Approved Signatory Registration No:

Date

03-Jun-97

Gordon-1, DST-1 30/04/97



**APPENDIX VI: WATER ANALYSIS** 

# **APPENDIX VI: WATER ANALYSIS**

Three samples were forwarded to Amdel for analysis.

Samp	ole Origin	Type	Collection Point
1	DST 2	Water	Top of sample chamber
2	DST 2	Water	Bottom of sample chamber
3	DST 1	Mud Filtrate	Pits



Amdel Limited A.C.N. 008 127 802

Petroleum Services PO Box 338 Torrensville Plaza SA 5031

Telephone: (08) 8416 5240

Facsimile: (08) 8234 2933

25 July, 1997

Santos Limited GPO Box 2319 ADELAIDE SA 5001

Attention:

A. Pietsch

# **REPORT LQ6104**

**CLIENT REFERENCE:** 

C24144

WELL NAME/RE:

Gordon-1

MATERIAL:

Water Samples

WORK REQUIRED:

Water Analysis

Please direct technical enquiries regarding this work to the signatory below under whose supervision the work was carried out. This report relates specifically to the sample or samples submitted for testing.

Brian L. Watson

Manager

**Petroleum Services** 

an Water

Amdel Limited shall not be liable for loss, cost, damages or expenses incurred by the client, or any other person or company, resulting from the use of any information or interpretation given in this report. In no case shall Amdel Limited be liable for consequential damages including, but not limited to, lost profits, damages for failure to meet deadlines and lost production arising from this report. This document shall not be reproduced except in full and relates only to the items tested.

# 1. INTRODUCTION AND RESULTS

Two (2) samples were received for standard water analysis (WA-10-01). All analyses were performed according to APHA methods (19th Edition). Results are presented on the following pages.



### **TABLE 1 - WATER ANALYSIS**

WELL / ID: Gordon-1,DST-2 (Sample 10)

SAMPLE TYPE: Water

SAMPLE POINT: Top Of Sample Chamber

DATE COLLECTED -

DATE RECEIVED: 24/07/97

**JOB NUMBER: LQ6104** 

FORMATION: INTERVAL: -

COLLECTED BY: Client

### PROPERTIES:

pH (measured) = 6.85 Resistivity (Ohm.M @ 25°C) = 0.18 Electrical Conductivity ( $\mu$ S/cm @ 25°C) = 54300 Specific Gravity (S.G. @ 20°C) = na Measured Total Dissolved Solids(Evap@180°C) mg/L = na Measured Total Suspended Solids mg/L = na

# CHEMICAL COMPOSITION

CATIONS		mg/L	meq/L	ANIONS		mg/L	meq/L
Ammonium	as NH <sub>4</sub>	na	na	Bromide	as Br	na	na
Potassium	as K	9571	244.78	Chloride	as CI	16998	478.82
Sodium	as Na	4749	206.57	Fluoride	as F	na	na
Barium	as Ba	na	na	Hydroxide	as OH	nd	nd
Calcium	as Ca	154	7.68	Nitrite	as NO <sub>2</sub>	na	na
Iron	as Fe	na	na	Nitrate	as NO <sub>3</sub>	nd	nd
Magnesium	as Mg	35	2.88	Sulphide	as S	na	na
Strontium	as Sr	na	na	Bicarbonate	as HCO3	1013	16.61
Boron	as B	na	na	Carbonate	as CO <sub>3</sub>	nd	nd
	•			Sulphite	as SO <sub>3</sub>	na	na
				Sulphate	as SO <sub>4</sub> ·	479	9.97
Total Cations		14509	461.92	Total Anions		18490	505.40

### DERIVED PARAMETERS

a)	Ion Balance	(Diff*100/Sum)	(%)	=	4.49
----	-------------	----------------	-----	---	------

b) Total Alkalinity (calc as CaCO<sub>3</sub>) (mg/L) = 830

c) Total of Cations + Anions = 32999 (measured dissolved salts) d) Theoretical Total dissolved salts = (From Electrical Conductivity)

34752

### **QUALITY CONTROL COMMENTS**

Item	Actual Value	Acceptance Criteria	Satisfactory? (Yes/No)
Ion Balance (%) =	4.49	5%	Yes
Undetected ions %=	5.04	10%	Yes
(from comparison of	measured vs theoretical salts deri	ved from measured conductivity	)
Expected pH range		< 8.3	Yes
% difference between	measured total dissolved solids	and	
calc total dissolved sa	alts (from ionic comp) = na	5%	na
na = not applicable			If No - what action is
nd = not detected			recommended by Amdel
is = insufficent sampl	e		i i i i i i i i i i i i i i i i i i i



# TABLE 1 - WATER ANALYSIS

WELL / ID: Gordon-1,DST-2 (Sample 12)

SAMPLE TYPE: Water

SAMPLE POINT: Bottom Of Sample Chamber

DATE COLLECTED -

DATE RECEIVED: 24/07/97

**JOB NUMBER: LQ6104** 

FORMATION: -INTERVAL: -

COLLECTED BY: Client

### PROPERTIES:

pH (measured) = 6.87Resistivity (Ohm.M @  $25^{\circ}$ C) = 0.18 Electrical Conductivity ( $\mu$ S/cm @ 25°C) = 54300 Specific Gravity (S.G. @ 20°C) = na Measured Total Dissolved Solids(Evap@180°C) mg/L = na Measured Total Suspended Solids mg/L = na

## CHEMICAL COMPOSITION

CATIONS		mg/L	meq/L	ANIONS		mg/L	meq/L
Ammonium	as NH <sub>4</sub>	na	na	Bromide	as Br	na	na
Potassium	as K	9848	251.87	Chloride	as CI	17484	492.51
Sodium	as Na	5136	223.40	Fluoride	as F	na	na
Barium	as Ba	na	na	Hydroxide	as OH	nd	nd
Calcium	as Ca	166	8.28	Nitrite	as NO2	na	na
Iron	as Fe	na	na	Nitrate	as NO <sub>3</sub>	nd	nd
Magnesium	as Mg	39	3.21	Sulphide	as S	na	na
Strontium	as Sr	na	na	Bicarbonate	as HCO3	1132	18.56
Boron	as B	na	па	Carbonate	as CO <sub>3</sub>	nd	nd
				Sulphite	as SO <sub>3</sub>	na	na
				Sulphate	as SO <sub>4</sub>	482	10.04
Total Cations		15189	486.76	Total Anions		19098	521.10

# DERIVED PARAMETERS

a) Ion Balance	(Diff*100/Sum)	(%)	=	3.41	
a) IUII Dalance	(Dill 100/Sull)	(/0)	_	J.41	

b) Total Alkalinity (calc as  $CaCO_3$ ) (mg/L) = 928

c) Total of Cations + Anions = (measured dissolved salts)

d) Theoretical Total dissolved salts = (From Electrical Conductivity)

34752

### **QUALITY CONTROL COMMENTS**

Item	Actual Value	Acceptance Criteria	Satisfactory? (Yes/No)			
Ion Balance (%) =	3.41	5%	Yes			
Undetected ions % =	1.34	10%	Yes			
(from comparison of	measured vs theoretical salts derive	ed from measured conductivity)				
Expected pH range		< 8.3	Yes			
% difference between	measured total dissolved solids an	đ				
calc total dissolved sa	alts (from ionic comp) = na	5%	na			
na = not applicable			If No - what action is			

nd = not detected

recommended by Amdel



Amdel Limited A.C.N. 008 127 802

Petroleum Services PO Box 338 Torrensville Plaza SA 5031

Telephone: (08) 8416 5240

Facsimile: (08) 8234 2933

22 May, 1997

Santos Limited GPO Box 2319 ADELAIDE SA 5001

Attention:

A. Pietsch

# REPORT LQ5871 - Part 2

CLIENT REFERENCE:

C18994

WELL NAME/RE:

Gordon-1

MATERIAL:

Mud Filtrate

WORK REQUIRED:

Water Analysis

Please direct technical enquiries regarding this work to the signatory below under whose supervision the work was carried out. This report relates specifically to the sample or samples submitted for testing.

Brian L. Watson

Manager

**Petroleum Services** 

Amdel Limited shall not be liable for loss, cost, damages or expenses incurred by the client, or any other person or company, resulting from the use of any information or interpretation given in this report. In no case shall Amdel Limited be liable for consequential damages including, but not limited to, lost profits, damages for failure to meet deadlines and lost production arising from this report. This document shall not be reproduced except in full and relates only to the items tested.

# 1. INTRODUCTION AND RESULTS

One (1) sample was received for standard water analysis (WA-10-01). All analyses were performed according to APHA methods (19th Edition). Results are presented on the following page.



### TABLE 1 - WATER ANALYSIS

WELL / ID: Gordon-1, DST-1 (Sample 3)

SAMPLE TYPE: Mud Filtrate

SAMPLE POINT: -

DATE COLLECTED: 29/04/97, 2400 h
DATE RECEIVED: 20/05/97

JOB NUMBER: LQ5871 - Part 2

FORMATION: INTERVAL: COLLECTED BY: Client

### PROPERTIES:

pH (measured) = 9.15 Resistivity (Ohm.M @ 25°C) = 0.14

Electrical Conductivity (μS/cm @ 25°C) = 74000

Specific Gravity (S.G. @ 20°C) = na

Measured Total Dissolved Solids(Evap@180°C) mg/L =

Measured Total Suspended Solids mg L = na

# . CHEMICAL COMPOSITION

CATIONS		mg/L	meq/L	ANIONS		mg/L	meq/L
Ammonium	as NH₄	na	na	Bromide	as Br	na	na
Potassium	as K	25592	654.53	Chloride	as CI	25646	722.42
Sodium	as Na	2566	111.61	Fluoride	as F	na	na
Barium	as Ba	na	na	Hydroxide	as OH	nd	nd
Calcium	as Ca	nd	nd	Nitrite	as NO2	na	na
Iron	as Fe	na	na	Nitrate	as NO3	nd	nd
Magnesium	as Mg	nd	nd	Sulphide	as S	na	na
Strontium	as Sr	na	na	Bicarbonate	as HCO3	397	6.51
Boron	as B	na	na	Carbonate	as CO <sub>3</sub>	195	6.50
				Sulphite	as SO <sub>3</sub>	na	na
				Sulphate	as SO <sub>4</sub>	932	19.40
Total Cations		28158	766.14	Total Anions		27170	754.84

### DERIVED PARAMETERS

is = insufficent sample

a) Ion Balance (Diff*100/Sum) (%) =	0.74	d) Theoretical Result of Evaporation Test =	47360
b) Total Alkalinity (calc as CaCO <sub>3</sub> ) (mg L) =	651	(From Electrical Conductivity)	
c) Total of Cations + Anions = 55328		e) 0.6 x Concentration of Bicarbonate ion* =	238.2
(measured dissolved salts)		f) Theoretical Total Dissolved Salts d) + e) =	47598.2

### QUALITY CONTROL COMMENTS

Item Actual Value		Ad	cceptance Criteria	Satisfactory? (Yes/No)	
Ion Balance (%) =	0.74		5%	Yes	
Undetected ions % =	-16.24		10%	Yes	
(from comparison of	measured vs theoretical s	alts derived from	measured conductivi	ty)	
Expected pH range			< 8.3	Yes	
% difference between	n measured total dissolved	l solids and			
calc total dissolved sa	alts (from ionic comp) =	na	5%	na	
na = not applicable	•			If No - what action is	
nd = not detected				recommended by Amdel	

**APPENDIX VII: PALYNOLOGICAL ANALYSIS** 



# APG Consultants

Report 640/05 SANTOS File 1997/20

Palynostratigraphy of SANTOS Gordon # 1 Otway Basin, Victoria

for SANTOS Ltd

P.L. Price 30 October, 1997

# Gordon #1

Table of Contents	Page
Summary of Conclusions	2
Introduction	. 3
Palynostratigraphy	4
Otway Basin Palynostratigraphic Nomenclature	4
Otway Basin Palynostratigraphic U	nits 9
Otway Basin Lithostratigraphic Uni	its 10
Sample Reliability and Biostratigraphic Resolution	ı 11
Gordon #1 Index Species Distribution	n 12
Gordon#1 Palynostratigraphy	13
Unit APK321; lower Eumeralla Formation	13
Unit APH21; Laira Formation	13
Unit APK12; Pretty Hill Sandstone	14
Unit APK11; Casterton Formation	15
Correlation with Adjacent Well Sections	16
Introduction	16
Basal Eumeralla Formation	17
Upper Laira Formation	17
Lower Laira Formation - Pretty Hill Sandsto	one 18
Otway Basin Palynostratigraphic Units Otway Basin Lithostratigraphic Units Sample Reliability and Biostratigraphic Resolution Gordon #1 Index Species Distribution Gordon#1 Palynostratigraphy Unit APK321; lower Eumeralla Formation Unit APH21; Laira Formation Unit APK12; Pretty Hill Sandstone Unit APK11; Casterton Formation Correlation with Adjacent Well Sections Introduction Basal Eumeralla Formation Upper Laira Formation Lower Laira Formation - Pretty Hill Sandstone Casterton Formation	18
References	19

# Appendices

Appendix 1; Palynostratigraphic Data Table

Appendix 2; Species Distribution Charts

Species Checklist

Oldest Occurrence list

Appendix3; Species and Group Diversity charts

# Gordon #1

# **Summary of Conclusions**

# Biostratigraphy

•	1035.0m - 1118.0m	APK321	lower Eumeralla Formation
•	1118.0m - 1184.0m	Unc	onformity
•	1184.0m - 1275.0m	APK212	upper Laira Formation
<b>*</b>	1369.0m - 1510.0m	APK21	Laira Formation
•	1536.0m - 1761.0m	APK122	upper Pretty Hill Formation
•	1768.0m - 1882.0m	APK12	Pretty Hill Formation
•	2126.0m - 2356.25m	APK11	Casterton Formation

# Depositional Environment

(from the perspective of the sampled sediments only)

•	1035.0m	Fluvial, overbank & billabong
<b>*</b>	1063.0m - 1118.0m	Fluvial to shallow lacustrine
•	1184.0m - 1882.0m	Fluvial, overbank & billabong; paralic coastal plain
•	2126.0m - 2205.0m	Lacustrine
•	2215.0m - 2325.0m	Fluvial, overbank & billabong
•	2337.5m - 2350.0m	Lacustrine
•	2356.25m	Peat Bog

# Maturity

(from a cursory examination only)

•	1035.0m - 1118.0m	Immature Dry Gas Zone
•	1184.0m - 2356.25m	Early Mature; upper "Oil Window"

# Hydrocarbon Source Potential

(based on a cursory examination and from the perspective of the sampled sediments only)

<b>•</b>	1035.0m - 1063.0m	Not a source rock
•	1105.0m	Moderate gas source with some oil potential
•	1118.0m - 1184.0m	Not a source rock
•	1211.0m	Moderate gas source with some oil potential
•	1275.0m - 1882.0	Not a source rock
<b>þ</b>	2126.0m - 2160.0m	Meagre potential for mostly gas
<b>*</b>	2205.0m - 2325.0m	Moderate gas source with some oil potential
•	2337 0m - 2356 25m	Rich ans and oil source

# Gordon #1

# Introduction

Thirty sidewall core samples from Gordon #1 representing the lower part (Early Cretaceous to latest Jurassic) of the Otway Basin section sequence penetrated by Gordon #1 were submitted for palynological examination. The study was directed primarily towards establishing the biostratigraphic succession and age relationships of the sampled section.

The samples were examined in detail from unoxidized  $+20\mu m$  fraction,  $+20\mu m$  -80 $\mu m$  oxidised 1.65sg floats fraction and  $+80\mu m$  oxidised 1.65sg floats fraction to determine their palynomorph assemblage characteristics; species lists were compiled from these examinations. The deposition environment, palynofacies organic facies characteristics and level of thermal alteration of the sampled section were established only in general terms; neither statistical assemblage data nor detail transmitted light - fluorescent examination of the unoxidized total organic fraction required for such studies was undertaken.

The biostratigraphic and broad qualitative palynofacies and environmental data for Gordon #1 are tabulated on the appended Palynostratigraphical Data Table; the text provides an overview of the results supplementing the sample by sample descriptions set out in the Data Tables. The distribution of all taxa identified is presented in the appended charts as alphabetical check lists and oldest occurrence lists for the Early Cretaceous to Late Jurassic palynofloras; the distribution of a subset including the index taxa is given on Page 12. Graphical presentations of palynomorph species diversity within various morphological and presumed phylogenetic groups are appended also.

# Palynostratigraphy

# Otway Basin Palynostratigraphic Nomenclature

The biostratigraphic nomenclature adopted for this study is based upon that of Price et al, 1985 and Filatoff & Price, 1988 developed primarily for the Surat and Eromanga Basin sections but adapted for the Otway Basin by Price, 1993, 1995, 1996. The units and their relationship to the nomenclatures of Morgan, 1985 and 1992, Dettmann, 1986 and Dettmann and Playford, 1969 and Morgan et al, 1995 are summarised on Page 9 and the relationship of the palynostratigraphic units to the Otway Basin lithostratigraphy is presented on Page 10. The lithostratigraphical conventions of Morton et al 1995 have been adopted (with slight modification). However, the evidence for an unconformity between the Casterton Formation and the lower Crayfish Sub Group (hence the exclusion of the Casterton Formation from the Otway Group) is questioned and there seems to be a need for revision and formal definition of the various lithofacies of the Pretty Hill Formation.

The units of Dettmann, 1963 and 1986, Dettmann and Playford, 1969, Morgan, 1985, 1988, 1989 and 1992 have been used widely in Otway Basin studies. These nomenclatures however, have been applied in different ways in the various well sections giving some confusion as to what is represented by a particular unit in any given study. Further, there is no consensus as to the precise order of appearance of certain of the Early Cretaceous index taxa in the Otway Basin as their introduction is blurred by the extent of the base Eumeralla unconformity, facies constraints and, possibly, floral migration.

Morgan et al, 1995 reviewed and revised the Otway Basin palynostratigraphy as part of the comprehensive stratigraphic review of the western Otway Basin by MESA (Morton and Drexel Eds., 1995). Although the revised nomenclature of Morgan et al, 1995 gives some stability to the Otway Basin palynostratigraphy, the units of Price et al, 1985 and Price, 1993, 1995, 1996 have been used in this study in an attempt to increase the biostratigraphic resolution and to lessen any possible

ambiguity with the earlier nomenclatures arising from differences of interpretation as to the order of entry of certain index taxa. The equivalent units of Morgan et al, 1995 however, are given also in the text to assist in relating the results of this study to the stratigraphic interpretation given in the 1995 MESA compilation; reference should be made to Page 9 if there is a need to relate an earlier nomenclature to this study.

In relating this study to earlier subdivisions, particular care should be taken with the *F. wonthaggiensis* Zone, the *C. hughesii* Zone and their stratigraphic relationship as their definition and application have varied from study to study (see Page 9). This variation in interpretation reflects their development as reliable Otway Basin palynostratigraphic units with additional data becoming available and relates also to regional differences between the Early Cretaceous palynofloras of the Otway Basin and other basins (see Dettmann, 1986 and Dettmann *et al*, 1991); certain of the "index" species prominent in areas such as the Surat/Eromanga Basins, are very scarce and sporadic in their distribution within the Otway Basin.

Dettmann, 1986 and Dettmann et al, 1991 also consider the time taken for migration of the parent plants from their point of evolution to the various basins as being discernible and resulted in different order of appearances for the index forms in these basins. The recent well section studies (eg Morgan, 1989, 1990, 1991, 1992, 1993, 1993; Price, 1993; Morgan et al, 1995) however, record a similar order of appearance of the index forms in the Otway Basin as Price et al, 1985 and Filatoff and Price, 1988 do for the Eromanga Basin. It is likely that facies and environmental variations (giving rise to more subtle and less systematic differences in the distribution of the index forms) are at least as significant as the migration processes suggested by Dettmann, 1986 and Dettmann et al, 1991. The application of the Early Cretaceous and Late Jurassic palynostratigraphic units in the Otway Basin, as in other basins, requires the recognition of the facies and preservational constraints upon the distribution of "marker" taxa in order to achieve a reliable biostratigraphic correlation; these factors are still not well understood. Thus, the down hole logging

of the various "index" taxa must be tempered by palynofacies considerations before a palynostratigraphic unit is assigned.

The Laira Shale/Pretty Hill section palynofloras seem less diverse than the equivalent Cadna-Owie/Murta/Namur Eromanga Basin section perhaps reflecting a more restricted range of environments within the Otway Basin catchment. Ferns, although prominent, are less diverse in the Crayfish Sub Group than they are in the Eromanga Basin. For example the fern derived index group Cicatricosisporites spp is scarce in the APK2 and APK1 (Foraminisporis wonthaggiensis Zone and C. australiensis Zone) assemblages such that the distribution of Cicatricosisporites australiensis may be too sporadic in many of the Otway sections to be a reliable biostratigraphic marker; however, this seemed not to be a problem in Gordon #1. It is worth noting that, in certain facies within the Surat and Eromanga Basins, the distribution of Cicatricosisporites can be erratic also. Considerable reservation is held for the biostratigraphic utility of presumed bryophyte form Foraminisporis wonthaggiensis within APK21; although a reliable marker in the Surat and Eromanga Basins, it has proved to be too elusive to be of any value in the resolution of the Crayfish Sub Group.

The relationship of the oldest occurrence of *Pilosisporites notensis* to that of *Foraminisporis asymmetricus* and the *P. notensis* Zone - *F. wonthaggiensis* Zone boundary (base APK22) and the unconformable boundary between the Eumeralla and the Katnook Sandstone - Laira Formation is perhaps blurred by differing applications of the earlier nomenclatures. In Katnook 2 (which seems to represent the most complete section at the basal Eumeralla Formation - Katnook Sandstone - Laira Formation interval) Morgan, 1989 placed the base of the "lower *C. hughesii* Zone" near the base of the Eumeralla Formation at 1896.5m but records *F. asymmetricus* down to 1925m (within the Windermere Sandstone or the top of the Katnook Sandstone, depending upon interpretation) and *P. notensis* at 2103m (within the uppermost Laira Formation just below the Katnook Sandstone); both taxa are recorded from SWC samples and therefore, should not represent contamination.

Thus, while the MESA correlations (Morton et al 1995) show the P. notensis Zone to be equivalent to the "C. hughesii Zone", their extent is restricted to the base of the Eumeralla Formation. Such a correlation seems to overlook the distribution of P. notensis (and perhaps F. asymmetricus) in Katnook 2 which suggests that the P. notensis Zone (as with APK22) should extend into the Crayfish Group. In most other areas (eg Sawpit #1 and Zema #1), lithological and seismic evidence suggests there is an erosional break between the Eumeralla Formation and Crayfish Sub Group. Thus, it is acknowledged that the P. notensis Zone is restricted to the Eumeralla Formation in such section, but it is a result of the loss of the lower part of the P. notensis Zone (equivalent to the APK22) with the erosion the top of the Crayfish Sub Group.

1.8

A further complication to the resolution of the C. hughesii - F. wonthaggiensis Zone boundary is a difficulty in the identification of Foraminisporis asymmetricus. Certain of the morphological variants within an undescribed complex (including "Verrucosasporites" "pseudoasymmetricus" 1410) in APK32 to APJ6 palynofloras can resemble F. asymmetricus and may have blurred the distribution of F. asymmetricus with respect to the base Eumeralla Formation unconformity. Similarly, morphological variation within the Cooksonites variabilis complex may account for some of the records of Coptospora paradoxa in APK3 and APK2 associations.

The occurrence of *Microfasta evansii* as a means of distinguishing the upper Crayfish Sub Group from the Eumeralla Formation (Morgan *et al* 1995) can no longer be relied upon as this form has been recovered from a number of sections within the lower Eumeralla Formation both in the Robe Trough and the Penola Trough; its occurrence in APK3 associations is proving to be the rule rather than the exception in the western Victorian region where Gordon was drilled. The upwards extension of *M. evansii's* range into APK32 is consistent with its distribution in other basins and the APK32 occurrences in the Otway Basin seem too numerous and with too wide a geographic distribution for them to be dismissed as reworking from the underlying Crayfish Sub Group.

Reliance on the extinction (youngest occurrence) of Cyclosporites hughesii as an indication of the top of the P. notensis Zone - base of the C. striatus Zone boundary (base APK4) in the Otway Basin should be accepted with caution as C. hughesii is known to persist up through the C. paradoxa Zone (APK5) in the Eromanga Basin; the data from Digby #1 suggests that it may do the same in parts of the Otway Basin.

Notwithstanding these differences of interpretation, certain of the marker species have a regional consistency recognised by most students of the Otway and Eromanga palynology and these have been given greater emphasis in this study. These include the oldest (initial) occurrence of *Pilosisporites parvispinosus* (base APK321), *Pilosisporites notensis* (base APK22), *Dictyotosporites speciosus* (base APK122), *Cyclosporites hughesii* (base APK121).

Of particular interest in terms of increased reliability of unit APK321 (uppermost part of the Lower *P. notensis Zone*) is the presence of the distinctive undescribed species *Foraminisporis wonthaggiensis "lunaris"* sp 1519 (?=F. "reticulowonthaggiensis" of Morgan). This form has a restricted range in both the Otway and Eromanga Basins being confined to about the introduction of *Pilosisporites parvispinosus* and not extending up the section much beyond the top of APK3. The presence of *F. wonthaggiensis "lunaris"* within APK321 (upper Lower *P. notensis* Zone) is a consistent feature of many Otway Basin wells and enhances the *P. parvispinosus* oldest occurrence datum as a reliable correlatable event.

SANTOS Gordon #1

# OTWAY BASIN NOMENCLATURE

					M. evansii	」 r. woninaggiensis Iunaris		M. evansii consistent 1 to frequent		:	→ M. evansii			-	27.	
		nner			•	•	•	•	įs		•					
Phyllocladidites mawsonii		C. paradoxa Crybelosporites sp. cf. C. brenner (sp. 1255) Phimopollenites pannosus	Pilosisporites grandis Coptospora paradoxa	S. S	Cooksonites variabilis	- Filosisponies parvispinosus 1 Foraminisporis asymmetricus	Pilosisporites notensis	Triporoletes reticulatus	J Foraminisporis wonthaggiensis	1 Dictyotosporites speciosus	Cyclosporites hughesii	Cicatricosisporites spp.	Foraminisporis dailyi	Ceratospontes equalis     Betitrilates watherpoensis	Murospora florida	
						•		112	=	22	21		2 5	Ť	T	i
ants					APK322 APK321			APK212	APK211	APK122	APK121		APJ622 APJ621	1		
APG Consultants			APK52 APK51		APK32	APK31	APK22	APK21		APK12		APK11	APJ62	APJ61		
IA I	APK7	APK6	APK5	APK4	APK3			APK2			APK1		AP J6		APJ5	
995 1y	sn	50	ם ח		1		د	⊃			ם	٦	sisı	<del></del>	T	ן ן
Morgan <i>et at</i> ; 1995 (MESA Otway Volume)	A. distocarinatus	P. pannosus	C. paradoxa	C. striatus		P. notensis		n diameter	r. woninag- qiensis	<b>.</b>		C. australiensis	R. watherooensis			
Morgan, 1992 (Zema 1)	A. distocarinatus	P. pannosus	C. paradoxa L	C. striatus	D	C. hughesii		U Sofficer	r. woninag- qiensis	,		C. australlensis	R. watherooensis			
Morgan, 1985 (Otway Basin Review)	A. distocarinatus	P. pannosus	C. paradoxa	C. striatus	Π						C. stylosus			<b>-</b>		
Dettman 1986	A. distocarinatus	P. pannosus	C. paradoxa U	C. striatus		D. speciosus C. hughesii					C. stylosus					
Dettman & Playford, 1969	A. distocarinalus	P. pannosus	C. paradoxa	C. striatus	sns	oio G huahesii	ds (	-1-1-	-!			C. stylosus		Jest Jest Jest Jest Jest Jest Jest Jest		April 1996

# STRATIGRAPHIC NOMENCLATURE

	,	AGE	PALYNO	STF	RATIGRA	APHY			LITH	IOSTRATIGRAPHY
			Morgan <i>et al</i> . 1	APG Consultants						
OLIG	OCE	NE-MIOCENE			APH6 -	API	14			GAMBIER LIMESTONE
PALI	EOC	ENE-EOCENE			APH3	API	<del>-</del> 11	WANGERRIP G	ROUP	
LAT	E CI	RETACEOUS			APA5	— API	<b>&lt;</b> 7	SHERBROO GROUP	ok	
			P. pannosı	ıs	Д	PK6			•	
		ALBIAN	C. paradoxa	U	APK5	APK5				======================================
			C. striatus	<u> </u>	Α	APK4		2 ZHEATHFIELD MBR		
		APTIAN		U	A DIZO	APK 32	322 321	₩. evansii		FORMATION
	E	BARREMIAN	P. notensis	L	APK3	APK31				WINDERMERE MEMBER Z
CRETACEOUS		HAUTERIVIAN				APK2	2			KATNOOK SANDSTONE
				U	APK2		212	common M. evansii	JUP	
EARLY		VALANGINIAN	nsis			APK21	211		SUB-GROUP	LAIRA FORMATION :
	MIAN		wonthaggiensis					ОТWАУ	,	PRETTY HILL SANDSTONE
	NEOCOMIAN	BERRIASIAN	F. wor	L	APK1	APK12	122		CRAVFISH	SAMPIT S'ST Z
				U	ALICI		121	M. evansii ◀——J		
			C. australiensis	_		APK	1-			
L. JUR.		TITHONIAN	R. watherooel	nsis	APJ6					
~~	$\sim$	MMERIDGIAN AEOZOIC	- Wallerood	~	AF30	APJ	~~ ~~	<b> </b>	~~	- V = - V = V = V = V = V = V = V = V = - V

# Sample Reliability and Biostratigraphic Resolution

Although the section between 1000m and 2500m (spanning from within the lower part of the Eumeralla Formation to within the basement rocks at the well's total depth) was sampled by sixty SWC samples, only some thirty were suitable for palynological study. Most of the samples from within the Pretty Hill Sandstone section and the basal nine SWCs shot in the metamorphic basement were excluded. The basal Eumeralla unconformity was not closely defined because of the unsuitability of SWC56 1149.5m (a sandstone) and a degree of ambiguity of the assemblages from 1184.m and 1211m (unusual palynofacies). The sample coverage in the Laira was a little sparse given the difficulty in recovering diagnostic assemblages from this interval in other wells. Although covered by a high sample density, the Pretty Hill section included very few shale intervals and thus its age relations to the Laira Shale and the Casterton Formation in this part of the Otway Basin remains somewhat enigmatic. The Casterton was closely sampled giving a clearer understanding of the age of the Casterton than has been achieved in previous intersections.

The majority of the SWC samples were sufficiently coherent to permit removal of the drilling mud. Only in one or two samples was contamination observed and this was extremely minor and had no influence on the biostratigraphic interpretation or resolution. The preservation of the recovered palynofloras was better than is generally achieved in the Crayfish Sub Group or the Casterton Formation. The local intrusions that affected the preservation of the Digby #1 palynofloras seemed not to be an influence in the Gordon section.

Ceratospor i tes aqual is 1243 Cicatr i cosispor i tes qual is 1243 Cicatr i cosispor i tes qual is 1243 Cicatr i cosispor i tes qual amis solu Cicatr i cosispor i tes autral i emis solu Cicatr i cosispor i tes autral i emis solu Cicatr i cosispor i tes autral emis solu Cicatr i cosispor i tes autra oras solu Concavissi in i spor i tes autra oras solu Concavissi in i spor i tes autra i cosis Concavissi in i spor i tes autra i cosis Concavissi in i spor i tes autra i cosis Concavissi in i spor i tes autra i cosis Concavissi i i i spor i tes autra i cosis Concavissi i i i i i i i i i i i i i i i i i	
BISACCATE PULLEN Cen. et spp. Indt. 2884	+ + + + + + + + + + + + + + + + + + + +
BishLate Tullen Gib. et Spp. Mut. 2004 Leinsphaeridia Spp. 1461 Microfasta evansii var. "evansii" 4920 Microfasta evansii var. "marganii" 1154	+ + + + + + + + + + + + + + + + + + +
Michiefidium Francis 130	+ + +

# Gordon #1 Palynostratigraphy

# Unit APK321; lower Eumeralla Formation

The diverse fern associations recovered from SWC60 1035m which included Cooksonites variabilis, Pilosisporites notensis, P. parvispinosus, Cyclosporites hughesii and Foraminisporis wonthaggiensis "lunaris"; Cicatricosisporites spp was a notable component. Such associations are typical of APK321 (lower C. hughesii Zone) palynofloras though out eastern Australia including those from the lower Eumeralla Formation. SWC 59 1063m yielded a more restricted palynoflora but the presence of Pilosisporites notensis and P. parvispinosus clearly indicate its affinities with APK32. The diverse palynoflora from SWC57 1118m is also assignable to APK321 although Foraminisporis wonthaggiensis "lunaris" was absent and Pilosisporites were represented by a slightly different suite including P. ingramii and with P. parvispinosus extremely rare; perhaps it is representative of the basal part of APK321.

The association recovered from SWC58 1105m was restricted, bearing some similarity with certain of the bland Crayfish Sub Group palynofloras from lower in the section; thus, apart form lying between typical APK321 palynofloras, there was little to associate it with APK3. The contrast in palynofacies in the lower Eumeralla Formation is a reflection of lithofacies variation and emphasis the need for close sampling of the section to achieve reliable biostratigraphic resolution of the mid Otway Group unconformity.

### Unit APK21; Laira Formation

The restricted associations recovered from 1184m to 1510m included Dictyotosporites speciosus but lacked both the APK3 forms typical of the overlying Eumeralla assemblages and Pilosisporites notensis; as such, they are referable to Unit APK21 or APK122. The occurrence of Microfasta evansii through out the interval (deepest occurrence in notable numbers at 1510m) and the tentative identification of Triporoletes reticulatus at 1275m suggests APK212 may extend down to 1275m and

APK21 may be represented to 1510m; however, as is usually the case in APK211 palynofloras from the Otway Basin, the index taxa, *Foraminisporis wonthaggiensis*, was not recorded.

The upper two of the associations referred to APK21 (SWC55 1184m and SWC54 1211m) are not typical of APK21 and their assignment should be accepted with some caution. These associations were very restricted in species diversity, dominated by Cyathidites spp and included a prominence of Cicatricosisporites spp... The abundance of this latter form is a little perplexing in that, although it extends down to the base of the succeeding palynostratigraphic unit (APK1), it has proved to be a scarce, intermittent component of the Crayfish Sub Group in other parts of the Otway Basin; however, in contrast, it is usually prominent in the overlying Eumeralla Formation palynofloras. Additionally, the prominence of the Cooksonites variabilis complex representatives perhaps is more in keeping with the lower Eumeralla than the upper Crayfish palynofloras. Thus, it is possible that these two associations may represent a restricted (specialised sand facies) Eumeralla Formation palynoflora similar to that at 1105m. Nevertheless, weight has been given to the absence of the APK3 index taxa in giving a tentative APK2 assignment and referring the section at 1184m and 1211m to the Crayfish Sub Group pending a regional review of the base Eumeralla - upper Crayfish interval in adjacent well sections.

# Unit APK12; Pretty Hill Sandstone

The associations from the Pretty Hill Sandstone (1536m - 1882m) were mostly poorly reserved and restricted; *Cyclosporites hughesii* was present to the base of the sampled interval with *Dictyotosporites speciosus* extending to 1761m; *Microfasta evansii* occurred sporadically as only isolated specimens to 1761m. On the basis of these associations, the section to 1761m is considered to be no older than APK122 (lower *Foraminisporis wonthaggiensis* zone of Morgan *et al* 1995) with the section to 1882m being at least unit APK12 (upper *C. australiensis* zone). The possibility that the upper part may be as young as APK211 can not be excluded given the poor palynomorph recoveries from this section.

The lower Pretty Hill Sandstone (approximately 1885m to 2120m), in common with the adjacent well section, was a almost entirely arenaceous retuning no argillaceous samples suitable for palynological examination.

# APK11; Casterton Formation

The high to moderate palynomorph yields recovered from the samples spanning 2126m to 2356.25m together with the prominence of inaperturate pollen and thin walled leiospheres, sparse restricted land plant spore component and restricted saccate pollen component (including few representatives of the trisaccate form *Microcachryidites antarcticus*) are characteristics of the Casterton Formation palynofacies. The diffuse translucent nature of the palynodebris is also characteristic although this aspect of the organic facies was not studied in any detail in this well. The sporadic occurrence of *Cicatricosisporites spp* almost to basement and the consistent occurrence of *Ceratosporites equalis* indicate the section is assignable to APK1 and the presence of *Cyclosporites sp cf C. hughesii* at 2126m suggests proximity to unit APK12 at the top of the Casterton section.

The bulk of the Casterton Formation has been suspected of being somewhat older than APK1, perhaps representative of the Late Jurassic unit APJ6. However, the present data (based upon the most comprehensively sampled section with some of the best preserved Casterton palynofloras recovered to date) suggests the "Jurassic" character of the Casterton assemblages (few M. antarcticus, prominence of inaperturate pollen, restricted land plant spore component sometimes with Contignisporites spp notable) is more a reflection of the specialised aquatic depositional environment associated with the initial rift development, than its previously supposed antiquity.

# Correlation with Adjacent Well Sections

## Introduction

In considering the palynostratigraphic data from Gordon #1, data from Digby #1 (Price, 1994), Bus Swamp #1 (Morgan, 1993; Alley, 1993; Burger, 1993), Mocamboro #11 (Morgan, 1991), Casterton #1 (Morgan, 1986) and McEachern #1 (Morgan, 1990) were reviewed. It should be noted that no taxa distribution data were available for Casterton #1.

The data from Mocamboro #11 is a little ambiguous in that, if the available taxa distribution data is taken at face value, there is evidence of contamination (eg downward extension Coptospora paradoxa into APK2 associations) even though the study was based upon conventional cores and side wall cores. Alternatively, it is possible there is some confusion over the identity of certain Cooksonites variabilis complex representatives. If the former is accepted, then the down ward extension of APK3 to the top of the Pretty Hill sand may be attributed to contamination but if forms such as C. paradoxa and Foraminisporis asymmetricus have been confused with the some similarly constructed forms known to occur in APK2 associations (and thus, there is no contamination problem), then the downward extension of P. notensis (and hence APK22) would suggest the facies relation of the Laira and Pretty Hill and the position of the Eumeralla unconformity relative to the other wells seems to be rather complex. Clearly there is a need to reprocess core samples from Bus Swamp #1, Casterton #1 and Mocamboro #11 and reconsider the palynostratigraphy and lithostratigraphy of the basal Eumeralla - Crayfish Sud Group transition in all the bores from this region.

# Basal Eumeralla Formation

The APK321 association from SWC60 1035mis representative of the lower Eumeralla Formation in other wells in the Otway Basin. However, from data in the Katnook region, it seems not to be the basal unit as APK31 is considered to be the

oldest Eumeralla association with APK22 being representative of the uppermost Crayfish Sub Group were that unit is fully developed. Unit APK321 is perhaps the most consistent of the lower Eumeralla Formation and Crayfish Sub Group palynofloras in terms of its ease of recognition and lateral distribution in the lower Otway Basin sequence. In this respect, it seems to be a reliable datum from which to start to unravel the subtlety of the mid Otway Group unconformity.

APK321 is represented in Gordon #1 (1035m - 1118m) Digby #1 (1096m), Bus Swamp #1 (?830m - 862m) and Mocamboro #11 (?557.2m - 777.8m). However, the distinction of APK22 and APK31 from APK321 can be difficult to establish in individual samples as several of the index can be somewhat sporadic in their distribution particularly within the more arenaceous intervals. For example, in Gordon #1, had SWC57 not been available, the placement of the restricted association from SWC58 1105m would have been a problem as it may have been taken to be as old as APK122 or APK2. Clearly, a high sample density and a comparison of adjacent well sections assists in the amelioration of the vagaries of facies upon the biostratigraphic resolution.

In Gordon #1 and Digby #1 APK321 seems to be represented the basal of Eumeralla while in Casterton #1 and Mocamboro #11 it is possible the basal Eumeralla section is marginally older being represented by APK31. However, the possibility that the APK31 associations are an impoverished APK321 palynoflora can not be eliminated on present data. It is of interest to note that in Casterton #1, Digby #1 and Gordon #1 Microfasta evansii is present in the APK3 associations emphasising the problems of relying upon this taxon as an indicator species confined to the Crayfish Sub Group in the Otway Basin.

# Upper Laira Shale

The downward extension of *Pilosisporites notensis* into Crayfish Sub Grouplike palynofloras is difficult to interpret in individual sections; the dilemma lies in the discrimination of impoverished APK3 Eumeralla associations from older APK22 Laira palynofloras. Such associations have been recovered from Digby #1 (1220.8m), Bus Swamp #1 (886m), McEachern #1 (1048m) and possibly Mocamboro #11 (965m) and are difficult to reconcile with a consistent lithological correlation of the section lying between the base of APK321 and the top of the Pretty Hill sand. If an extensive APK22 section is accepted (suggesting that the top of the Crayfish Sub Group is young as that at Katnook #2 section) then the possibility of an unconformity within the Crayfish Sub Group should be considered particularly if the antiquity of the Pretty Hill Sandstone is accepted.

# Lower Laira Shale - Pretty Hill Sandstone

With the possible exception of the of Mocamboro #11, the lower Laira Formation seems to be assignable to APK21, with APK122 (lower F. wonthaggiensis zone of Morgan et al 1995) extending into the upper half of the Pretty Hill sand. In some other parts of the western Otway Basin, unit APK21 extends into the upper part of the Pretty Hill sand facies. The base of the Crayfish sand facies in the Gordon region is probably APK121 (upper C. australiensis zone of Morgan et al 1995) although the lower Pretty Hill has relatively few palynologically productive samples.

## Casterton Formation

SANTOS Gordon #1

The Casterton Formation palynofloras are distinctive reflecting specialised palynofacies of a lacustrine depositional setting. As a the association are restricted in species diversity, they have given an impression of greater antiquity in the poorly preserved assemblages from sections sampled prior to the drilling of Gordon #1. On present data it seems probable that the Casterton in western Victoria and eastern South Australia is confined to APK11 (with a slight possibly of being as young as APK121 at the top). In this region of the Otway, there is little palynological evidence of a depositional break between Casterton Formation and the Pretty Hill Sandstone, particularly when considered in conjunction with the Sawpit #1 data. On this basis, there seems to be little justification for excluding the Casterton Formation from either the Otway Group or the Crayfish Sub Group.

# References

- Alley, N.F., 1993. Palynological dating and correlation of samples from Bus Swamp #1, Otway Basin, South Australia. MESA Report Book 93/43.
- Burger, D., 1993. Palynological examination of DEM Bus Swamp 1 stratigraphic hole, Otway Basin, Victoria. In Abele, C., Bus Swamp Report Appendix 9.
- Dettmann, M.E. 1963. Upper Mesozoic microfloras from south eastern Australia.

  Proceedings of the Royal Society of Victoria, 77, 1-148.
- Dettmann, M.E. 1986. Early Cretaceous palynofloras of subsurface strata correlative with the Koonwarra Fossil Bed, Victoria. *Memoirs of the Association of Australasian Palaeontologists*, 3, 79-110.
- Dettmann, M.E. & Playford, G. 1969. Palynology of the Australian Cretaceous: a review. In *Stratigraphy and palaeontology: essays in honour of Dorothy Hill* (ed. Campbell, K.S.W.), pp 174-210 (Australian National University Press, Canberra).
- Filatoff, J. and Price, P.L. 1988. A pteridacean spore lineage in the Australian Mesozoic. Mem. Assoc. Australas. Palaeontol., 5, 89-124.
- Morgan, R. 1980. Palynostratigraphy of the Australian Early and Middle Cretaceous. Mem. Geol. Surv. N.S.W., Palaeont., 18, 1-153.
- Morgan, R. 1985. Palynology review of 13 Otway Basin (South Australia) wells. Unpublished Report.
- Morgan, R., 1986. Palynology data sheet on Casterton #1. Palynology Rept.
- Morgan, R., 1990. Palynology of Gas and Fuel McEachern #1, Otway Basin, Australia. Morgan Palaeo Associates Report.
- Morgan, R., 1991. Palynology of Victorian Geological Survey Mocamboro #11, Otway Basin, Victoria. Morgan Palaeo Associates Report.
- Morgan, R., 1992. Palynology of Ultramar Zema 1, Otway Basin, South Australia.

  Morgan Palaeo Associates Report for SAGASCO/Ultramar
- Morgan, R., 1993. Updated Palynology of Bus Swamp #1, Otway Basin, Victoria, Australia. Morgan Palaeo Associates Report.

- Morgan, R., 1993. New palynology of the Laira Shale in the Katnook 1, 2 & 3,

  Banyula 1, Laira 1, Ladbroke Grove 1 and Kalangadoo 1 Otway Basin, South

  Australia. Morgan Palaeo Associates Report for SAGASCO
- Morgan, R., Alley, N.F., Rowett, A.I. and White, M.R., 1995. Chapter 6; Biostratigraphy. In Morton and Drexel Eds *Petroleum Geology of South Australia. Volume 1: Otway Basin.* Mines and Energy South Australia Report Book 95/12 95-101
- Morton, J.G.G., Alexander, E.M., Hill, A.J. & White, M.R., 1995. Lithostratigraphy and environments of deposition. In Morton and Drexel Eds *Petroleum Geology of South Australia. Volume 1: Otway Basin.* Mines and Energy South Australia Report Book 95/12 95-101
- Morton, J.G.G. & Drexel, J.F., (Eds) 1995. Petroleum Geology of South Australia.

  Volume 1: Otway Basin. Mines and Energy South Australia Report Book 95/12.
- Price, P.L., 1993. Palynostratigraphy, Organic Facies and Geochemistry of Sawpit #1, Otway Basin. APG Consultants Report 264/13 for Oil Company of Australia.
- Price, P.L., 1996. A review of the Palynostratigraphy of some Otway Basin Wells.

  APG Consultants Report 264/24
- Price, P.L. & Filatoff, J. 1990. Applications of morphological lineages in Australian palynostratigraphy. *Review of Palaeobotany and Palynology*, 65, 195-207.
- Price, P.L., Filatoff, J., Williams, A.J., Pickering, S.A., & Wood, G.R. 1985. Late Palaeozoic and Mesozoic palynostratigraphical units. *CSR Oil and Gas Div.*, *Palynol. Facil. Rep.*, 274/25, 1-20 (Queensland Dep. Mines Open File Rep. 14012).

# Appendix 1

Palynostratigraphical Data Table

Gordon #1



Gordon #1 File 97/20 (Report 640/05)

Page 1 of 8

		<del> </del>				T							
Bemarks		Land plant spores and pollen dominant. Bisaccate and trisaccate pollen	refunding profinitely, finaper totate power notable. Letti sportes profinitely, mostly <i>Cyathidites; Pilosisporites</i> notable and diverse. Lycopod spores conspicuous; mostly <i>Retitifietes.</i> Bryophyte spores notable and moderately diverge; mostly <i>Cooksonites</i> and <i>Foraminisporis</i> . Algal forms scarce.	Land plant spores and pollen dominant. Bisaccate pollen remnants prominent; inanaturate nollen norable. Forn snores prominent but restricted in diversity.	mostly <i>Cyathidites</i> . Lycopod spores conspicuous; mostly <i>Retitriletes</i> . Leiospheres and <i>S. reticulatus</i> notable	Palynoflora dominated by saccate pollen, ?inaperturate pollen and cuticle	rennants (nostry univentificable), chelluleprodeedli poller prominent. Spores prominent but restricted in diversity; Cyathidites minor, Retitriletes and Neoraistrickia conspicuous. Almost no bryophyte spores present. Algal forms	SCATCE. [The prominence of Cheirolepidiacean pollen, the scarcity of <i>Cicatricosisporites</i> and the absence of <i>Pilosisporites</i> and <i>Foraminisporis</i> are unusual in the Eumeralla ]	Palynoflora dominated by land plant spores; diverse fern association;	Cyathidites dominant (mostly <i>C. minor</i> but with <i>C. punctatus</i> conspicuous); Osmundacidites and Cicatricosisnorites prominent: <i>Pilosisnorites</i> notable.	Bryophyte spores notable and relatively diverse; Aequitriadites and	<i>cooksonites - Verrucosisportes</i> conspicadus, r <i>oranimisporis</i> group and sphagnaceous forms scarce. Lycopod spores sparse but moderately diverse.	Conifer pollen prominent; M. antarcticus conspicuous. Algal forms notable;
	Diversity	Moderate		Low		Low			High			<u> </u>	
Palynomorph	Yield ( <i>Org. Yield</i> )	High	[Extremely low]	Moderate	[Extremely low]	High	[High]		Moderate	[Extremely low]		, ,	
	Preservation	Fair		Fair	(Thin; over oxidised) [ <i>Extremely low</i> ]	Poor	[thin, corroded, fragmented]		Fair				
Inferred Deposition Environment	(Lithology)	Fluvíal	Sandstone, f. grained; & Claystone, slightly carbonaceous.	Fluvial lacustrine	Siltstone, mid grey, carbonaceous flecks	Fluvial - swamp	Siltstone, brownish black; carbonaceous laminations.		Paralic lagoonal	Siltstone, mid dark	olive grey, carbonaceous flecks	Tarina	
Inferred Lithostratigraphic Unit	(Log Interpreted Unit)	Eumeralla Formation	(Eumeralla Formation)	Eumeralla Formation	(Eumeralla Formation)	Eumeralla Formation	(Eumeralla Formation)	The state of the s	Eumeralla Formation	(Eumeralla Formation)	A TOTAL CONTRACTOR	· · · · · ·	
Palynostratigraphic Unit	Age [Index taxa]	APK321 Antian	P. notensis, P. parvispinosus, C. variabilis, F. asymmetricus F. wonthaggiensis lunaris, C. hughesii	APK32 possibly APK321	Aptian [P. notensis, P. parvispinosus, D. speciosus]	APK122 · APK3	Aptian (C. humbooii D. snorineus)		APK321	Aptian	(P. notensis, P. ingramii, P. parvispinosus, C. variabilis, C. hughesii,	Crybelosporites 'burgeri' M. evansii]	
Sample Sample number	Depth Preparation Num.	SWC 60 s6298	1035.0m P19271	SWC 59 s6297	1063.0m P19270	SWC 58	1105.0m P19269		SWC 57	s6295 1118.0m	P19268		

24/10/97 [Print: 12:17 31/10/97]

# APG Consultants Palynostratigraphic Data

# Gordon #1

File 97/20 (Report 640/05)

Laira Shale   Fluvial - lacustrine   Fair to fresh   Moderate   Low	(Laira Formation) Claystone, mid grey, silty	Laira Shale Fluvial Fair - poor Moderate Low	Eumeralla - Crayfish Group Unconformity	Age (Log Interpreted Unit) Preservation Yield Diversity (Undex taxa) (Lithology) (Org. Yield)	Palynostratigraphic Unit Inferred Lithostratigraphic Unit Inferred Lithostration Inferred L	The tentative alternative position (between 1211 & 1275m) of the unconformity reflects a possible assignment of the associations at 184m and 1211m to APP3 based on the rather uncertain assemblage criterian of Cicatricosigonites australiensis being a significant component of the associations; it is usually extremely rare in the Crayfish Sub Group. There are acceptions to this assemblage trend and acceptance of the lower (between 1211m and 1275m) position should be considered only if there were compelling lithostratigraphic or seismic evidence.  Restricted (?specialised) fern spore dominated palynoflora; mostly Cyathidifes minor, Osmundacidites prominent; Cicatricosisporites notable. Bryophyte spores notable, mostly Aequitriradites. Fragmented saccate pollen, inaperturate pollen and corroded cuticle sheets conspicuous. Few leiospheres and S. reticulatus  Restricted (?specialised) fern spore dominated palynoflora; mostly Cyathidites minor, Osmundacidites conspicuous; Cicatricosisporites notable. Saccate and inaperturate pollen scarce. Few aquatic forms; S. reticulatus and leiospheres notable. Fern pores subdominant but somewhat restricted in diversity, Osmundacidites prominent; Cyathidites conspicuous. Small leiospheres and M. evansii notable. Fern pores subdominant but somewhat restricted in diversity, Osmundacidites prominent, Cyathidites conspicuous. Small leiospheres and M. evansii notable; few S. reticulatus and Micrhystridium present.	Palynor vation Yiete (Org. Fried)  poor Moder (High Moder iir Moder (Very h	iroup Uncon stroug Uncon art.	Inferred Deposition Environme (Lithology)  Fluvial Fluvial Fluvial - lacustrine Siltstone, dark grey black, argillaceous in pe Paralic coastal pla Claystone, mid tree	Laira Shale  (Laira Formation)  (Laira Formation)  (Laira Formation)  (Laira Formation)	Sample Between 1118m and 1275m Preparation Num.  Between 1118m and 1275m probably between 1118m and 1184m) (or a much less likely alternative of between 1211m and 1275m) \$SWC 55 1184.0m \$P19239 P19239 P19239 P19239 P19239 SWC 54 P19240 P192
	Laira Shale Fluvial - lacustrine Fair to fresh Moderate Low  (Laira Formation) Siltstone, dark grey - hilack, argillaceous in part.  Laira Shale Paralic coastal plain Fair Moderate Moderate  (Laira Formation) Claystone, mid It grey;  v. fine sandstone in part	(Laira Shale       Fluvial - lacustrine       Fair to fresh       Moderate       Low         (Laira Formation)       Siltstone, dark grey - black, argillaceous in part.       Fair to fresh       (High)         Laira Shale       Paralic coastal plain       Fair       Moderate         (Laira Shale       Paralic coastal plain       Fair       Moderate         (Laira Shale       Claystone, mid tt grey;       IVery low]         v. fine sandstone in part       v. fine sandstone in part	Laira Shale Fluvial Fair - poor Moderate Low  (Laira Shale Fluvial - lacustrine Fair to fresh Moderate Low  Laira Shale Fluvial - lacustrine Fair to fresh Moderate Low  Laira Shale Paralic coastal plain Fair Moderate Moderate  (Laira Shale Paralic coastal plain Fair Moderate Woderate  (Laira Shale Paralic coastal plain Fair Moderate  (Laira Formation) Claystone, mid tt grey:  v. fine sandstone in part	Laira Shale Fluvial Fair - poor Moderate Low  Laira Shale Fluvial Fair to fresh Moderate Low  Laira Shale Fluvial - lacustrine Fair to fresh Moderate Low  Laira Shale Fluvial - lacustrine Fair to fresh Moderate Low  Laira Shale Paralic coastal plain Fair Moderate Moderate  Laira Shale Paralic coastal plain Fair Moderate Woderate  Laira Shale Paralic coastal plain Fair Moderate  Laira Shale Paralic coastal plain Fair Woderate  Laira Shale Paralic coastal plain Fair Woderate  Laira Shale Paralic coastal plain Fair Woderate	Laira Shale     Fluvial Laira Shale     Fluvial Laira Shale     Fair to fresh Moderate     Low     Low       Laira Shale     Fluvial Jacustrine     Fair to fresh Moderate     Low       Laira Shale     Fluvial Jacustrine     Fair to fresh Moderate     Low       Laira Shale     Fluvial Jacustrine     Fair to fresh Moderate     Low       Laira Shale     Fluvial Jacustrine     Fair to fresh Moderate     Moderate       Laira Shale     Paralic coastal plain     Fair Moderate     Moderate       Laira Shale     Paralic coastal plain     Fair Moderate     Moderate       Laira Shale     Paralic coastal plain     Fair Moderate     Moderate				ple gap	94m sample gap	



# Gordon #1

File 97/20 (Report 640/05)

Page 3 of 8

Sample	Palynostratigraphic Unit	Inferred Lithostratigraphic Unit	Inferred		Palynomorph		
Sample number	4		Deposition Environment				Remarks
Depth Preparation Num.	Age [Index taxa]	(Log Interpreted Unit)	(Lithology)	Preservation	Yield ( <i>Org. Yield</i> )	Diversity	
SWC 52 1369.0m s6291 P19242	APK122 - APK22 very tentatively APK21 Hauterivian - Valanginian [0. speciosus, C. hughesii, F. dailyi M. evansii]	Laira Formation (Laira formation)	Paralic coastal plain Mudstone, mid grey, arenaceous	Fair	Moderate I <i>Extremely low</i> ]	Moderate	Palynoflora dominated by spores; mostly <i>Osmundacidites</i> ; <i>Cyathidites</i> prominent; <i>C. equali</i> s and <i>L. verrucatus</i> notable; Saccate pollen remnants subdominant. Few leiospheres; few <i>M. evansii</i> ; isolated <i>S. reticulatus</i> and <i>Micrhystridium</i> present.
SWC 51 1413.0m s6290 P19243	APK12 - APK2 very tentatively APK21 Hauterivian - Valanginian IC. australiensis, C. equalis, C. hughesii	Crayfish Group (Laira Formation)	Fluvial Mudstone, dark grey, arenaceous in part.	Very poor Very low strongly corroded [Extremely low]	Very low Extremely low]	Low	Sparse palynoflora of mostly spore remnants with only the more robust forms identifiable: <i>Cyathidites, Ceratosporites equalis, Leptolepidites major</i> and <i>Retitriletes</i> conspicuous. Fragmented saccate pollen remnants conspicuous.
SWC 50 1428.0m s6289 P19244	APJ2 - APK2 [L. verucatus]	Crayfish Group (Laira Formation)	Fluvial - lacustrine Claystone, dark grey	Very poor	Very low [Extremely low]	Very low	Sparse palynoflora of mostly unidentifiable saccate pollen, cuticle and spore remnants: <i>Cyathidites, Leptolepidites verrucatus</i> and <i>Retitriletes</i> conspicuous. Small leiospheres notable
SWC 49 1482.5m s6288 P19245	APK122 - APK2 very tentatively APK211 Valanginian [D. speciosus, C. equalis, L. belfordii Concavissimisporites "sparsus"]	lower Laira Formation or upper Pretty Hill Sandstone (Laira Formation)	Fluvial Claystone, mid dark grey, arenaceous in part	Poor corroded	Moderate [Extremely low]	Moderate	Restricted palynoflora of mostly spores; <i>Cyathidites</i> and <i>Retitriletes</i> conspicuous; <i>L. belfordii, B. spectabilis, Klukisporites, Leptolepidites</i> and <i>Neoraistrickia</i> notable. Saccate pollen prominent; mostly unidentifiable remnants. Very few aquatic forms.
SWC 48 1510.0m s6287 P19246	APK122 - APK2 very tentatively APK211 Valanginian 10. speciosus, C. hughesii, M. evansii	lower Laira Formation or upper Pretty Hill Sandstone (Laira Formation)	Fluvial - lacustrine Mudstone, mid brown grey, grading to v. fine sandstone in part	Poor	Moderate [Very low]	Moderate	Palynoflora dominated by land plant spores; mostly <i>Retitriletes</i> and <i>Osmundacidites; Cyathidites; Leptolepidites</i> conspicuous. Bisaccate pollen prominent. Leiospheres and <i>M. evansii</i> notable

Gordon #1 File 97/20 (Report 640/05)

Remarks		Palynoflora dominated by land plant spore and pollen remnants. Fern spores subdominant but restricted in diversity; mostly <i>Osmundacidites spp</i> with <i>Cyathidites minor, C. equalis</i> and <i>L. verrucatus</i> notable. Lycopod spores notable but relatively diverse; mostly <i>Retitriletes spp</i> . Bryophytes very scarce. Almost no aquatic forms noted. Cuticle sheets prominent in oxidised residue.	Very low organic recovery	Palynoflora dominated by inaperturate pollen and saccate pollen. Fern spores conspicuous; mostly <i>Cyathidites</i> and <i>Osmundacidites</i> . Lycopod spores notable; mostly <i>Retitriletes</i> and <i>Kekryphalospora</i> . Bryophytes scarce. Almost no aquatic forms noted.	Palynoflora mostly unidentifiable saccate pollen, inaperturate pollen and cuticle remnants. Spores restricted in diversity; Osmundacidites prominent; Cyathidites and Retitriletes conspicuous. Few leiospheres; isolated M. evansii.	Sandy section; additional samples from this section unlikely to yield definitive palynomorph associations.
4	Diversity	Low		Low	Moderate	
Palynomorph	Yield ( <i>Org. Yield</i> )	Moderate [Low]		Moderate [[ow]	Low - Moderate [Very low]	we and action to the control of the
	Preservation	Fair		Poor corroded fragmented	Poor thin corroded	
Inferred Deposition Environment	(Lithology)	Fluvial Claystone, dark grey	Siltstone, mid dark grey	Fluvial Laminite, dark grey siltstone & v. fine off white sandstone,	Fluvial Siltstone, It - mid grey brown; v. fine sandstone in part	ple gap
Inferred Lithostratigraphic Unit	(Log Interpreted Unit)	lower Laira Formation or Pretty Hill Sandstone (Pretty Hill Sandstone)		lower Laira Formation or Pretty Hill Sandstone (Pretty Hill Sandstone)	lower Laira Formation or Pretty Hill Sandstone	147m sample gap
Palynostratigraphic Unit	Age [Index taxa]	APK122 - APK2 tentatively APK122 Valanginian - Berriasian [D. speciosus, C. hughesti, C. equalis, Converucosisporites, cf.C. exquisitus 6371	Not examined	APK1 - APK2 tentatively APK1 Valanginian - Berriasian - Tithonian IC. hughesii, C. stylosus)	APJ6 - APK2 tentatively APK12 Valanginian - Berriasian 1C. equalis, M. evansii, C. "hemisphericus"]	
Sample number	Depth Preparation Num.	SWC 47 1536.0m s6223 P19247	SWC 46 1549.0m s6222 P19248	SWC 44 1593.25m s6221 P19249	SWC 43 1614.0m s6220 P19250	Between 1614m & 1761m



# Gordon #1

File 97/20 (Report 640/05)

Page 5 of 8

Sample	Palynostratigraphic Unit	Inferred Lithostratigraphic Unit	Inferred		Dalymomorph		
Sample number		•	Deposi				Bomarlo
Depth Preparation Num.	Age [Index taxa]	(Log Interpreted Unit)	(Lithology)	Preservation	Yield ( <i>Org. Yield</i> )	Diversity	nellidi Ko
SWC 40 1761.0m	APK122 - APK2 possibly APK122	lower Laira Formation or	Paralic coastal plain	Poor	Low	Low	Palynoflora mostly unidentifiable spore, saccate pollen and cuticle remnants. Snores prominent but restricted in divarsity: Osmandariditas and Betitrilates
s6219 P19251	Valanginian - Berriasian	Pretty Hill Sandstone	Siltstone, mid·mid dark grev	thin corroded	[Very low]		conspicuous. Algal forms scarce; isolated <i>M. evansii</i> and <i>Micrhystridium</i> .
	(D. filosus cloisonne, D. speciosus, C. hughesii, C. ludbrookiae, M. evansii)	(Pretty Hill Sandstone)					
SWC 39	APJ2 - APK3 very tentatively APK1	lower Laira Formation	Lacustrine	Very poor	Very low	Very low	Sparse restricted palynoflora of mostly unidentifiable fragmented saccate
s6218 P19252	Valanginian · Berriasian · Tithonian	Pretty Hill Sandstone	Claystone, mid grey		[Extremely low]		ponen and courde remnants, opore tragments subdomnant, <i>cyamunes</i> and <i>Retitriletes</i> conspicuous, Algal forms notable; mostly leiospheres.
	[L. verrucatus, ]	(Pretty Hill Sandstone)					
SWC 38 1810.0m s6217 P19253	Not examined	(Pretty Hill Sandstone)	Mudstone, mid greenish grey, sandstone in part; calcite veins				Very low organic recovery
SWC 36	APK1 - APK2	lower Laira Formation	Paralic lagoonal	Very poor	Low	Low	Palynoflora mostly unidentifiable saccate pollen and cuticle remnants;
s6216 P19254	Valanginian - Berriasian	Pretty Hill Sandstone	Siltstone, mid - dark grey.		[Extremely low]		naperturate pollen notable. Spores fragments subdominant but restricted in diversity, <i>Osmundacidites</i> conspicuous. Leiospheres notable, few <i>Micrhystridium.</i>
sence in the second sec	L. equalis, C. nugnesri	(Fretty Hill Sandstone)	CONTRACTOR AND				
56tween 1882m & 2126m		244m sample gap	ple gap				Sandy section; additional samples from this section unlikely to yield definitive palynomorph associations.
SWC27	APK1	Casterton Formation	Fluvial	Very poor	Moderate	Very low	Palynoflora of mostly corroded and fragmented inaperturate pollen remnants
s6211 P19255	Berriasian - Tithonian	(Casterton Formation)	Siltstone, dark grey	diffuse, corroded & fragmented	[Very low]		totten uniticuit to distilligaisti from the abundant very fragmented and corroded cuticle remnants); very few forms could be identifies; few processingly consists of the control of the c
	(C. 'quasihughesii', ?C. 'backhousei') [Casterton palynofacies]						recognisatic accate pointi opotes scalce and very testricted in diversity. Few aquatic algal spores; almost entirely leiospheres.

24/10/97 [Print: 12:17 31/10/97]

# APG Consultants Palynostratigraphic Data

# Gordon #1

File 97/20 (Report 640/05)

Palynostratigraphic Unit	Inferred Lithostratigraphic Unit	Inferred Deposition Environment		Palynomorph		Colorana O
(Log.	(Log Interpreted Unit)	(Lithology)	Preservation	Yield ( <i>Org. Yield</i> )	Diversity	Reliairs
Caste (Cass	Casterton Formation (Casterton Formation)	Lacustrine Siltstone, mid dark grey brown	Pollen: very poor diffuse, corroled & tragmented Acritarchs: fair - fresh.	High [Low]	Very low	Palynoflora of mostly strongly corroded inaperturate pollen fragments (mostly difficult to distinguish from the abundant very fragmented and corroded cuticle remnants); very few forms could be identifies. Few recognisable saccate pollen. Aquatic algal spores subdominant to co dominant; almost entirely thin and moderately thick walled leiospheres.
Castert (Caster	Casterton Formation (Casterton Formation)	Fluvial Siltstone, mid grey brown; v. fine sandstone in part	Extremely poor diffus, coroded & regnented	Moderate [Low]	Very low	Spores very scarce and extremely restricted in diversity.  Palynoflora mostly strongly corroded thin ?inaperturate pollen, ?saccate pollen and cuticle fragments; few forms could br recognised. Spores extremely scarce and restricted in diversity. Isolated algal spores present.
Casterti (Castert	Casterton Formation (Casterton Formation)	Lacustrine Siltstone, light mid brownish grey, off white sandstone laminations	Pollen: extrm. poor diffus, crotad & fragmented Algae; fair	Moderate [Moderate]	Very low	Palynoflora mostly strongly corroded thin inaperturate pollen remnants together with cuticle fragments; very few forms could br identifies; few recognisable saccate pollen. Spores very scarce and restricted in diversity. Algal spores conspicuous; mostly thin walled and small leiospheres.
Casterto ( <i>Castert</i> o	Casterton Formation (Casterton Formation)	Fluvial Siltstone, mid brown; fine sandstone in part.	Extremely poor diffuse, corroded & fragmented	Moderate [	extremely low	Extremely low Palynoflora mostly strongly corroded thin ?inaperturate pollen remnants and cuticle fragments; very few forms could br identifies; few recognisable saccate pollen. Spores extremely scarce and restricted in diversity. Few algal spores (mostly leiospheres) present.
Casterton (Casterton	Casterton Formation (Casterton Formation)	Fluvial Siltstone, dark brown black, claystone in part	Very poor diffuse, corroled & fregmented	High [Moderate]	Low	Palynoflora dominated by corroded inaperturate pollen remnants and cuticle fragments; few recognisable saccate pollen. Spores sparse and restricted in diversity; Osmundacidites and Ceratosporites equalis notable; Contignisporites cooksoniae represented by several specimens. Algal spores very rare; mostly leiospheres.



Gordon #1

File 97/20 (Report 640/05)

Page 7 of 8 24/10/97 [Print: 12:17 31/10/97]

Sample	Palynostratigraphic Unit	Inferred Lithostratigraphic Unit	Inferred Denosition Environment		Palynomorph	1	
Depth	Age	(Log Interpreted Unit)	10.15.15	Preservation	Yield	Diversity	Remarks
rreparation Num.	Invest vanid		(Filmonoly)		(Org. Yield)		
SWC 17	APJ62 - APK2	Casterton Formation	Fluvial	Very poor	Moderate	Very low	Palynoflora dominated by thin corroded inaperturate pollen remnants and
2270.Um s6189	very tentatively APK I I	(Casterton Formation)	Siltstone, dark brown	unuse, corroged & fragmented	[Moderate]		cuticle fragments; few recognisable saccate pollen; pollen and cuticle ronnants often difficult to distinguish. Spores you enarse and restricted in
P19261	Berriasian · Tithonian		black, claystone in part				diversity, Osmundacidites and Cyathidites notable. Algal spores extremely
	[C. equalis, C. glebulentus] [Casterton palynofacies]	·					rare; mostly leiospheres.
SWC 16	APK1	Casterton Formation	Fluvial	Very poor	Low	Very low	Sparse palvnoflora of mostly unidentifiable remnants. Land plant spores
2295.5m	tentatively APK11			:			dominant; Lycopods (mostly Retitriletes and Kekryphalospora) prominent and
s6188 P19262	Berriasian - Tithonian	(Casterton Formation)	Siltstone, mid dark brown	corroded Tragmented	[wo7]		moderately diverse. Few recognisable inaperturate or saccate pollen. Few possible algal spores.
	C. equalis, Cicatricosisporites purbeckensis   Sand palynofacies						
SWC 15	APK1	Casterton Formation	Fluvial	Very poor	Moderate	Very low	Palynoflora dominated by thin strongly corroded ?inaperturate pollen
2325.0m	tentatively APK11		;	diffuse, stained corroded &			remnants and cuticle fragments; few recognisable saccate pollen; pollen and
s6187 P19263	Berriasian - Tithonian	(Casterton Formation)	Siltstone, mid dark brown, carbonaceous	fragmented	[Moderate]		cuticle remnants often difficult to distinguish. Spores very sparse and restricted in diversity, <i>Retitriletes</i> and <i>Kekryphalospora</i> notable. Algal spores
	[ <i>C. australiensis, C. equalis</i> ] [Casterton palynofacies						extremely rare; mostly leiospheres.
SWC 14	APJ62 - APK1	Casterton Formation	Lacustrine	Ext poor	Very high	xtremely low	Extremely low Palynoflora consists almost entirely of thin strongly corroded inaperturate
2337.5m	tentatively APK11	(Casterion Formation)	Citotopo	diffuse, stained corroded &		•	pollen, thin ?leiospheres and cuticle tissue fragments; few forms could be
P19264	Berriasian · Tithonian · Kimmeridgian		brown, carbonaceous	noninelikeri	lugui Kisal		identified. Some numic staining but less than the section 2295 - 2325m. Land plant spores extremely scarce.
	(C. equalis)						

24/10/97 [Print: 12:17 31/10/97]

# APG Consultants Palynostratigraphic Data

Gordon #1

File 97/20 (Report 640/05)

		<u> </u>		
Bemarks		Palynoflora dominated by somewhat corroded but mostly entire inaperturate pollen; bisaccate pollen notable. Cuticle tissue highly corroded, diffuse and finely divided; less humic staining than at 2295 · 2337.5m. Land plant spores extremely scarce and restricted in diversity. Algal spores prominent; mostly thin walled and small leiospheres including <i>Granodiscus minutia</i> .  [Palynoflora seem similar to the section from 2105m · 2270m but haperturate pollen better preserved, spore association differs in that <i>C. equalis</i> absent but doubt that it is significantly older. Very few forms free of the granular-fibrous matrix in unoxidized + 20µm fraction]	Fern spores dominate but restricted in diversity; mostly <i>Osmundacidites</i> ; <i>Klukisporites</i> notable. Inaperturate pollen remnants conspicuous. Few bisaccate pollen. Lycopod spores scarce; <i>Dictyotosporites</i> notable. Isolated algal spores. [Palynomorphs thin with humic staining; <i>cf</i> assemblage above. Few palynomorphs free of humic matrix in +20,rm unoxidized fraction]	
ų.	Diversity	Very low	Low	
Palynomorph	Yield ( <i>Org. Yield</i> )	Very high [Very high]	Moderate [Very high]	
	Preservation	Pollen: fair - poor Spores: very poor Algae; fair - fresh	Poor	
Inferred Deposition Environment	(Lithology)	Lacustrine Siltstone, dark brownish grey, carbonaceous	Peat Bog Coal, black sub vitreous	
Inferred Lithostratigraphic Unit	(Log Interpreted Unit)	Casterton Formation (Casterton Formation)	Casterton Formation (Casterton Formation)	
Palynostratigraphic Unit	Age [Index taxa]	APJ6 - APK1 tentatively APK11 Berriasian - Tithonian [7C. purbeckensis, 7R. watherooensis] [Casterton oil shale aquatic palynofacies]	APJ62 - APK1 very tentatively APK11 Berriasian - Tithonian - Kimmeridgian [C. equalis] [Casterton Coal palynofacies]	
Sample number	Depth Preparation Num.	SWC 12 2350.0m s6185 P19265	SWC 11 2356.25m s6184 P19266	

# Appendix 2

Species Distribution Lists

Gordon #1

# PE905777

This is an enclosure indicator page. The enclosure PE905777 is enclosed within the container PE905781 at this location in this document.

The enclosure PE905777 has the following characteristics:

ITEM\_BARCODE = PE905777 CONTAINER\_BARCODE = PE905781

NAME = Spore/Pollen Distribution Chart showing

Species Check List

BASIN = OTWAY BASIN

PERMIT = PEP/119

TYPE = WELL

SUBTYPE = DIAGRAM

DESCRIPTION = Pollen Distribution Chart showing Species Check List (from WCR) for

Gordon-1

REMARKS =

DATE\_CREATED =

DATE\_RECEIVED =

 $W_NO = W1191$ 

WELL\_NAME = GORDON-1

CONTRACTOR =

CLIENT\_OP\_CO =

(Inserted by DNRE - Vic Govt Mines Dept)

### PE905774

This is an enclosure indicator page.

The enclosure PE905774 is enclosed within the container PE905781 at this location in this document.

The enclosure PE905774 has the following characteristics:

ITEM\_BARCODE = PE905774
CONTAINER\_BARCODE = PE905781

NAME = Spore/Pollen Distribution Chart showing

Oldest Occurence Species List

BASIN = OTWAY BASIN

PERMIT = PEP/119

TYPE = WELL

SUBTYPE = DIAGRAM

DESCRIPTION = Pollen Distribution Chart showing

Oldest Occurence Species List (from

WCR) for Gordon-1

REMARKS =

DATE\_CREATED =

DATE\_RECEIVED =

 $W_NO = W1191$ 

WELL\_NAME = GORDON-1

CONTRACTOR =

CLIENT\_OP\_CO =

(Inserted by DNRE - Vic Govt Mines Dept)

Appendix 3

Group Diversity Charts

Gordon #1

# PE905775

This is an enclosure indicator page. The enclosure PE905775 is enclosed within the container PE905781 at this location in this document.

ITEM\_BARCODE = PE905775 CONTAINER\_BARCODE = PE905781 NAME = Spore/Pollen Distribution Chart showing Morpho-Group Diversity BASIN = OTWAY BASIN

The enclosure PE905775 has the following characteristics:

PERMIT = PEP/119TYPE = WELL SUBTYPE = DIAGRAM

DESCRIPTION = Pollen Distribution Chart showing Morpho-Group Diversity (from WCR) for Gordon-1

REMARKS = DATE\_CREATED = DATE\_RECEIVED =

> $W_NO = W1191$ WELL\_NAME = GORDON-1

CONTRACTOR = CLIENT\_OP\_CO =

(Inserted by DNRE - Vic Govt Mines Dept)

### PE905776

This is an enclosure indicator page. The enclosure PE905776 is enclosed within the container PE905781 at this location in this document.

```
The enclosure PE905776 has the following characteristics:
```

ITEM\_BARCODE = PE905776
CONTAINER\_BARCODE = PE905781

NAME = Spore/Pollen Distribution Chart showing

Phylo-Group Diversity

BASIN = OTWAY BASIN

PERMIT = PEP/119

TYPE = WELL

SUBTYPE = DIAGRAM

DESCRIPTION = Pollen Distribution Chart showing

Phylo-Group Diversity (from WCR) for

Gordon-1

REMARKS =

DATE\_CREATED =

DATE\_RECEIVED =

 $W_NO = W1191$ 

WELL\_NAME = GORDON-1

CONTRACTOR =

CLIENT\_OP\_CO =

(Inserted by DNRE - Vic Govt Mines Dept)


# **APPENDIX VIII: GEOTHERMAL GRADIENT**


Information for the geothermal gradient may be taken from the following data:-

97 °C at 2499m after 8.2 hours from Run 1, Suite 1, with the SP, GR, Resisivity, Sonic etc.

99 °C at 2485m after 16.3 hours from Run 2, Suite 1, with the sidewall cores.

96 °C at 2498m after 6.5 hours, from Run 3, with the FMI log, following last wiper trip.





**APPENDIX IX: WELL LOCATION SURVEY** 

Santos Ltd A.C.N. 007 550 923 39 Grenfell Street Adelaide SA 5000 GPO Box 2319 Adelaide SA 5001

Santos

Telephone: (08) 218 5111 **Geology Operations** Facsimile: (08) 224 7962 Telephone: (08) 224 7957

# **Facsimile**

To:

Cultus

Attn: Mr. V. Dauzacker

CC:

Department of Natural Resources

Environment - Petroleum Branch

& Attn: Mr. K. Mehin

From:

A.P. Pietsch

Date:

15th April, 1997

Subject: Gordon 1

No of pages:

(incl. this one)

1

(IF INCOMPLETE TRANSMISSION RECEIVED PLEASE PHONE: (08) 224 7967)

Ground Elevation and Co-ordinates after lease preparation are as follows:

Ground Level:

124.89m

141° 17' 38.4" E

Rotary Table:

129.59m

37° 14.5" S 35'

Please amend your records accordingly.

A.P. PIETSCH

CHIEF OPERATIONS GEOLOGIST

APP:ap

cc:

A. McGee

Ops Geologist Wellsite Geologist Peter Davidson

	APPENDIX	X: DRILLING, CAS	SING, AND ABAND	ONMENT SUMMARY
Note		e forwarded when it be		
Note				
	This appendix will b	e forwarded when it be		
	: This appendix will b	e forwarded when it be		
	This appendix will b	e forwarded when it be		

**APPENDIX XI: RIG SPECIFICATIONS** 

## **ODE RIG #30 SPECIFICATIONS**

# **CONTRACTOR'S EQUIPMENT**

ONTRACTOR'S RIG

: Rig #30 - rated to 11,000 ft. with 4.1/2," drill pipe

**DRAWWORKS** 

Ideco H725 Hydrair, driven by EMD D79 electric motor. Maximum input 900 hp Parmac V-80 Hydromatic brake.

Transmission - 3 speed transmission with Fawick 40CB525 air clutch.

**ENGINES** 

Four (4) Caterpillar Model 3412 PCTA diesel engines.

**SUBSTRUCTURE** 

One piece substructure 14' high x 13'6" wide x 50' long with 12' BOP

clearance.

Setback area loading:250,000 lbs Casing area loading:275,000 lbs

**MAST** 

Dreco Model #: M12713-510 Floor Mounted Cantilever Mast designed in accordance with API Specification 4E Drilling & Well Servicing

Structures.

Hook load Gross Nominal Capacity - 510,000 lbs with:-

10 lines strung-365,000 lbs 8 lines strung-340,000 Lbs Clew working height of 127'

Base width of 13'6".

Adjustable racking board with capacity for:-

i) 108 stands of 4.1/2" drill pipe,

ii) 10 stands of 6.1/2" drill collars,

iii) 3 stands of 8" drill collars

Designed to withstand an API windload of 84 mph with pipe racked and

100 mph with no pipe racked.

**CATHEADS** 

One (1) Foster Model 37 make-up spinning cathead mounted on drillers

side.

One (1) Foster Model 24 break-out cathead mounted off drillers side.

**CROWN BLOCK** 

215 ton with five (5) 36" sheaves and one (1) 36" fastline sheave grooved

1.1/8".

TRAVELLING BLOCK

One (1) 667 Crosby McKissick 250 ton combination block hook Web

Wilson. 250 ton Hydra hook Unit 5 - 36" sheaves.

**SWIVEL** 

One (1) Oilwell PC-300 ton swivel.

192 tons API bearing rating at 100 rpm.

**RIG LIGHTING** 

Explosive proof fluorescent. As per approved State Specifications.

**MUD PUMPS** 

Two (2) Gardner Denver mud pumps Model PZ-8 each driven by 800 HP

EMD motors. 8" stroke with liner size 6".

**MIXING PUMPS** 

Five (5) Mission Magnum 5" x 6" x 14" centrifugal pumps complete with

50 HP, 600 Volt, 60 Hz, 3 phase explosion proof electric motors.

**MUD AGITATORS** 

Six (6) Geolograph/Pioneer 40TD - 15" 'Pitbull' mud agitators with 15

HP, 60 Volt, 60 HZ, 3 phase electric motors.

**SHALESHAKER** 

Two (2) DFE SCR-01 Linear motion shale shakers.

Adjustable screen deck -  $1^{\circ}$  to +  $5^{\circ}$ .

DEGASSER

One (1) Drilco See-Flo.

DESILTER

One (1) Pioneer T12-4 'Siltmaster' desilter.

12 x 4" cones. Approximate output of 2,250 litres per minute.

**DESANDER** 

Harrisburg DSN-1000 unit with 2 x 10" cones. Approximate output of

3,600 litres per minute.

**GENERATORS** 

Four (4) Brown Boveri 600 Volt, 600 kw 3 phase, 60 HZ AC generators.

Powered by four (4) Cat 3412 PCTA diesel engines.

B.O.P.'s

One (1) Hydril 13.5/8" x 3,000 psi spherical annular BOP, studded to

and flanged bottom.

One (1) Hydril 13.5/8" x 5,000 psi flanged double gate BOP.

**SPOOLS** 

Double studded adaptor, 4.1/2" H 13.5/8" 5000 BXI60 x 13.518" 3000

RX57.

Double studded adaptor, 4.1/2" H 13.5/8" 5000 BXI60 x 7.1/16" 5000

Double studded adaptor, 5.1/2" H 13.5/8" 5000 BXI60 x 7.1/16" 3000

R45.

BOP spacer spool (drilling spool), 17" H 13.5/8" 5000 BXI60 x 13.5/8"

5000 BXI60.

BOP spacer spool (drilling spool), 14.1/2," H 13.5/8" 3000 R57 x 13.5/8"

3000 R57.

BOP adaptor spool, 18" H 13.5/8" 5000 BXI60 x 11" 3000 R53.

**ACCUMULATOR** 

One (1) Wagner Model 130-160 3 BND 160 gallon accumulator

consisting of:-

• Sixteen (16) 11 gallon bladder type bottles.

• One (1) 20 HP electric driven triplex pump 600 volts, 60 HZ, 3 phase

motor and controls.

• One (1) Wagner Model A - 60 auxiliary air pump 4.5 gals/minute.

- One (1) Wagner Model UM2SCB5S mounted hydraulic control panel with five (5) 1" stainless steel fitted selector valves and two (2) stripping controls and pressure reducing valves.
- Three (3) 4" hydraulic readout gauges:
  - one for annular pressure
  - one for accumulator pressure
  - one for manifold pressure

One (1) Wagner Model GMSB - 5A 5 station remote drillers control with three pressure gauges, increase and decrease control for annular pressure.

**DRILL PIPE SAFETY** 

**VALVE** 

One (1) 4" IF inside BOP. One (1) 4" IF Stabbing Valve.

AIR COMPRESSORS &

RECEIVERS

Two (2) LeRoi Dresser Model 660A air compressor packages c/w 10 HP motors rated at 600 Volts, 60 HZ, 3 phase. Receivers each 120 gallon capacity and fitted with relief valves.

AIR WINCH

One (1) Ingersol Rand HU-40 with 5/8" wireline. Capacity 2,000 lb.

**POWER TONGS** 

One (1) Farr 13.5/8" - 5.1/2" hydraulic casing tongs c/w hydraulic power pack and hoses and torque gauge assembly.

One (1) Farr Model LW5500 5.1/2" high torque hydraulic power tong

complete w/- 3.1/2" rotating assembly.

One (1) Foster hydraulic kelly spinner with 6.5/8" LH connections.

One (1) Varco SSW-30 hydraulic spinning wench. Self adjusting 2.7/8"

through to 7" OD pipe.

**ROTARY TABLE** 

One (1) Ideco 23" rotary table shaft driven from drawworks.

MUD TANKS (SHAKER)

One (1) Shaker tank total 236 bbls

• trip tank - 24 bbls

• sand trap - 92 bbls

• settling tank - 120 bbls

(INTERMEDIATE)

One (1) Intermediate tank total 337 bbls.

• with desilter tank - 113bbls

• with desander tank - 112bbls

• with reserve tank - 112bbls

(SUCTION)

One (1) Suction tank total 222 bbls.

• with pill tank - 23 bbls

• with two (2) suction tanks - 100 bbls each

Total system: 795 bbls

TRIP TANK PUMP : One (1) Mission Magnum

One (1) Mission Magnum 2" x 3" centrifugal pump complete with 20

HP, 600 Volts, 60 HZ, 3 phase explosion proof motors.

**CHOKE MANIFOLD** : One (1) Choke manifold, complete with Cameron type 'FL' 3" 5000 psi

valves and Hydraulic Swaco "super" choke.

**DRILL PIPE** : 2,280m - 4.1/2" OD 16.60 lb/ft Grade "G" drill pipe.

465m - 4.1/2" OD 16.60 lb/ft Grade "E" drill pipe. 2,500m - 3.1/2" OD 13.30 lb/ft Grade "G" drill pipe.

**PUP JOINTS** : One (1) - 5' 4.1/2" OD Grade 'G'.

One (1) - 5' 3.1/2" OD Grade 'G'. One (1) - 10' 4.1/2" OD Grade 'G'. One (1) - 10' 3.1/2" OD Grade 'G'. One (1) - 15' 4.1/2" OD Grade 'G'.

**HEVI-WATE DRILL PIPE** : 142m (15 jts) of 4.1/2" H.W.D.P.

142m (15 jts) of 3.1/2" H.W.D.P.

DRILL COLLARS : 60m - 8" OD drill collars

230m - 6.1/4" OD drill collars 285m - 4.3/4" OD drill collars

KELLY : One (1) Square Kelly drive 4.1/4" x 40' complete with Scabbard - 4" Y

pin connection.

One (1) Hex Kelly drive 3.1/2" x 40' complete with Scabbard. 3.1/2" IF

pin connection.

**KELLY DRIVE** : One (1) 20 HDP Varco kelly drive bushing to suit 4.1/4" square kelly and

changeable rollers to suit 3.1/2" Hex Kelly.

**KELLY COCK (UPPER)** : One (1) Griffith Upper Kelly Cock 7.3/4" with 6.5/8" API connections.

**KELLY COCK (LOWER)** : One (1) Griffith Lower Kelly Cock 6.1/2" OD with 4" IF

connections.

One (1) Griffith Lower Kelly Cock 4.3/4" OD with 3.1/2," IF

connections.

FISHING TOOLS : One (1) only 10.5/8" Bowen series 150 FS overshot c/w grapples md

packoffs to fish Contractors downhole equipment.

One (1) only 8.1/8" Bowen series 150 FS overshot c/w grapples and

packoffs to fish Contractors downhole equipment.

One (1) only 5.3/4" Bowen series 150 FS overshot c/w grapples &

packoffs to fish Contractors downhole equipment. One (1) only 8" OD fishing magnet 4.1/2" reg pin. One (1) only Reverse circulating junk basket 4" IF box.

One (1) only Fishing Jar 6.1/2" OD 4" IF pin & box.

One (1) only Fishing Jar 4.3/4" OD 3.1/2" IF pin & box.

One (1) only 12" Junk Mill - 6.5/8" reg pin.

One (1) only 8" Junk Mill - 4.Y2" reg pin

# SUBSTITUTES

Two (2) Bit Subs - 6.5/8" reg double box.

Two (2) Bit Subs - 4.1/2" reg x 4" IF double box.

Two (2) Bit Subs - 3.1/2" reg x 3.1/2" IF double box.

One (1) XO Sub - 7.5/8" reg x 6.5/8" reg double box.

One (1) XO Sub - 4" IF box x 4.1/2" IF pin.

One (1) XO Sub - 3.1/2" IF box x 4" IF pin.

Two (2) XO Sub - 6.5/8" reg pin x 4" IF box.

One (1) Junk Sub - 6.5/8" reg pin x 6.5/8" reg box.

Two (2) Kelly Saver Subs 4" IF pin & box.

One (1) Kelly Saver Subs 3.1/2" IF pin & box.

Two (2) Circulating Subs - 4" IF x 2" 1502 hammer union.

One (1) 6.5/8" reg. x 4.1/2" IF double box.

One (1) 4" IF Box x 4" FH pin.

Two (2) 4" IF Box x 4.1/2" IF pin.

Two (2) 4" IF x 4.1/2" IF double box

Two (2) 4.1/2" IF Box x 4" IF pin.

One (1) 3.1/2" IF Pin x 4.1/2" IF box.

One (1) 2.7/8" Pin x 2.3/8" IF pin.

One (1) 3.1/2" IF x 2.7/8" IF pin.

# **MANDLING TOOLS**

1 only 13.3/8" Baash Ross 150 ton side door elevator.

1 only 13.3/8" single joint P.U. elevators.

1 only 9.5/8" Webb Wilson 150 ton side door elevators.

1 only 9.5/8 single joint P.U. elevator.

1 only 7" BJ 200 ton side door elevators.

1 only 7" single joint P.U. elevators.

1 only 5./2" BJ 200 ton side door elevator

1 only 3.1/2" BJ 150 ton 18 degree taper D/P elevators.

2. only 4.1/2" BJ 250 ton 18 degree taper D/P elevators.

1 only 3.1/2" 100 ton tubing elevator.

1 only 2.7/8" 100 ton tubing elevator.

1 only 2.3/8" - 3.1/2" YT slip type tubing elevator.

1 only 8" Webb Wilson 150 ton single door elevator D/C.

1 only 6.1/2" Webb Wilson 150 ton single door elevator D/C.

1 only 13.3/8" Varco CMS-XL casing slips.

1 only 9.5/8" Varco CMS-XL casing slips.

1 only 7" Varco CMS-XL casing slips.

1 only 5.1/2" Varco SDXL casing slips.

2. only 4.1/2" Varco SDXL D/P slips.

1 only 3.1/2" Varco SDML tubing slips.

1. only 2.7/8" Varco SDML tubing slips.

2. only 8" - 6.1/2" DCS-R drill collar slips.

2. only 3.1/2" Varco type SDML DP slips.

2. only 4.3/4" DCS drill collar slips.

**ROTARY TONG** : One set Web Wilson type 'AAX' c/w latch & lug jaws 13.3/8" - 3.1/2".

BIT BREAKERS : One (1) each 17.1/2", 12.1/4", 8.1/2", 6".

**FUEL TANK** : 1 only 25,000 litres.

1 only 30,000 litres.

**WATERTANK** : 1 only 400 bbls.

**DRILLING RATE** 

**RECORDER** : 1 only 6 pen drill sentry recorder to record:

• weight (D)

• penetration (feet)

• pump pressure (0-6,000 psi)

electric rotary torque

• rotary speed (rpm)

• pump spm (with selector switch)

**DEVIATION INSTRUMENT**: 1 set Totco 'Double Shot' deviation instrument 0°-8°.

INSTRUMENTS &

INDICATORS : 1 only Martin Deck Type 'D' weight gauge.

1 only National Type 'D 'dead man anchor.

• Electric rotary torque gauge

• Pit scan

• SPM gauge (2 per console)

• Rotary rpm gauge

**MUD TESTING** : 1 set Baroid mud testing laboratory (standard kit).

**RATHOLE DRILLER** : One (1) fabricated rotary table chain driven.

WATER PUMPS : Three (3) Mission Magnum 2" x 3" centrifugal pumps c/w 20

HP, 600 Volts, 60 HZ, 3 phase explosion proof motors.

CUP TESTER : One (1) Grey Cup Tester c/w test cups for 9.5/8" & 133/8".

**DRILLING LINE** : 5,000' 1.1/8" - E.I.P.S.

# TRANSPORT EQUIPMENT AND MOTOR VEHICLES

International 530 Forklift

1 Tray Top Utility - 4WD 1 Crew Wagon - 8 perso

# **CAMP EQUIPMENT**

- 4 8 Man Bunkhouses
- 1 Recreation/Canteen unit
- 1 Ablution/Laundry/Freezer unit
- 1 Kitchen/Cooler/Diner unit
- 2 Toolpusher units
- 1 Combined Water/Fuel Tank unit
- 2 CAT 3304PC generator sets each 106 Kva, 86 KW, 50 HZ.

Note: At Contractor's discretion any of the foregoing items may be replaced by equipment of equivalent or greater capacity.

EXPWXS: S:\GEOLOGY\REPORTS\WCR\R-WCR301.DOC Page 36 of 62

## **SAFETY EQUIPMENT**

# General Safety Equipment to be provided By the drilling

Contractor

Wet weather gear

Safety glasses

Safety hats

Safety footwear

Safety belts c/wlines

Ear protection -grade 4

Leather gloves

Rubber gloves

Rubber aprons

Fullface visors

Eye shields (for grinding machines, etc)

Dust masks

Rubber gloves - elbow length for chemical handling

"No-Smoking" signs

"Hard-Hat" signs

**Eye Wash Stations** 

Quantity

Make/model

Located at

**Derrick Safety Equipment** 

Derrick escape (Geronimo)

Derrick safety belts

**Derrick Climbing Assist** 

Make

Fire Extinguishers

Make

Type:

1. Dry Chemical

2. Other

First Aid Equipment

First Aid Kits
Ouantity

T 1 CC

Located at office

**Bum Kits/Fire Blankets** 

Quantity

Located at office

**Stretchers** 

Quantity

Type

Located at

Sufficient personal protective equipment will be available at all times. All equipment will

comply with International

standards.

Pictographic signs will be displayed in prominent

locations around the Rig giving wanting to a specific hazard.

3

1 x Enware eye wash

Deluge shower.

2 x Protector eye wash station

Intermediate tank

Dog House Mud Hopper

Geronimo

Lewis Type SC

R.T.C.

Quell or equivalent

10 x 9kg

2 x 11.5 BCF

2

Dog House, Toolpushers Office

2 - H2O GEL blanket

Toolpushers office (1), Dog House (1)

2

1 MSA Stokes

1 MSA Stokes Fold canvas

Dog House/Offices

**APPENDIX XII: FMI INTERPRETATION** 

# GORDON-1 FMI\* IMAGE INTERPRETATION NOVEMBER 1997

# **Summary**

An interpretation was made on scaled FMI\* images recorded in Gordon-1 from within the Casterton Formation and 'Basement Unit'. The Casterton Formation has a structural dip of 8° to the ENE with common drilling induced fracture and borehole breakout striking NW-SE and NE-SW respectively. The 'Basement Unit' contained numerous natural open and healed continuous and discontinuous fractures. Detailed interpretation focused on natural open fractures which were classified into the following classes: 'Vertical' fractures (70°-90°), 'High' angle (70°-20°) or low angle (0°-20°).

The High angle fractures were the most numerous fracture set identified and had a polymodal distribution with a dominant N-S trend. Hydrocarbon shows from the mudlog show an approximate correlation to increases in high angle fracture density such as seen at 2398m-2408m, 2421-2429m and 2449-2460m. Vertical fractures were rare and irregularly spaced with a dominant NE-SW strike orientation. Resistive fractures were rare and have a N-S strike orientations, similar to the orientation of the High Angle fractures.

A number of open natural fractures with dip magnitudes lower than 20° were observed with a polymodal strike distribution. The genesis of these fractures is not known.

Mean drilling induced fracture and borehole breakout orientation was 144°-324° and 052°-232°. This implies a maximum horizontal stress orientation of NW-SE (144°-324° and a minimum horizontal stress orientation of NE-SW (052°-232°).

## Introduction

An FMI\* (FBST-B) log was acquired in Gordon-1 (28/4/1997) from 2501.5m-2270m in 8.5" hole (78% borehole coverage). This interval covered the 'Basement Unit' and Casterton Formation. An interpretation was made by S.Horan (Schlumberger) and Siew Looi at the Santos DCC in Adelaide. The aim of the interpretation was to determine the fracture attributes from the 'Basement Unit'.

FMI images were calibrated to the PEX\* shallow resistivity measurement recorded in the same logging suite as the FMI\*. The resultant scaled FMI images were then interpreted on Borview, the image log interpretation package on Schlumberger's GeoFrame Software System.

A data quality check was made on the data prior to interpretation and is discussed in a separate report 'Borehole Electrical Image Log Quality Check - Gordon-1 FMI\*, November 1997'. A main log pass was made first from 2500m-2270m followed by a

repeat section from 2493m-2377m. During the main pass from 2498m-2443m the calipers did not open more than 8" which did not agree with the caliper from the PEX\*. However the caliper data from the repeat section agrees with the PEX\* caliper and is considered to be valid. Interpretation then focused on the repeat section and on the upper section of the main log from 2377-2270m considered to have a valid caliper..

Formation tops were provided by Graham Parsons and refer to meters beneath the drill floor.

# **Interpretation Methodology**

## **Image Calibration**

Electrical dipmeter (e.g. SHDT\*) and imaging tools (e.g. FMS\* & FMI\*) record the conductance of a formation from a number of microresistivity button electrodes. In order to achieve resolutions of 0.2"-0.3" required for detailed stratigraphic analysis these buttons have had to be designed so that they are un-calibrated and un-focused. This is in contrast to resistivity tools such as the Dual Laterlog Tool\* (DLT) which is designed to record a focused and calibrated resistivity measurement but has a vertical resolution of only 32".

In order to measure fracture attributes such as fracture aperture and porosity FMI\* data has to be scaled to give a measurement "resembling" the formation conductivity as measured by a true resistivity tool. This is done by cross-plotting FMI\* conductivity data against a shallow resistivity device such as the LLS and checking for a correlation between the two data sets. It has been found that in relatively thick and homogeneous beds the button focusing is unimportant and FMI\* data can be calibrated to read true formation conductivity.

The final processing step in image calibration is entering temperature corrected mud resistivity. Open fractures are assumed to filled with mud and hence the boundaries of each open fracture is defined by the mud resistivity.

## Fracture and Dip Classification

Formation Micro-Imager images were interpreted with fracture and bedding features classified into the following classes:

Bed Boundaries:

bedding planes from claystones and siltstones which

provide a good estimate of structural dip,

Drilling Induced Fractures:

Induced hydraulic fractures due to tensile failure of the borehole wall. Drilling induced fractures appear as vertical to sub-vertical open fractures that don't cross the borehole. They form parallel to the maximum horizontal stress and perpendicular to the minimum horizontal stress (breakout orientation).

Borehole Breakout: abrupt ovalization of the borehole due to the presence of

> anisotrophic stress fields surrounding the borehole. If the difference between these two horizontal stresses reaches a certain threshold the area around the well bore will undergo compressive shear failure orientated parallel to the minimum horizontal stress (Bell 1990). This resulting in spalling and caving of the borehole wall and the formation of breakouts.

Low angle Fracture:

open natural fractures with dip magnitudes less than 20°.

HACC Fractures:

open high angle natural fractures that dip between 20° and 70°.

VCC Fractures:

open vertical natural fractures that dip at greater than 70°.

Resistive Fractures: Healed natural fractures.

#### **Fracture Attributes**

The following fracture attribute curves were computed after interpretation of scaled images:

FVDC Corrected Fracture Density in number of fractures per meter of borehole. A correction is applied for orientational bias (i.e. angle between planar fracture and borehole axis) of:  $1 / ((\cos(\text{Dip}^{\circ})) + \text{Borehole Size}^{\circ}) \times ((\sin(\text{Dip}^{\circ})))$ .

FCNB Cumulative number of fractures in the uphole direction.

**PVPA** Apparent Electrical Fracture Porosity in porosity units. This is calculated as ratio of two areas: the area of fracture seen on the borehole wall, and the borehole wall.

HA Hydraulic aperture is the square root of the sum of aperture length multiplied by the cube width of the aperture, all divided by the sum off the aperture length. Hydraulic aperture has been shown to be proportional to flow rate of fluids throw smooth walled fractures (Brown 1987; Jones et al 1988).

## Results

Enclosures 1 and 2 show 1:20 scaled images interpretation from the repeat log (2493m-2377m) and for the main log (2498m-2270m). Enclosures 3 and 4 show corrected fracture density (FVDC), apparent electrical fracture porosity (PVPA) and cumulative number of fractures for the HACC (red curves) and VCC (green curves).

Interpretation of the FMI images was initially undertaken in the Casterton Formation to determine structural dip, borehole breakout and drilling induced fracture orientation in an interval with relatively few fractures. Borehole breakout and drilling induced fractures were clearly identified and strike NE-SW and NW-SE respectively (Enclosure 2). Claystones were finely bedded on a 10s cm scale and dipped to the E (071°) at 8° (Fig. G1-2).

Figure G1-1 shows the borehole breakout and drilling induced fractures strike orientation for the Casterton Formation and Basement 'Unit' which strike 052°-232° and 144°-324° respectively.

### **Basement Fracture Attributes.**

Continuous fractures were classified as per the scheme outlined above. Strike orientations for HACC, VCC, low angle natural fractures and resistive fractures is shown in Figures G1-3, -4, -5, -6.. HACC fractures were the most common (n=266) which had a dominant N-S orientation (Fig G1-3) which is similar in orientation to resistive fractures (Fig G1-5). VCC fractures have a dominant NE-SW trend with a minor NNE-SSW trend also (Fig. G1-4).

Low angle natural open fracture show a polymodal strike distribution (Fig G1-6). These fractures are problematical as they are interpreted as open fractures based on there resistivity image however with dip magnitudes less than 20° it is difficult to imagine them staying open at there present depth without a significant horizontal compressive stress being applied

Tables 1 and 2 below list a summary of some of the fracture attributes calculated for the HACC and VCC fractures. Vertical fractures were not common and were irregularly spaced so a mean fracture porosity was not calculated. Fracture porosity is shown on Enclosure 4 but should be interpreted with caution given the small amount and irregular spacing.

<b>High Angle Fractures (HACC)</b>	n = 266
Minimum-Maximum Depth	2378m-2492m
Mean Hydraulic Aperture	0.001377 cm
Mean Dip Spacing	0.43 m
Mean Trace Length	22.28cm
Minimum-Maximum	$0-0.000181 \text{ m}^3/\text{m}^3$
Fracture Porosity	
Mean Fracture Porosity	$0.0000144 \text{ m}^3/\text{m}^3$

Table 1. Summary of HACC fracture attributes.

Vertical Fractures (VCC)	$\mathbf{n} = 20$
Minimum-Maximum Depth	2393m-2477m
Mean Hydraulic Aperture	0.000657 cm
Mean Dip Spacing	4.35 m
Mean Trace Length	49.13 cm

Table 2. Summary of VCC fracture attributes.

Hydrocarbon shows from the mudlog show an approximate correlation to the High angle fracture density. For instance fracture densities of 10 or more per meter were seen from 2398m-2408m, 2421-2429m and 2449-2460m which equate to increases in ditch cuttings and presence of fluorescence.

Numerous open and healed discontinuous fractures were observed (Enclosure 1 & 2) but no attempt was made to determine there orientation due to the large numbers

Simon Horan Division Geologist Schlumberger Wireline & Testing

\* Mark of Schlumberger

## References.

- Bell, J.S. . 1990. Investigating stress regimes in sedimentary basins using information from oil industry wireline logs and drilling records. Geological Applications of Wireline Logs Geological Society Special Publication No.48, pp305-325.
- **Brown,S.R.** 1987. Fluid flow through rock joints: the effect of surface roughness. Journal of Geophysical Research. 92, p1337-1347.
- Jones, T.A., Wooten, S.A., Kaluza, T.J., 1988. Single-phase fluid flow through natural fractures: Proceeding Annual Conference Society Petroleum Engineers. Formation evaluation and reservoir geology, p687-696.

(Inserted by DNRE - Vic Govt Mines Dept)

This is an enclosure indicator page. The enclosure PE905778 is enclosed within the container PE905781 at this location in this document.

```
The enclosure PE905778 has the following characteristics:
    ITEM_BARCODE = PE905778
CONTAINER_BARCODE = PE905781
            NAME = Fracture Strike Plot, sheet 1 of 3, for
                   Gordon-1
           BASIN = OTWAY BASIN
          PERMIT = PEP/119
            TYPE = WELL
         SUBTYPE = DIAGRAM
     DESCRIPTION = Fracture Strike Plot, 1of 3, (from WCR)
                   for Gordon-1
         REMARKS =
    DATE_CREATED =
   DATE_RECEIVED =
            W_NO = W1191
       WELL_NAME = GORDON-1
      CONTRACTOR =
    CLIENT_OP_CO =
```




Figure G-1 Gordon-1 Borehole Breakout (black) and Drilling Induced Fracture (pink) strike plot. Mean strike orientation for Borehole Breakouts is 052°-232° and 144°-324° for Drilling Induced Fractures.




Figure G1-2 Gordon-1 Casterton Formation Shale bed boundary dip histogram. Mean dip orientation is 8.0°/071°.

(Inserted by DNRE - Vic Govt Mines Dept)

This is an enclosure indicator page. The enclosure PE905779 is enclosed within the container PE905781 at this location in this document.

```
The enclosure PE905779 has the following characteristics:
     ITEM_BARCODE = PE905779
CONTAINER_BARCODE = PE905781
            NAME = Fracture Strike Plot, sheet 2 of 3, for
                   Gordon-1
           BASIN = OTWAY BASIN
           PERMIT = PEP/119
            TYPE = WELL
          SUBTYPE = DIAGRAM
     DESCRIPTION = Fracture Strike Plot, 2of 3, (from WCR)
                   for Gordon-1
         REMARKS =
    DATE_CREATED =
   DATE_RECEIVED =
           W_NO = W1191
       WELL_NAME = GORDON-1
      CONTRACTOR =
    CLIENT_OP_CO =
```






Figure G1-3 Gordon-1 High Angle Conductive (HACC) natural fracture strike plot.




Figure G1-4 Gordon-1 Vertical Conductive natural fracture strike plot.

(Inserted by DNRE - Vic Govt Mines Dept)

This is an enclosure indicator page.

The enclosure PE905780 is enclosed within the container PE905781 at this location in this document.

```
The enclosure PE905780 has the following characteristics:
     ITEM_BARCODE = PE905780
CONTAINER_BARCODE = PE905781
            NAME = Fracture Strike Plot, sheet 3 of 3, for
                   Gordon-1
           BASIN = OTWAY BASIN
          PERMIT = PEP/119
            TYPE = WELL
          SUBTYPE = DIAGRAM
     DESCRIPTION = Fracture Strike Plot, 3 of 3, (from
                   WCR) for Gordon-1
         REMARKS =
    DATE_CREATED =
   DATE_RECEIVED =
            W_NO = W1191
       WELL_NAME = GORDON-1
      CONTRACTOR =
    CLIENT_OP_CO =
```




Figure G1-5 Gordon-1 Resistive natural fracture strike plot.




Figure G1-6 Gordon-1 Low Angle natural fracture strike plot.

This is an enclosure indicator page. The enclosure PE604423 is enclosed within the container PE905781 at this location in this document.

The enclosure PE604423 has the following characteristics: ITEM\_BARCODE = PE604423 CONTAINER\_BARCODE = PE905781 NAME = Scaled FMI Interpretation, 2 fo 2, (scale 1:20) for Gordon-1 BASIN = OTWAY BASIN PERMIT = PEP/119TYPE = WELL SUBTYPE = WELL\_LOG DESCRIPTION = Scaled FMI Interpretation, scale 1:20, (from WCR) for Gordon-1 REMARKS = DATE\_CREATED = 29/04/97DATE\_RECEIVED = 30/07/98  $W_NO = W1191$ WELL\_NAME = GORDON-1 CONTRACTOR = SCHLUMBERGER

(Inserted by DNRE - Vic Govt Mines Dept)

CLIENT\_OP\_CO = SANTOS LTD/CULTUS

This is an enclosure indicator page. The enclosure PE604424 is enclosed within the container PE905781 at this location in this document.

The enclosure PE604424 has the following characteristics: ITEM\_BARCODE = PE604424 CONTAINER\_BARCODE = PE905781

BASIN = OTWAY BASIN
PERMIT = PEP/119

TYPE = WELL

SUBTYPE = WELL\_LOG

DESCRIPTION = Scaled FMI Interpretation, scale 1:20, (from WCR) for Gordon-1

REMARKS =

DATE\_CREATED = 29/04/97 DATE\_RECEIVED = 30/07/98

W\_NO = W1191
WELL\_NAME = GORDON-1
CONTRACTOR = SCHLUMBERGER

CLIENT\_OP\_CO = SANTOS LTD/CULTUS

This is an enclosure indicator page. The enclosure PE604419 is enclosed within the container PE905781 at this location in this document.

The enclosure PE604419 has the following characteristics: ITEM\_BARCODE = PE604419 CONTAINER\_BARCODE = PE905781 NAME = Fracture Attribute Log, 1 of 2, for Gordon-1 (1:20) BASIN = OTWAY BASIN PERMIT = PEP/119TYPE = WELL SUBTYPE = WELL\_LOG DESCRIPTION = Fracture Attribute Log, scale 1:20, (from WCR) for Gordon-1 REMARKS =  $DATE\_CREATED = 29/04/97$ DATE\_RECEIVED = 30/07/98  $W_NO = W1191$  $WELL_NAME = GORDON-1$ CONTRACTOR = SCHLUMBERGER CLIENT\_OP\_CO = SANTOS

This is an enclosure indicator page. The enclosure PE604420 is enclosed within the container PE905781 at this location in this document.

The enclosure PE604420 has the following characteristics:

ITEM\_BARCODE = PE604420
CONTAINER\_BARCODE = PE905781

BASIN = OTWAY BASIN

PERMIT = PEP/119

TYPE = WELL

SUBTYPE = WELL\_LOG

DESCRIPTION = Fracture Attribute Log, scale 1:20,

(from WCR) for Gordon-1

REMARKS = shows different veiws to 1st Fracture

Attributed Log

DATE\_CREATED = 29/04/97

DATE\_RECEIVED = 30/07/98

 $W_NO = W1191$ 

WELL\_NAME = GORDON-1

CONTRACTOR = SCHLUMBERGER

 $CLIENT_OP_CO = SANTOS$ 

**ENCLOSURE I: 1: 200 COMPOSITE LOG** 

This is an enclosure indicator page. The enclosure PE604422 is enclosed within the container PE905781 at this location in this document.

The enclosure PE604422 has the following characteristics:

ITEM\_BARCODE = PE604422
CONTAINER\_BARCODE = PE905781

NAME = Composite Well Log for Gordon-1

BASIN = OTWAY BASIN

PERMIT = PEP/119

TYPE = WELL

SUBTYPE = COMPOSITE\_LOG

DESCRIPTION = Composite Well Log (enclosure 1 from

WCR) for Gordon-1

REMARKS =

 $DATE\_CREATED = 3/05/97$ 

DATE\_RECEIVED =

 $W_NO = W1191$ 

WELL\_NAME = GORDON-1 CONTRACTOR = SANTOS

CLIENT\_OP\_CO = SANTOS

**ENCLOSURE II: 1:500 MUDLOG** 

This is an enclosure indicator page.

The enclosure PE604421 is enclosed within the container PE905781 at this location in this document.

The enclosure PE604421 has the following characteristics:

ITEM\_BARCODE = PE604421
CONTAINER\_BARCODE = PE905781

NAME = Formation Evaluation Log /Mudlog for

Gordon-1

BASIN = OTWAY BASIN

PERMIT = PEP/119

TYPE = WELL

SUBTYPE = MUD\_LOG

DESCRIPTION = Formation Evaluation Log (enclosure 2

from WCR) for Gordon-1

REMARKS =

DATE\_CREATED = 26/04/97

DATE\_RECEIVED =

 $W_NO = W1191$ 

WELL\_NAME = GORDON-1
CONTRACTOR = HALIBURTON

CLIENT\_OP\_CO = SANTOS/CULTUS